

# PRICE BID

## PROPOSED FURNITURE WORK ON 4TH FLOOR FOR SAMB AT SBI (OLD LHO BUILDING), LAL DARWAJA, AHMEDABAD.

Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage & removing of all existing furniture items and relocating the same as per instruction by bank etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills

Sr. No.	Description	Quantity	Unit	Rate	Amount
	FURNISHING WORK				
1	TABLES				
	<u>Note : for all work stations</u>				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished				
	2) Front Apron & Sides: 1.0 mm thick Dark Laminate				
	3) Facing of Drawers: 1.00 mm thick laminate finish				
	The W.S. should have Ready Made Foot Rest. High impact polysterene with crome plated metal structure of approved make.				
	There should be provision for cable manager(Metal Cable Manager) system with necessary cutouts in top surface				
	<u>C.P.U. trolly with castors/roller supports/ Nylon castors.</u>				
	Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete				
	Heavy duty <u>telescopic full extension</u> sliding channel of approved make shall be used in all drawers.				
1A	DGMTABLE SIZE: 8'-0" X 3'-0" X2'-6" HT. with Laninate finish on Table Top , sides and all other visible surfaces etc complete as follows	1.00	NO		
	Supplying and installation of Table as per the following description : Size 8'-0" x 3'-0". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Drawers of size of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Ready made metal Key board with mouse pad of approved make shall be provided. Exposed surfaces of darwers shall have laminate, All internal surface will have 0.60 mm thick balacing laminate				
	Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing				
	Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.				

	Drawer ( 3 numbers of drawers in each drawer box) Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with lacquer polished etc complete as directed.				
	Table shall have stand for keeping CPU and metallic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.				
	All the surface without laminate / balancing laminate shall be lacquered polished of approved shade				
	As per drawing and instruction of Architect/Bank work to be Completed (FOR DETAILS REFER DRG. NO- )				
1B	Same as above Item-no-2 but Size: 6'-0"x3'-0" with 3 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	7.00	NO		
1C	Same as above Item-no-2 but Size: 5'-0"x2'-6" with 3 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	1.00	NO		
2	CONFERENCE/MEETING ROOM TABLE	7.70	SQ MT		
	Supplying and installation of conference Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. [ Only Top shall be measured for payment purpose.]				
3	SIDE CREDENZA (SIDE TABLE)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) Front Apron & Sides: Frosty White Laminate				
	Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. ( For BM & Officer's) Rate for length Less then 3'-3"	4.00	SQ.MT		

	Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balancing laminate				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
4	DRAWER BOX (PEDESTAL WITH 3 DRAWERS)	23.00	NOS		
	Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laquer polished etc complete as directed.				
5	STORAGE CABINET with Top & Front laminate finished. Storage of any height	4.00	SQMT		
	Same as above Item No-7, but all external surfaces to be finished with Laminate (approved shades)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pillshade				
	2) Front Apron & Sides: Dark Laminate/Frosty white Laminate as per design & instructions				
8	FULL HEIGHT PARTITION WORK				
	P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR	10.50	SQMT		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.[REFER DRG NO- ]				
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.				

9	FALSE CEILING WORK				
	P/F GYPSUM BOARD FALSE CEILING	22.00	SMT		
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA ( Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.				
	Note : (1) Rate includes dismantalling of existing GYPSUM/ AMF/ POP false ceiling including stacking of servicable materials & disposal of unservicable materials & making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMT and paid in SqM (3) Only finished visible surface area shall be measured for payment.				
10	Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid	25.00	SMT		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				
	Rate includes dismentalling of existing Mineral fibre ceiling.				
11	Providing and Fixing of Armstrong Mineral Fibre Accoustical FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid in the existing structure of the ceiling.	360.00	NOS.		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles.				
	Rate includes removing of existing Mineral fibre grid tiles				
12	Providing & Supplying Sofas, Sofa chairs of various types & categories (Single seater, Two seater & Three seater) etc complete as per the manufacturers specifications as mentioned below. The rights to select & approve the sofas & seating shall vest with the clients. The contractor shall submit brochures of manufacturer at the time of quoting for this item etc complete as per layout. The consultants reserve the right to select the sofas in line with the technical specifications envisaged & meeting the specifications standards expected. (Approved makes: Godrej / Durian / Featherlite)				

A	Two seater sofa	7.00	Nos.		
B	Three seater sofa	3.00	Nos.		
13	Center Table (3'-0" X 2'-0" Oval / Rectangular)	2.00	Nos.		
	Providing and supplying in position oval or rectangular centre table to be made out of 2" X 2" teakwood frame including 12mm thk clear glass top with bevelled edges including bottom glass shelf with etching etc complete. The rate shall also include SS lining design to the teakwood frames including all the necessary hardware, fittings, fixtures as per manufacturers specifications complete.				
14	Corner table same as above but size of 2'-0" X 2'-0" (Square)	4.00	Nos.		
15	Roller Blinds	55.00	Sq.m.		
	Providing, fabricating and fixing vertical roller blinds of approved make preferably of "Vista Levelor" with a woven made acrylic coated fabric of 100% polyester of thickness 0.50 – 0.60 mm ( +/- 5% tolerance) with the main properties like resistance to Cracking & Fraying, dust repellence, UV proof and virtually maintenance free along with the Vista accessories of like Head rail , Roller tube Idler, Bottom rail, chain, matching colour installation brackets etc. including all fixtures and fittings of Vista like Rainbow curtain rods with electric resistance welded MS pipe having a corrugated virgin PVC extrusions reinforced to minimize friction, finials and along with standard anchoring arrangements etc. all complete done in workmanlike manner as per the approved design, colour and including necessary scaffolding as directed.				
16	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)	600	SMT		
	Providing and applying (with rollers only) Acrylic emulsion paint of required shed and approved make on new/old work in two or more coats to give an even shed including the preparation of surface for painting, applying FULL primer and putty, at all heights complete as per manufacturer's specification and as directed.				
17	P/A SYNTHETIC ENAMEL PAINT	110	SMT		
	Providing and applying synthetic enamel paint, at all heights of required shade and approved make on old work including the scrapping/cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.				

	MISCELLANEOUS				
18	P/F GRANITE WINDOW SILL/JAMBS	2.50	SMT		
	Removing old wooden door frame & door shutter and Providing and laying Polished Granite stone frame in required design and patterns, in linear as per the architectural drawings with 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent. (Basic price of slab shall be Rs.1700=00 Per Sqmt) (No scaffolding work required) Rate shall include the fixing of door shutter.				
19	Replacing broken glass in MS window with new float glass panes of 5 mm thickness including fixing with necessary putty/wooden beading/MS flat etc. complete.	20.00	sq.m.		
20	Providing 8mm float glass for table top.	15.00	sq.m.		
<b>TOTAL COST</b>					
	NOTE:				
[a]	In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this.				
[b]	All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balancing laminate of approved make & shade in the all S.W Counters/Tables/ Credenza, Storage Cup Board etc.				