D Part D : Air Conditioning Works : Supply, installation, testing and commissioning of following AIR CONDIRIONERS as under. The Rate shall be inclusive of all taxes excluding GST. GST will be paid additionally by the Bank as applicable subject to GST Number. and system has complete one year warranty & If any additinal warranty provided by company/vendor in any specific part like compressor etc that is acceptable, please mentioned it. 1 Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC FIVER* STAR INVERTER RATING OF BEE AIR CONDITIONERS 1.50 TON Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with	Qty	Unit	Rate	Amount
 Supply, installation, testing and commissioning of following AIR CONDIRIONERS as under. The Rate shall be inclusive of all taxes excluding GST. GST will be paid additionally by the Bank as applicable subject to GST Number. and system has complete one year warranty & If any additinal warranty provided by company/vendor in any specific part like compressor etc that is acceptable, please mentioned it. Supply, installation, testing and commissioning of Higher Efficient models of <u>SPLIT AC FIVER*</u> <u>STAR INVERTER RATING OF BEE AIR CONDITIONERS 1.50 TON</u> Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with 				
Efficient models of <u>SPLIT</u> <u>AC</u> <u>FIVER*</u> <u>STAR</u> <u>INVERTER</u> <u>RATING OF BEE AIR CONDITIONERS</u> <u>1.50</u> <u>TON</u> Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with				
suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 3 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should have LED display. The rates inclusive of all repairs of civil and carpentry work The cost includes original fill and additional top up of refrigerant gas as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only	8	Nos		

	2			
2	Supply, installation, testing and commissioning of Higher			
	Efficient models of <u>SPLIT</u> <u>AC</u> <u>FIVER*</u> <u>STAR</u> <u>INVERTER</u>			
	RATING OF BEE AIR CONDITIONERS 2.0 TON Machines			
	confirming to latest Indian Standards and suitable for operation			
	on 230 Volts + 10 %, single Phase, 50 Hz AC supply with			
	rotary compressor, Refrigerant and capable to perform			
	cooling, dehumidifying, Air Circulating, auto mode, auto swing,			
	anti bacteria filtering, ventilation and with remote control with			
	Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with			
	suitable thermostat. The rate should include installation			
	charges after making appropriate changes in existing false			
	ceiling. Heavy ready made/fabricated M S Stand to house the			
	out door unit as per site conditions including carpentry work,			
	minor civil work and material including copper piping of hard &			
	prime quality of min. 22 G upto 3 metres with class "o" Nitrile			
	insulation 12mm, cabling from indoor to outdoor unit, heavy			
	gauge PVC drain piping with insulation as per site requirement.			
	The copper piping, drains piping and electrical cabling should			
	be fixed with clamps and no loose piping/cabling is allowed.			
	The out door unit should be anti-rust powder coated. Indoor			
	unit should have LED display. The rates inclusive of all repairs			
	of civil and carpentry work The cost includes original fill and			
	additional top up of refrigerant gas as per site condition. The			
	rate inclusive of all chisel work, plastering, finishing, painting &	•	NI	
	all civil related work portaing to montioned work	2	Nos	
3	Supply, installation, testing and commissioning of Higher			
	Efficient models of <u>CASSETTE</u> <u>A.C.</u> <u>FIVER*</u> <u>STAR</u> <u>OF</u> <u>AIR</u>			
	<u>CONDITIONERS</u> <u>3.0</u> <u>TON</u> Machines confirming to latest			
	Indian Standards and suitable for operation on 415 Volts + 10			
	%, three Phase, 50 Hz AC supply with Scroll compressor,			
	Refrigerant and capable to perform cooling, dehumidifying, Air			
	Circulating, auto mode, auto swing, anti bacteria filtering,			
	ventilation and with remote control with Cool/Fan/Dry/Auto			
	mode, sleep mode & on/off timer with suitable thermostat. The			
	rate should include installation charges after making			
	appropriate changes in existing false ceiling. Heavy ready			
	made/fabricated M S Stand to house the out door unit as per			
	site conditions including carpentry work, minor civil work and			
	cabling from indoor to outdoor unit, heavy gauge PVC drain			
	piping with insulation as per site requirement. The copper			
	piping, drains piping and electrical cabling should be fixed with			
	clamps and no loose piping/cabling is allowed. The rates			
	inclusive of all repairs of civil and carpentry work The out door			
	unit should be anti-rust powder coated. The cost includes			
	original fill and additional top up of refrigerant gas as per site			
	condition. The rate inclusive of all chisel work, plastering,	8	Nos	
	finishing, painting & all civil related work pertaing to mentioned	0	INUS	
	Cupply and installation of east 9 prime mustice of min. 00.0			
4	Supply and installation of soft & prime quality of min. 22 G			
	Copper pipe for "Split AC only" with class "o" Nitrile insulation			
	of minimum 12mm for split air conditioner including inter			
	connection power/ communication cable between indoor &			
	outdoor unit as per site requirement. (If required additionally,			
	payment will made as per actual installtion. The rate inclusive			
	of all chisel work, plastering, finishing, painting & all civil related			
	work pertaing to mentioned work. Make of Insulation:-			
	Superion/Aflex/Armacell/Kflex Make of cable:-			
	Finolex/RR/Havells	50	Mtr	
		50	ivid	

5	Supply and installation of hard & prime quality of min. <u>22 G</u> <u>Copper pipe</u> <u>f</u> or "Cassette AC Only" with class "o" Nitrile insulation of minimum 12 mm for 3 / 4 ton cassette type air conditioner including interconnection power/ communi cation cable between indoor and outdoor unit as per site requirement.(If required additionally, payment will made as per actual installtion.) The rate inclusive of all chisel work,				
	plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:-				
	Superion/Aflex/Armacell/Kflex . Make of cable:Finolex/RR	100	Mtr		
6	Drain Pipe (If Required additional) Applicale to both ACs(Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. (If required additionally, payment will made as per actual installtion.) Make:- Kasta/supreme		Mtr		
	Sub Total : Part D (Air Conditioning Works)				
	Total : Part (D)				
	TOTAL				
	Note:- The rates quoted includes all other taxes,duties, loading, unloading,transportation,other expenses etc to site.			L	
	GST will be paid additionally as applicable				
					
		Seal & Signature of Contractor			
	J				