

### Upgradation of seating arrangement at 5th floor SBI GITC

Sr. No.	Perticular	Quantity	Unit	Rate	Amount
1	Carefully removing existing table & furniture & cleaning debris from the site out of Banks premises.	1	Job		
2	Providing & Fixing new low height partition with Aluminium frame covered by 8 mm ply from both side, and surface finished with both side laminate, matched with existing surrounding after approval of shade from the Bank, along with wooden moulding at the top with suitable polish work complete as per site conditions and instructions of the Bank.	200	Sft		
3	Providing, supplying and fixing new wooden tables of size 4'6" x 2' x 2'6" made out of 18 mm thick commercial Ply finished with 1mm thick laminate of approved shade & make, polishing etc. complete as per the existing design, cable managers, keyboard tray, CPU stand as per the requirement and instruction of Bank.	10	No		
4	Providing, supplying and fixing side storage of size 3' x 1'6" X 2' 6" made out of 18 mm thick commercial Ply Confirming IS 303 finished with 1mm thick laminate of approved shade & make, complete as per the existing design, site condition and instruction of Bank.	400	sft		
5	Providing & fixing new laminate over existing storage to match with existing surrounding rates are inclusive of material, wood, adhesive glue with cutting to match with existing surrounding etc complete	300	Sft		
6	Providing and fixing hardware material for refurbishing of the storage unit, table drawer etc. complete as per site conditions and instructions of the Bank:				
a	3 " hinges	60	Nos		
b	Drawer channel	20	Nos		
c	Multi purpose lock	45	Nos		
d	4" handle	40	Nos		
e	Magnet Stopper	45	Nos		
7	Providing and fixing in position running counter of 600 mm wide to be made out of 19 mm thick ply (confirming to IS 303) the vertical support at every 2'11" All the exposed surfaces of the counter shall finished with approved make/colour/pattern of 1mm thick laminate with approved colour as per surrounding area, rates are inclusive of necessary hardware, keyboard tray, cable manager etc to complete the work as per site conditions and instruction of the Bank.	100	Rft		
8	Providing and fixing double charged vitrified tiles of Kajaria, Johnson, etc. make (size 600 mm x 600 mm) flooring matching with existing flooring in cement sand mortar (1:4) bedding including removal of existing damaged flooring, debris etc. from site as per directions of the Bank	160	sft		
9	Providing and applying one or more coat plastic paint to walls and ceiling after suitable surface preparation leveling with putty, POP etc. complete the work as per site conditions & instructions of the Bank	1000	sft		
<b>Total:</b>					

\*GST will be paid extra as applicable