

PRICE BID FOR PAINTING WORKS AT CANTEEN BUILDING OF LHO, POOJAPPURA

Sl. No.	Qty.	Description	Unit	Rate Excl. GST	Amount(Rs.)
1	2400.00	Painting the wall with one coat primer and 2 coat of exterior grade plastic emulsion paint after preparation of the surface after scrubbing and cleaning including all staging work etc complete. Approved make of paint: Asian, Berger, Nerolac - Upto 13.00 m Height	Sq. M		
2	80.00	Filling all the surface cracks of more than 2mm and upto 5mm depth in walls with FOSROC DECOFILL after making grooves and cleaning the joints, including staging work upto 13.00 m Height	RM		
3	35.00	Carefully chipping and removing the existing plaster to the walls so as to receive new plaster/ dado etc., and apply modified styrene butadiene latex like Dr. Fixit pidicrete URP , Nitabond etc apply to the brick/ concrete surface with two coat as per manufactures specification at an interval of six hours and apply 15 to 20mm thick (average) cement plaster in CM 1:4 (1 part of cement and 4 parts of sand) mix to walls add liquid water proof in cement mortar 200mi for 50kg as directed by the Engineer in charge,including staging work upto 13.00 m Height.	Sq. M		
		Total			

GST @ 18% EXTRA