## NAME OF WORK : PRICE BID OF FURNISHING WORK OF BRANCH & ATM FOR STATE BANK OF INDIA BRANCH AT LANJ (H.P.)

	PART -A (INTERIOR WORKS)				
S.N	Item of Work	Qty	Unit	Rate	Total Amount
1 (a)	Main Entrance ,BM Chamber & ATM's Doors	70	Sq.Ft		
	<b>(Toughened Glass 12.0 mm thk. with etching )</b> Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf /Double leaf glazed Toughened door of size approximately, 4'-0" to 3'-0"X 7'-0" all sides edge grinded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fitting etc. the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant where ever required and SS cover over patch fittings to accommodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete of godrej / dorma. the rate shall be include frosted film / logo all inclusive, complete in all respect. (Note: In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of Glazing payable will be below the false ceiling only).				
(b)	<b>12mm clear float toughened Glass partition :-</b> Providing and fixing in position 12mm clear float toughened Glass partition with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughen the same. The cost to include all hardware (PATCH FITTINGS etc) required of <b>Ozone/EBCO/GODREJ o</b> r approved equivalent make viz., single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge, along with frosted film as per design and drawing. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed.The cost to include the cost of bevelling and smoothening of the exposed edges of the glass.		Sq.Ft		

			1	
2	WALL PANELLING :- Wall paneling to be providing in Banking hall	750	Sq.Ft	
	made from aluminum frame work using aluminum sections of 50 mm			
	X 25 mm - 18 gauge section un anodized Aluminum of Jindal/ Indal			
	make work Properly fixed to the Wall or Column with proper Spirit			
	level. Frame work to be covered with 8mm thick Plywood of BWR			
	grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated			
	) of century, green make and 1 mm Thick laminate as per color			
	scheme of the bank. 35mmX 12mm steam beach Lipping to be			
	provided to all the edges Complete job including melamine polish on			
	edge beading/Cornices etc. and painting of grooves in approved			
	colour. All job to be done as per architects satisfaction/ bank			
	direction .			
	BANKING HALL:- Wall paneling Ht : 4'-6", Centre pillars to be			
	cladded upto ceiling bottom "(i.e. + 9'-0 level)			
	(Note: the area under storage or table, side credenza shall not be			
	counted in wall paneling, only visible area will be payable).			
3(a	FULL HEIGHT SOLID PARTITIONS:- Providing and fixing full height	110	Sq.Ft	
010	partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded		59.1 0	
	sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom			
	member shall be aluminum extruded sections of size 65 mm X 44 mm			
	X 16 Gauge. The aluminum extruded sections frame shall be fixed			
	rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8			
	mm thick Ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer			
	proof, chemically treated ) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank.doors with lock is to be			
	providing as per drawing and fixed with Steam beach molding duly melamine polished/paint. 35mm X 12mm steam beach Lipping to be			
	provided to all the edges of the door. All wood to be painted in wood			
	preservative. The rate include making provision for electrical			
b)	conduits and switch boxes. All job to be done as per architects FULL HEIGHT PARTLY GLAZED PARTITIONS:- Providing and fixing full	170	Sq.Ft	
,	height partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded	170	зү.гі	
	sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom			
	member shall be aluminum extruded sections of size 65 mm X 44 mm			
	X 16 Gauge. The aluminum extruded sections frame shall be fixed			
	rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8			
	mm thick Ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer			
	proof, chemically treated ) and 1 mm Thick laminate shall be fixed on			
	both sides as per color scheme of the bank.Glass (10mm thick) with			
	frosted film as per design and doors with lock is to be providing as per			
	drawing and fixed with Steam beach molding duly melamine			
	polished/paint. 35mm X 12mm steam beach Lipping to be provided to			
	all the edges of the door. All wood to be painted in wood			
	preservative. The rate include making provision for electrical			
	conduits and switch boxes. All job to be done as per architects			
	satisfaction/ bank direction . Note: (In case of false ceiling, the vertical			

c) LOW HT. PARTITION FOR COUNTER SEPARATION: Providing and fixed low height partitions made of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the	t
aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm	
horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm	
sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm	
sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm	
rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm	
phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm	
bank.12mm thick glass to be provided on the Top of Partition. Teak	
wood beading 1 ½ " X 3 ¼" (melamine polished ) around partition	
edges complete in all respects, height : 4'-0"	
d) 12 MM thk. toughend glass for Banking / SWO Counters with 50 Sq.F	t
Etching front & Sides.: Providing and fixing 12 mm thick, clear plain	
toughened glass of fixed in vertical position at counter level & to side	
partitions with frosted film as per drawing, the counter top glass fixed	
on both sides to toughened glass partitions & side partitions fixed to	
wooden partition with superior quality stainless steel L - shaped	
clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole	
at the bottom for transaction shall be provided. All the edges of the	
glass shall be grinded and polished complete in all respects.	
4 Hardware	
a Providing and fixing of Godrej /Harrison night latches in cash cabin 1 Nos	
doors as per the directions of the Bank.	
/Ozone/Hettich/ Dorma) in UPS, Record Room, etc. as per the directions of the Bank.	
c Providing and fixing hydraulic door closures Silver colour of approved 6 Nos	
make(Godrej /Ozone/Hettich/ Dorma) & color.	
5 Single Level SWO Counters : 14 R.Ft	
Providing and fixing at site SWO counters each upto4'-6"/ 5'0" long, 2'6" high	
and 3'0" wide, as per design and drawing. SWO counters to be made of 19	
mm thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer	
proof, chemically treated) with 40 mm X 12 mm thick teak wood beading	
required all around, as per drawing. Provision for 3" dia. round / 3" square	
cable manager for computer / electrical cables at appropriate place will be	
made in the top surface of the counter. The top with Curvilinear profile shall	
be made out of 19mm thk. Comm. ply BWR grade IS 303 and finished with	
6mm thk. flexi ply as base & 1 mm thick laminate over there as per design	
,acrylic sheet with provision for LED Light in bottom. Teak wood lipping will	
be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray	
of size 600 X 270 finished with laminate on top side with back support, of	
EBCO make fixed on channels, as per manufacturer's instructions /	
specifications.	
Three drawers with autolock running on both sides mounting Telescopic	
(channels) of EBCO make, made of 19 mm thick commercial ply with 1 mm	
thick laminate on front face and drawer locks to be provided on one side of	
the counter as per layout. The sides of the drawers shall be made of 12 mm	
thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick	
commercial ply. Non Visible / Inside surface i.e. inside leg-space of table,	
inside drawers shall be finsihed with 0.7mm thick laminated white /off	
white. All exposed Teakwood edges / teak wood lipping beading shall be	
Spray painted Satin Enamel paint or spirit (natural) polish as required. The	
Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter	

		110	а <u>г</u> .	
6	Low storage unit :-	110	Sq.Ft	
	Providing storage unit of size 18"'x2'-6" & 18" x 3'-6" (W x H) of ¾"			
	thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P.,			
	borer proof, chemically treated ) with 1.0mm thick horizontal			
	laminate and 1.0mm thick vertical laminate having one shelf in			
	center. The storage unit will have all necessary hardware, laminate			
	band and teakwood/ partal wood beading ¾ ″X ½″/ moulding.			
	Recessed skirting (3/4") finished with 1.0mm thick laminate is			
	present. Clip hinges ( dadoo kabzaa ) to be used for fixing storage unit			
	shutters. All inside surfaces are finished with 0.7mm thick laminated			
	and beading/moulding shall be paint/polish .the work to be done			
	complete in all respects.			
a)	STORAGE UNDER PANTRY PLATFORM:- Providing storage of size 2'-	21	Sq.Ft	
	0" x 2'-9" (WXH) under pantry plateform made with $\frac{3}{4}$ " thick			
	commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer			
	proof, chemically treated ) with 1.0mm thick horizontal laminate and			
	1.0mm thick vertical laminate having one shelf in center, rest of the			
1	specification as per item no-7.			
	<b>OVER HEAD STORAGE:-</b> Providing storage of size 16" x 2'-3" (WXH) of	25	Sq.Ft	
	<sup>3</sup> / <sub>4</sub> " commercial Ply BWR grade IS 303 ( phenol bonded, B.W.P., borer			
	proof, chemically treated )with 1.0mm thick horizontal and vertical			
	laminate having one shelf in center. Top portion of storage shall be			
	tapered with 3". Cedar wood lipping $\frac{3}{4}$ " X $\frac{1}{2}$ " is provided at edge.			
	Open able shutter with clip hinges ( etching colour ), ball catchers,			
	multi purpose locks(approved make) are to be provided. All inside			
	surfaces are finished with 0.7mm thick laminated and			
	beading/moulding shall be paint/polish. All work is done complete in			
	all respects to architects satisfaction & as per colour scheme of bank.			
	The storage unit is properly fixed to wall at+ 5'-9". concealed tube			
	lights ( 3 Nos. ) to be provided along with electrical wires and			
	connections (Note : Electrical fittings given separately in electrical			
8	Wooden boxing for electrical panel: Providing Cabinet unit of size	50	С ~ Г+	
•	$18'''x8'-6''$ (W x H) of $\frac{3}{4}''$ thick commercial ply BWR grade IS 303 (	50	Sq.Ft	
	phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0mm			
	thick horizontal laminate.8mm thick bison panel board back side			
	alongwith wall. The storage unit will have all necessary hardware,			
	decorative jalli pattern laminate band and teakwood/ partal wood			
	beading / moulding. Recessed skirting (3/4") finished with 1.0mm			
	thick laminate is present. Clip hinges ( dadoo kabzaa ) to be used for			
	fixing storage unit shutters. All work to be done complete in all			
	respects			
	<b>Full height storage unit :</b> Providing storage unit of size 18"'x9'-0" (W	200	Sq.Ft	
	x H) of ¾" thick commercial ply BWR grade IS 303 ( phenol bonded,			
	B.W.P., borer proof, chemically treated ) with 1.0mm thick horizontal			
	laminate and 1.0mm thick vertical laminate having shelves @1'-3"			
	C/C. The storage unit will have all necessary hardware, decorative jalli			
	pattern laminate band and teakwood/ partal wood beading /			
	moulding. Recessed skirting (3/4") finished with 1.0mm thick			
	laminate is present. Clip hinges ( dadoo kabzaa ) to be used for fixing			
	storage unit shutters. All inside surfaces are finished with 0.7mm			
	thick laminated and beading/moulding shall be paint/polish. All work			
	is done complete in all respects. All work to be done complete in all			
	respects.			 
10	FALSE CEILING:-			 

a	Providing and fixing Gypsum board false ceiling in levels as per the detailed drawing - made up of G.I. frames as specified by Gypsum India limited and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200c/c, and ceiling section at 457mm c/c.the work includes finishing of joints, applying primer, two or more coats of plastic emulsion paints (white colour), making cut-out for light fixtures, etc. providing of perimeter channels / beading etc. complete in all respect. <b>Note: Provision of cove shall be given as mentioned in drawings.</b>	940	Sq.Ft	
b	Providing and fixing <b>Teak wood Vinear false ceiling</b> in levels as per the detailed drawing - made up of G.I. frames as specified by Gypsum India limited and Frame work to be covered with <b>4 mm thick Vinear</b> <b>over 8mm thick Plywood of BWR grade IS 303</b> (phenol bonded, B.W.P., borer proof, chemically treated ) of century, green make and 1 mm Thick laminate as per color scheme suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200c/c, and ceiling section at 457mm c/c. 35mmX 12mm steam beach Lipping to be provided to all the edges Complete job including melamine polish on edge beading/Cornices etc. and painting of grooves in approved colour. All job to be done as per architects satisfaction/ bank direction the work includes making cut-out for light fixtures, etc. complete in all respect. <b>Note: Provision of cove shall be given as mentioned in drawings.</b>		Sq.Ft	
C	Providing and fixing of false ceilings at all heights of 600 mm x 600 mm x 16 mm <b>ARMSTRONG Mineral Fibre ceiling tiles</b> of type Prima Dune Premier-Beveled Tegular Edge RH-99 laid on 15mm exposed grid system. The suspension system shall be the <b>Armstrong Trulok Silhouette</b> revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions. The framework comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjusters and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 x 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200m cross tees and making arrangement for light fixtures, etc. complete in all respect.	444	Sq.Ft	

			, , , , , , , , , , , , , , , , , , ,	[]
11	<b>Manager's table :-</b> Providing Table for Manager (Size5'-6" x 3'-0"		Nos	
	x2'-6") of 1½" thick Tops & $3\!\!\!4$ " thick commercial ply BWR grade IS			
	303 ( phenol bonded, B.W.P., borer proof, chemically treated )			
	finished with 1.0mm thick horizontal and 1.0mm thick vertical			
	laminate of specified colour and make. 12mm thick bevelled glass			
	(approved make) of same size is placed with edges covered with			
	partal wood beading. Drawer unit ( drawer size: 1'-1" x 1'-6" x6",			
	3Nos. ) is located on one side with proper sliding arrangement and			
	auto lock are provided along with storage unit. The counter will have			
	all necessary hardware, laminate band and teakwood/ partal wood			
	beading 1 $\%$ " X $\%$ " / moulding. Recessed skirting ( $\%$ ") finished with			
	1.0mm thick laminate is present below the counter. In front, apron of			
	3/4 " board ( laminate finished ) is provided. Keyboard drawer. CPU			
	shelf 12" x 18" & footrest 3" x 1 $\frac{1}{2}$ " etc. to be provided. Laminate			
	colour combination scheme with beading to be followed.All inside			
	surfaces are finished with 0.7mm thick laminated and			
	beading/moulding shall be paint/polish. All work is to be done			
	complete in all respects.			
	Officer's table :-	1	Nos	
	Providing Table for Officer's tables(Size4'-6" x 2'-6" x2'-6" ) rest			
	specification as per Item No-11.			
13	Side credenza : :- Providing and placing side rack(Size 3'-6" x 2'-3"	2	Nos	
	$x1'-4''$ ) made of $\frac{3}{4}''$ thick ply BWR grade IS 303 ( phenol bonded,	-		
	B.W.P., borer proof, chemically treated )finished with 1.0mm thick			
	horizontal laminate. 4 Drawers (Size 1'-1" x 1'-3" x 4") of $\frac{3}{4}$ " board			
	are placed below. Remaining portion has 2 shutters with 1 shelf.			
	Laminated colour combination scheme to be followed. All necessary			
	hardware eg hinges, screws, multipurpose locks, stoppers, drawer			
	slides, ball catchers to be provided along with teakwood / partal			
	wood beading/ moulding .All inside surfaces are finished with 0.7mm			
	thick laminated and beading/moulding shall be paint/polish .All works			
	to be done complete in all respects.			
		4	N 1 -	
	Writing desk / Customer Voucher Stand / Forms Stand including	1	No	
	Cheque Drop & Suggestion Box with 1½" thick Tops :-Providing and			
	fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3nos. storage units			
	of forms with 12 mm glass top fixed with 3" SS spacer. Space for			
	housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on			
	the top and on side (L-shaped, wall hung) including provision of 2 Nos			
	Cheque Drop & 1 no Suggestion Box made of 19 mm thick			
	commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer			
	proof, chemically treated ) with 1.0 mm thick laminate to be fixed and			
	<sup>3</sup> / <sub>4</sub> " x <sup>1</sup> / <sub>4</sub> " teak wood lipping on two visible sides on it All exposed Teak			
	wood edges / teak wood lipping / beading shall be spirit polished with			
	matching pigment. All inside surfaces are finished with 0.7mm thick			
	laminated and beading/moulding shall be paint/polish & to be fixed			
	on the wall cost of spacers etc. all inclucive complete.			
a)	Writing desk / Customer Voucher Stand / Forms Stand in ATM	1	No	
	including Cheque Drop & Suggestion Box with 1½" thick Tops :-			
	Providing and fixing forms stand of size 3'-0" X 1'-6" X 3'-9" with 3nos.			

15	CIDE TABLE . Drowiding and placing side table of size $2^{\prime} 0^{\prime} + 2^{\prime} 0^{\prime} + 4^{\prime}$	10	Nec	
15	SIDE TABLE :- Providing and placing side table of size 2'-0" x 2'-0" x 1'-	10	Nos	
	6" made with 2" x 2" teakwood frame melamine polished with			
	decorative $2 \frac{1}{2}$ x $1 \frac{1}{2}$ " beading along with 12mm thick Glass on the			
	top. All inside surfaces are painted with 2 coats of synthetic enamel			
	paint over coat of wood primer .All work is done complete in all			
	respects to architects / bank managements satisfactory .			
16	Dismental of existing door with frame and Providing and fixing Fire	21	Sq.Ft.	
	Resistant Door -Fire rated steel door including frame Hrs Metal test			
	certificate will be provided issued from			
	GQMC. (Kutty flush doors & furniture co. Pvt ltd.paonta sahib, distt.			
	Sirmour,H.P. & GMT, Baddi)			
	Frame - Providing and fixing fire resistant door frame of section 100 x			
	50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly			
	powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm			
	/ sqm ) duly filled with vermiculite based concrete mix, suitable for			
	mounting 120 minutes fire rated door shutters. The frame is fitted			
	with intumuscent fire seal strip of size 10 x 4 mm (minimum) around			
	the frame and fixing with dash fastener of approved size and make,			
	including apply a coat of approved brand fire resistant primer etc.			
	complete as per direction of Engineer – in charge (including Dash			
	fasteners).			
	Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up			
	of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120			
	minutes fire rating conforming to IS : 3614 (Part – II), tested and			
	certified as per laboratory approved by Engineer – in – charge, with			
	suitable mounting on door frame, the entire shutter filled insulation			
	material / Honeycomb craft paper of 160gsm (zinc coating not less			
	than 120 gm/m2) and fixing with necessary stainless steel ball bearing			
	hinges of approved make, provision of Fire Rated Wired Glass size of			
	glass 300 X 200 including applying a coat of approved fire resistant			
	primer etc. all complete as per direction of Engineer – in			
	charge (paneling to be paid for separately). Hardware for fixing - Fire			
	rated steel door including frame. Providing and fixing following			
17	<b>TEXTURE PAINT:</b> Ground Floor walls to be finished with texture paint	1150	Sq.Ft	
	of approved make (Rustic) above 4'-6" upto ceiling bottom including			
	scaffolding, cleaning & supply of all materials.			
18	Panelling With ACP(Exterior Grade ) / Aluminium Composite Panels	270	Sq.Ft	
	(With Aluminium Frames) Supplying & fixing 4mm thick Aluminum			
	component sheet of approved make and shade including making of			
	ground of (1"X2") aluminum hollow section as per design ,with 6mm-			
	19mm wide vertical or horizontal groove finished with Dow Cowing			
	sealant (789) as per Architect's drawings & instructions aluminum			
	componenet sheet should be of virgin grade and having aluminum			
	profile thickness of 0.5 mm on both sides of core. The rate is inclusive			
	of all fixtures and fittings (with sealent) for proper finish. The works			
	includes front face shutter boxing complete. the rate includes all			
	required shuttering, scafoulding, labour, material, complete			

19	Panelling With ACP (Interior Grade ) / Aluminium Composite Panels	170	Sq.Ft	
1.9		170	Sy.Fl	
	(With Aluminium Frames) Supplying & fixing 4mm thick Aluminum			
	component sheet of approved make and shade including making of			
	ground of (1"X2") aluminum hollow section as per design ,with 6mm-			
	19mm wide vertical or horizontal groove finished with Dow Cowing			
	sealant (789) as per Architect's drawings & instructions aluminum			
	componenet sheet should be of virgin grade and having aluminum			
	profile thickness of 0.5 mm on both sides of core. The rate is inclusive			
	of all fixtures and fittings (with sealent) for proper finish. The rate			
	includes all required shuttering, scafoulding, labour, material,			
	complete			
a)	ACP partition and door with ACP sheet on both sides inclusive of all	90	Sq.Ft	
-	hardware like lock.handle etc. and fittings .	50	59.10	
	<b>TROPHY CASE</b> :-Providing and fixing trophy case using <sup>3</sup> / <sub>4</sub> " thick	20	Sq. ft.	
20		20	эч. п.	
	commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer			
	proof, chemically treated ) of century, green, Archid ply makewith			
	1.0mm thick horizontal laminate and 1.0mm thick vertical lamina			
	TOTAL OF PART-A (INTERIOR WORKS)			
	DISCOUNT(IF ANY)			
	G.TOTAL			
	GST Extra as applicable.			

(IN WORDS) RS

NAME OF CONTRACTOR:

ADDRESS OF CONRACTOR: