

STATE BANK OF INDIA
ADMINISTRATIVE OFFICE, DURGAPUR

SCHEDULE OF WORKS : CIVIL WORKS AT SME PURULIA BRANCH

PROJECT : CIVIL WORKS AT SME PURULIA BRANCH
UNDER RBO PURULIA (REGION – VI)

2	Providing and erecting Brickwork: The brickwork shall be executed with 1st class bricks only, unless mentioned otherwise. All bricks are to be made saturated with surface dry by dipping into potable water for at least 24 hours before using. Also, scaffolding and staging are to be done wherever necessary. The work is to include all necessary materials, accessories, labour, tools & tackles. All materials should be approved by the Bank. Executed volume of brickwork is to be measured for finished work. The job is to be done with cement-sand mortar as below –				
a	In superstructure in upper floors (5" thick) at Toilets & Kitchen room (mix proportion of mortar = 1 : 4 or 1 : 6)	SQ MT	14.00		
b	Providing & erecting of 10" thick brickwork (For Vault Room)	CUM	6.00		
3	Providing & erecting RCC lintel on brick all	CUM	2.00		
4	Providing and applying Plastering Work: Plastering shall be applied to walls, ceiling, columns, beams, etc. or any other surface as directed and as per design. The job is to be finished with rounding off or chamfering corners as directed. The work includes raking out joints along with throating, nosing and drip course as required. Also, scaffolding and staging are to be done wherever necessary. The work is to include all necessary materials, accessories, labour, tools & tackles. All materials should be approved by the Bank. Executed plastered area is to be measured for finished work. The job is to be done with cement-sand mortar as below –	Square Metre	88.00		
5	Providing and fixing MS Collapsible gate with necessary men & materials.	Square Metre	5.85		
6	Providing and fixing MS Rolling Shutter with necessary men & materials.	Square	6.00		
B. PAINTING RELATED JOBS					
1	Supply & applying wall putty Providing & applying WALL PUTTY: Providing and applying powder form wall putty (interior grade) of Biral/Asian/Berger or equivalent as approved by Engineer in Charge on wall surfaces including preparation of plastered surfaces (making good of uneven plaster with plaster of paris mixed with water, sand papering, cleaning). The thickness of putty will be of Minimum 2 mm average. The work shall be done to the satisfaction of bank as per manufacturer's specifications etc complete in all respect.	Sq mtr	88.00		
2	Applying Acrylic Emulsion Paints on plastered surface at any floor level as directed: Firstly, the surface shall be scraped thoroughly and prepared to receive fresh paints by means of appropriate tools & tackles. Also, sand papering in intermediate coats for smoothening and cleaning the surface thoroughly shall be done prior to painting. White Cement-based Putty is to be applied up to approximately 1.5 mm thickness, if required. Two coats of Acrylic Primer of approved make as required are to be applied on the prepared surface. Then, two coats of best quality Acrylic Emulsion Paint of approved shade & make are to be applied over the primer coats. Protective and decorative approved grade paint is to be applied, and duly completed up to smooth finishing. The work is to be done as per manufacturer's specification. Also, scaffolding and staging are to be done wherever necessary. The work is to include all necessary materials, accessories, labour, tools & tackles. All materials should be approved by the Bank. Painted area is to be measured for finished work.	Square Metre	90.00		
3	Storage Units with openable shutters, overall depth: 450 mm, min. height: 2100 mm, made out of 19 mm thick BWP block board for sides, top & bottom, and 12 mm thick BWP plywood for back & 19 mm thick BWP plywood for shelves & shutters, with laminate-finishing on exposed surface & polished finishing to inside surface including back surface grouting to walls & all necessary hardware like hinges, ball catches, tower bolts, etc.	Square Metre	15.00		
4	Applying Synthetic enamel paint at metal surface:	Square Metre	15.00		
5	Providing & laying vitrified tiles	Square Metre	15.00		
TOTAL VALUE OF CIVIL WORKS:			Rs		
(IN WORDS :					

GST will be extra as applicable

Signature of the Contractor with Official Seal
Bank reserves the right to select any material out of the specified make.

