

TENDER & SPECIFICATIONS FOR AIR-CONDITIONING WORKS OF NEW BRANCH PREMISES OF DHIMARKHEDA BRANCH , RBO-4, KATNI

Tender & Specifications for Proposed Air-conditioning work of New Branch Premises of SBI Dhimarkheda Branch Under RBO-4 katni					
S.N	Description of items	Qty	Unit	Rate	Amount
(A)	AIR CONDITIONING				
	Supply, installation, testing and commissioning of following AIR CONDITONERS as under. The Rate shall be inclusive of all taxes excluding GST. GST will be paid additionally by the Bank as applicable subject to GST Number and system has complete one year warranty & If any additional warranty provided by company/vendor in any specific part like compressor etc that is acceptable, please mentioned it.				
1	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, 5 STAR INVERTER RATING OF BEE AIR CONDITIONERS 1.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 3 metres with class "o" Nitrile insulation For ATM	2	Nos		
2	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, 5 STAR INVERTER RATING OF BEE AIR CONDITIONERS 1.5 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 3 metres with class "o" Nitrile insulation	2	Nos		
3	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, 5 STAR INVERTER RATING OF BEE AIR CONDITIONERS 2.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of SIZE 12.5/22mm upto 3 metres with class "o" Nitrile insulation	4	Nos		

TENDER & SPECIFICATIONS FOR AIR-CONDITIONING WORKS OF NEW BRANCH PREMISES OF DHIMARKHEDA BRANCH , RBO-4, KATNI

S.N	Description of items	Qty	Unit	Rate	Amount
4	Supply and installation of soft & prime quality of min. 22 G Copper pipe for " Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement. (If required additionally, payment will made as per actual installtion. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:- Superlon/Aflex/Armacell/Kflex Make of cable:Finolex/RR	95	R Mtr.		
5	Drain Pipe (If Required additional) Applicable to both ACs (Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. (If required additionally, payment will made as per actual installtion.) Make:- Kasta/supreme	80	R Mtr.		
6	Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1Tr /1.5Tr Split AC & 1.5 Tr Cassette AC) Make: Microtek, V-Gards (Voltage Range 150- 280 Volts)	4	Nos		
7	Providing & fixing of 5 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 2 Tr Split AC & Cassette AC) Make: Microtek, V-Gards (Voltage Range 150- 280 Volts)	4	Nos		
8	Electronic Timer for auto swith on/off to AC of server/ATM/E-lobby for 4Hr/8Hr. Make:- Legrand, L&T, and other Eq. ISI make	1	Nos		
TOTAL AMOUNT FOR AIR-CONDITIONING WORK					