1	BRANCH DETAIL:	Ghatiya Branch, Distt. UJJAIN (M.P.)				
	AIRCONDITIO					
I.No	Description of items	Unit	Qty	in I Rate Rs	NR Amount R	
•	AIR CONDITIONING WORK			Kate KS	Amount K	
	IMP NOTES: The Contractor shall visit the site before					
	quoting rates for a better understanding of the working					
	conditions on site. The scope work shall include Careful					
	Dismantling/ Removing/ Deinstallation of Old, Non- Functional Air conditioning units including Window units/					
	Indoor and Outdoor Units, Ductable Units/ any other type					
	of window/wall/ceiling mounted units, all the connected					
	ducts/piping etc. The work shall be done without damaging the unit being removed or the structure on which					
	it has been mounted or the other fixtures like AC grills, AC					
	ducts or any type of conduiting/wiring/electrical					
	fixtures/fire alarm sensor etc. complete. The task shall include safe handling and removal from site of un-installed					
	ducts etc to a safe distance and of usable material to stores					
	or as directed by the engineer-in-charge					
	Supply, installation, testing and commissioning of following					
	AIR CONDIRIONERS as under. The Rate shall be inclusive					
	of all taxes excluding GST. GST will be paid additionally by					
	the Bank as applicable subject to GST Number. and system has complete one year warranty & If any additinal					
	warranty provided by company/vendor in any specific part					
	like compressor etc that is acceptable, please mentioned it.					
1	Supply, installation, testing and commissioning of Higher	Nos	2			
-	Efficient models of SPLIT AC, THREE STAR RATING OF	1105	2			
	BEE AIR CONDITIONERS 1.0 Ton Inverter Machines					
	confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC					
	supply with rotary compressor, Refrigerant and capable to					
	perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with					
	remote control with Cool/Fan/Dry/Auto mode, sleep mode					
	& on/off timer with suitable thermostat. The rate should					
	include installation charges after making appropriate civil or interior changes on site if required and shall include all					
	required Heavy duty or company provided ready made or					
	fabricated M S Stands if required to install the out door and indoor units as per site conditionscont'd					
	Quoted competitive rate should deduct cost of company provided copper piping, the cost shall be paid as per actual					
	length with nil deductions under the appropriate item only.					
	The copper piping, drains piping and electrical cabling					
	should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder					
	coated. Indoor unit should have LED display. The rates					
	shall be inclusive of all repairs of civil and carpentry work, original fill and additional top up of refrigerant gas as per					
	site condition, testing and commissioning complete.					
	Make of ACs: - Daikin/Hitachi/Voltas/Bluestar/Carrier only					
2	Supply, installation, testing and commissioning of	Nos	1			
	Higher Efficient models of SPLIT AC, THREE STAR		1			
	RATING OF BEE AIR CONDITIONERS 1.5 Ton Inverter Machines confirming to latest Indian Standards and					
	suitable for operation on 230 Volts + 10 %, single Phase,					
	50 Hz AC supply with rotary compressor, Refrigerant and					
	capable to perform cooling, dehumidifying, Air Circulating,					
	auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode,					
	sleep mode & on/off timer with suitable thermostat. The					
	rate should include installation charges after making					
	appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as					
	per site conditions including carpentry work, minor civil					
	work and material including copper piping of hard & prime					
	quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit,					
	cont'd					

	Quoted competitive rate should deduct cost of company provided copper piping, the cost shall be paid as per actual length with nil deductions under the appropriate item only.				
	The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is				
	allowed. The out door unit should be anti-rust powder				
	coated. Indoor unit should have LED display. The rates shall be inclusive of all repairs of civil and carpentry work,				
	original fill and additional top up of refrigerant gas as per site condition, testing and commissioning complete.				
	Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only				
	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, THREE STAR RATING OF	Nos	5		
	BEE AIR CONDITIONERS 2.0 Ton Inverter AC Machines confirming to latest Indian Standards and suitable for				
	operation on 230 Volts + 10 %, single Phase, 50 Hz AC				
	supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode,				
	auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode				
	& on/off timer with suitable thermostat. The rate should include installation charges after making appropriate				
	changes in existing false ceiling. Heavy ready				
	made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work,cont'd				
	Quoted competitive rate should deduct cost of company provided copper piping, the cost shall be paid as per actual				
	length with nil deductions under the appropriate item only. The copper piping, drains piping and electrical cabling				
	should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder				
	shall be inclusive of all repairs of civil and carpentry work,				
	original fill and additional top up of refrigerant gas as per				
	site condition, testing and commissioning complete. Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only				
	Supply and installation of hard & prime quality of min. 22	Mtr	RO		
	G Copper pipe for "Cassette AC Only" with class "o" Nitrile insulation of minimum 12 mm for 3 / 4 ton cassette				
	type air conditioner including interconnection power/ communication cable between indoor and outdoor unit as				
	per site requirement. (If required additionally, payment will made as per actual installtion.) The rate inclusive of all				
	chisel work, plastering, finishing, painting & all civil related				
	work pertaing to mentioned work. Make of Insulation:- Superlon/Aflex/Armacell/Kflex Make of cable:- Finalox/DP/Havellc				
	Finolex/RR/Havells Supply and installation of soft & prime quality of min. 22 G	Mtr	86		
	Copper pipe for " Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner	-	-		
	including interconnection power/ communication cable				
	between indoor and outdoor unit as per site requirement. Payment will made as per actual installtion and nil				
	deduction shall be made for company provided lengths. The rate shall be inclusive of all chase making and/or chisel				
	work, plastering, finishing, painting & all civil repair work pertaining to mentioned work. Make of Insulation:-				
	Superlon/Aflex/Armacell/Kflex Make of cable:- Finolex/RR/Havells				
_	Drain Pipe Applicable to both ACs(Cassette & Split AC).	Mtr	48		
	Supply and laying of heavy gauge PVC drain piping of				
	40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition.				
	The rate inclusive of all chase making and/or chisel work, plastering, finishing, painting & all civil repair work				
	pertaining to mentioned work. Make:- Kasta/supreme				
	Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at	Nos	8		
	site (For 1Tr /1.5Tr Split AC & 2 Tr Split AC) Make:- Microtek, V-Guard (Voltage Range 150- 280 Volts)				
1	TOTAL OF AIR CONDITIONING WORK			Rs	
	/ords Rs.				<u>/</u>