STATE BANK OF INDIA

SCHEDULE OF WORKS: ELECTRICAL AND AIR CONDITIONING WORKS

TIKARI BRANCH RBO GAYA : AO GAYA

	DESCRIPTION ELECTRICAL	UNIT	QTY	RATE	AMOUNT
	LLLOTTIONL				
1	MAIN INCOMING SOURCE PANEL (MISP): Supply, installation, testing and commissioning of main incoming (MIP) Panel suitable for wall /floor mounted indoor type, air insulated, totally enclosed vermin-proof (IP 42), dead front, cubicle type, 2 mm thick sheet steel enclosure use on 415 V, 3 Ph., 4 wire, 50 Hz. A.C. system, instrumental panel, CTs, incoming and outgoing cable compartment. The Panel shall be complete with switches as per site requirement, interconnection, G.I. earth busbar of adequate size covering the total length of switch board with drilled holes, G.I. bolts, nuts, washers etc. as directed by E-I-C. The cubicle should be painted with two coats of light grey synthetic enamel paint over two coats of zinc chromate primer. The complete fabrication, construction shall be done as per the site condition and conforming to the relevant IS. Name plate of Panels Danger Board, incoming and outgoing feeders with Ampere rating of switches are to be fixed up on front door above or below the respective switches. Approval of Manufacturer's drawings from E-I-C. The Panel consists of the following				
1.1	INCOMING: 1 No.: 415V, 160A 4P MCCB (36 KA) for Mains(ICs=ICu=100%), 1 No.: 415V, 100A 4P MCCB (36 KA) for DG, 1 No.: 415V, 160A 4P On-Load Changeover Switch 2 No.: Digital Multi Function Meter (MFM) for Current, Voltage, Frequency, Power. 6 Nos.: LED Phase indicating lamps, 6 Nos.: Suitable CTS(200/5) PVC sleeved TPN Tinned Copper Busbar 35mm x 6mm for phases and neutral. (2sets) G.I. EARTH BUSBAR - 25mm x 3mm covering the total length of panel. OUTGOING: Termination I: (To be connected with C.O.) 2 No 32A DP MCB for Glow Sign Board and others, 1 No 63A 4P MCCB(25KA) for Raw Power VTPN, 1 No 63A 4P MCCB for UPS, 1 No 63A TPN MCB Spare, 1 NO 63A DP SPARE Termination-II: (Not to be connected with C.O.) 1 Nos. 100A 4P MCCB(25KA) for AC VTPN, 1 no 63A TPN spare	SET	1		
2.1	(A) UPS INCOMING DB: Supply of all required materials and fixing of input UPS box (Company made) having provision of the following arrangement complete with all respects per the direction of engineer in charge. Incoming: 1 No. 63A (10KA) TPN MCB Outgoing: 2 Nos. 63 A (10KA) DP MCB		1		
2.2	(B) UPS OUTGOING DB: Supply of all required materials and fixing of output UPS box (Company made) having provision of the following arrangement complete with all respects per the direction of engineer in charge. <i>Incoming:</i> 1 no. 63 A DP MCB <i>Outgoing:</i> 3 No. 40A (10KA) DP MCB	No.	1		
3	SITC of following VTPN Distribution Board (HVAC DB), having vertical fishbone busbar type, factory assembled wall mounted, sheet metal fabricated, fully powder coated, having dust proof & vermin proof hinged door with all internals such as DIN channels, neutral link, internal wiring complete with double earthing lugs including DB wiring dressing with ferruling, termination of circuits with ping type copper lugs, etc. housing following switchgears. (Schneider / ABB/ Legrand / Siemens / L&T make)				
3.1	Incoming:1 no 415V ,4P,63A MCCB,25/36KA rating(L&T/ABB/SIEMENS) outgoing:- 8 nos 40A SP MCB(10KA), FOR RPDB/LDB/BM AC etc	SET	1		
3.2	Incoming:1 no 415V ,4P,100A MCCB,25/36KA rating(L&T/ABB/SIEMENS) outgoing:- 12 nos 40A SP MCB, FOR AC etc	SET	1		

4	RAW POWER DB/LIGHT DB / COMPUTER DB Supply and installation of following metallic double door MCB Distribution Board with MCB having breaking capacity of 10 KA (minimum) complete with busbar, interconnection, painting, mounted on flat iron frame on wall/flushed with finished wall by chase cutting, mending good to original finish painting etc. as required. Name plate & number of DBs are to be fixed up on front door of DBs for their identification.			
а	CDB: Consumer unit SPN MCB DB complete with busbar and the following MCBs. INCOMING: 1 No. 240V 40A (10KA) DP RCBO OUTGOING: 8 Nos. 240V 10A (10 KA) SP MCB		2	
b	Double pole MCB DB in sheet steel enclosure with Incoming: 1 no. 25A DP ELCB, Outgoing: 2 no. 10A SPN MCB complete with interconnection, timer(QT-31) & contactor (2P 25A) for glow sign board and Street Light. (L&T/ABB/SCHNEIDER)	No	1	
С	LDB: Consumer unit SPN MCB DB complete with busbar and the following MCBs. INCOMING: 1 No. 415V 40A (10KA) DP MCB OUTGOING: 8 Nos. 240V 10A (10 KA) SP MCB	No.	3	
d	UPS Essential DB for CCTv, Fire Alarm Etc: Consumer unit SPN MCB DB complete with busbar and the following MCBs. INCOMING: 1 No. 240V 40A (10KA) DP RCBO(30mA-100mA) OUTGOING: 6 Nos. 240V 10A (10 KA) SP MCB		1	
е	RPDB: Consumer unit SPN MCB DB complete with busbar and the following MCBs. INCOMING: 1 No. 415V 40A (10KA) DP MCB OUTGOING: 6 Nos. 240V 10A-16A (10 KA) SP MCB		2	
5	Wiring flame retardant FRLS/FRLSH as mentioned in rows below in MS conduit of IS specification of proper size with all material supply installation and commissioning complete from DB . The wiring shall be carried out on surface above false ceiling, and below of false ceiling by chiseling the existing surface and plastering the same with cement etc., or as cutting of tiles(with finishing), as per site conditions after fixing the MS conduit with all accessories like saddles screws, bends T-joint etc			
а	With FRLS 2 nos. 6 Sq.mm + 1 no. 2.5 Sq.mm. (green colour for earth) PVC insulated copper wire in ms conduit for UPS Outgoing to LDB/RPDB/CDB	Mtr	150	
b	With FRLS 4 nos. 6 Sq.mm + 1 no. 2.5 Sq.mm. (green colour for earth) PVC insulated copper wire in ms conduit for UPS input	Mtr	40	
С	With FRLS 2 nos. 6 Sq.mm + 1 no. 2.5 Sq.mm. (green colour for earth) PVC insulated copper wire in ms conduit for cassette AC (2 tr) as per direction of E-I-C.		110	
d	With FRLS 2 nos. 4 Sq.mm + 1 no. 2.5 Sq.mm. (green colour for earth) PVC insulated copper wire in ms conduit for AC (1.5 tr) as per direction of E-I-C.		25	
6	SUPPLY, LAYING, LUGGING, DRESSING, GLANDING, FINISHING, TESTING AND COMMISSIONING OF POWER CABLE: Following 1.1KV grade fire resistant A2XFY XLPE armored aluminium conductor cable with one no. 10 SWG GI wire , laying of the cable partly on wall/column including supply and fixing with 300mm apart MS clamps/galvanized bar saddles and double compression type brass cable gland Dowel make along with rubber rings for dust and moisture proof entry of the cable and finishing the ends by crimping method (POLYCAB/FINOLEX/NICCO/UNIVERSAL)			
6.1	SITC of 3.5CX 70 SQMM cable incoming cable	Mtr	50	
6.2	SITC of 3.5CX 50 SQMM cable incoming cable for AC VTPN	Mtr	25	
6.3	SITC of 3.5CX 35 SQMM cable incoming cable for Raw Power VTPN AND ATM	Mtr	55	

			Sheet1	
7	(A) COMPUTER SOCKET OUTLET WITH WIRING Computer socket outlet cluster point including supply and fixing of modular type socket outlet clusters components and its wiring from CDB, complete in all respect as detailed below. Each computer socket outlet cluster comprising the following 5 Nos. 6/16A 5 pin modular type International sockets 1 No. 16A modular type common controlling switch with indicator on table top with 2 Nos. 2.5 Sq.mm. + 1 x 1.5 Sq.mm.FRLS (green colour for earth) PVC insulated copper wire in pre - laid (as per ISI) M.S. conduit including interconnection, painting etc. as required to be completed in all respect from CDB to Computer point.	No.	8	
	(B) COMPUTER SOCKET OUTLET AND ITS WIRING Computer socket outlet cluster point including supply and fixing of modular type socket outlet clusters components complete in all respect as detailed below. Each computer socket outlet cluster comprising the following 3 Nos. 6/16A 5 pin modular type International sockets 1 No. 16A modular type common controlling switch with indicator on table top with 2 Nos. 2.5 Sq.mm. + 1 x 1.5 Sq.mm. PVC insulated copper wire (1.1 KV grade FRLS/FR-LSH) in pre - laid (as per ISI) M.S. conduit including interconnection, painting etc. as required to be completed in all respect from CDB to Computer point. (proper colour code must be followed)	No.	3	
	C) UPS/ RAW POWER SOCKET OUTLET AND ITS WIRING Raw power socket outlet cluster point including supply and fixing of modular type socket outlet clusters components AND WIRING 1100V grade, FRLS complete in all respect as detailed below. Each computer socket outlet cluster comprising the following 2 Nos. 6A/16A 5 pin modular type International sockets. 1 No. 16/20A modular type controlling switch with 2 Nos. 2.5 Sq.mm. + 1 x 1.5 Sq.mm. (green colour for earth) PVC insulated copper wire in pre- laid (as per ISI) M.S. conduit including interconnection, painting etc. as required to be completed in all respect from RPDB to Raw Power Outlet. Proper colur code must be followed.	No.	9	
	D) UPS / RAW POWER SOCKET OUTLET AND ITS WIRING Raw power socket outlet cluster point including supply and fixing of modular type socket outlet clusters components AND WIRING 1100V grade, FRLS complete in all respect as detailed below. Each computer socket outlet cluster comprising the following 1 Nos. 6A/16A 5 pin modular type International sockets with indicator 1 No. 16/20A modular type controlling switch with 2 Nos. 2.5 Sq.mm. + 1 x 1.5 Sq.mm. (green colour for earth) PVC insulated copper wire in prelaid (as per ISI) M.S. conduit including interconnection, painting etc. as required to be completed in all respect from RPDB to Raw Power Outlet. Proper colur code must be followed.	No.	4	
×	SITC of metal clad socket MCB for AC point with controlling 32 A DP MCB with industrial top complete in all respects in suitable enclosure.	No.	7	

			Sheet1	
9	. SITC of OBO Betterman make earthing system - * - UL Listed Earth Electrode - Copper bonded low carbon steel electrode, coating 250 microns - Tested as per IEC 62561-2 - Meets the requirement of IS 3043 and IEC 60364-5-54 - Tested for short circuit withstanding capacity - High tensile strength In one set it should include: a) One nos of Earthing rod-Type 17 3000 CCER, Length - 3000 mm Outer Dia - 17.2 mm Copper bonded low carbon steel Electrode WITH 250 microns copper bonded b) One bag (25 KG) Earth Enhancement Compound confirming to IEC 62561-7 c) One nos of universal clamp .The work shall also include required masonry work, CI cover plate & Earthing name plate. The vendor shall also submit the earth test report with required values. Pics of earthing	No.	2	
10.1	SITC of Earth distribution Box (Bus Bar Station) to be installed in the branch near Main Panel and UPS, comprising of a bus bar of 3x25x180mm cu strip	SET	2	
	Supply and laying of 8 SWG Cu cotton coated wire in 20mm dia rigid PVC conduit for earthing From the existing earth pit to the Main panel/UPS		50	
11	POINT WIRING AND CIRCUIT WIRING Point wiring with FRLS 1100 V grade 3 nos. single core 1.5 sq.mm. and 1 for common earth by looping method) PVC insulated stranded copper conductor wire (IS:694) through suitable size M.S. conduit (ISI marked embossed on conduit surface) by thred cutting, complete with junction box, circular box, elbows, bends, couplers and other accessories on surface above false ceiling or concealed by chase cutting on wall from light & fan switch board to light, fan & 6A socket outlet on the same switch board or separately mounted switch board. The work includes supply and fixing of all materials such as modular type 6A switch for light and fan point, 6A 2/3 pin shuttered socket outlet with switch in each switch board, 3 plate ceiling rose / angle or batten holder etc. as required. The point wiring also includes circuit wiring with FRLS 1100 V grade 2 nos. single core 2.5 sq.mm. +1 no. single core 1.5 sq.mm. PVC insulated stranded copper conductor cable (IS:694) through suitable size M.S. conduit as described above from DB to switch board, interconnection, mending good all damages to original finish, painting			
а	1 Light control by 1 switch	No.	36	
b	2 /3 Light control by 1 switch	No.	30	
С	UPS light point	No.	6	
d	Glow sign board wiring	No.	1	
е	Exhaust fan point	No.	5	
f g	Ceiling fan point with supply and fixing of Electronic Regulator as required as per site conditions. 1x16A 2/3 pin modular socket with switch on separate switch board outside the Cash Room complete with wiring. Suitable Top to be provided for supply to Cash Room. (PECORD ROOM) (TATIONERY ROOM)	INO.	2	
h	for supply to Cash Room. /RECORD ROOM/STATIONERY ROOM Wall fan point with socket	No.	13	
	3 pin 6/10A modular socket with switch in board	No.	8	
12	Supply and fixing of ding-dong calling bell with complete wiring in BM's Chamber as per direction of E-I-C	No.	1	

			Sheet1	
	MAIN TPN SFU: Supply, installation, testing and commissioning (SITC)			
	of following TPN SFU with HRC fuses in sheet steel enclosure with cable			
13	end-box on MS Angle Frame/ MS Legs/ wall with interconnection,			
	painting and finishing.			
	160A TPN SFU with HRC fuses	No.	1	
		140.		
	PART B-SUPPLY AND FITTING OF ELECTRICAL FITTINGS			
14	Supply & Fixing of 36W-2'x2' LED Panel light recessed mounted make complete with all accessories.	No.	20	
15	Supply & Fixing of 15W LED Downlighter recessed mounted of make complete with all accessories	No.	10	
16	Supply & fixing of 20W/22W LED T5 Batten fitting complete with all	No.	12	
17	Supply & fixing of 35W LED Street Light with suitable mounting pipe etc. Of complete in all respect	No.	2	
18	Supply & fixing of 450mm sweep, oscillating type, wall mounting, multi speed wall fan metal blades three pin complete with all respect as per direction of Bank/E-I-C.		10	
19	SITC of 1200MM ceiling fan	No.	1	
20	SITC of 9" dia 230V,1400 rpm exhaust fan as in toilets, ups room, toilets etc.	No.	5	
	PART C- LAN CABLING WORK			
	Supply of 1 mtr. Long E-CAT 6 PATCH CHORD			
21	(Make: D-LINK, AMP,	No.	18	
	Supply of 2 mtr. Long E-CAT 6 PATCH CHORD			
22	(Make: D-LINK, AMP,	No.	9	
23	INTERNET SOCKET WITH DATA CABLE:: SITC of modular RJ-45 internet sockets with suitable mounting box (modular type) including all inter-connections as required with front plate D link or equivalent make approved by the bank connections etc as required along with supply, laying, concealing of CAT 6 LAN cables upto 30 metres or less or as per site conditions in rigid pvc conduit pipes complete in all respects from Data Rack to I/O points. Rates to include cost of LAN cable and its installation.	No.	18	
24	Supply & installation of 9U Rack with power supply arrangement, ventilation fan, mounting racks ect. Complete with all accessories.	No.	1	
25	SITC of 24 port Patch Panel complete in all respects.	No.	1	
26	ONLOAD CHANGE OVER SWITCH: SITC of 1 no. 415V, 63A, 2P with on indication on load Change over switch with suitable enclosure.		2	
27	Charges for making and submitting neat and clean computerised Electrical Drawing of the Branch indicating SLD of the Branch, indicating DB, switch boards, etc along with proper numbering and indicating power flow and laminating	SET	1	
28	Charges for making and submitting neat and clean computerised lan WIRING Drawing of the Branch indicating Data Rack, lan wiring to different I/O boxes etc along with proper numbering and laminating the same		1	

			Sheet1	
29	Supply of labour and material as required for dismantling of exiting wiring, DBs, panel etc, and providing temporary connection of power or lan for smooth running of branch during course of renovation.		1	
30	Supply & Installation of single color (warm white / any other approved color) flexible LED strip light for cove including required rated driver / power supply in multiples of 1 Rmtr as approved along with all necessary hardware & accessories, etc. Complete as required (PHILIPS / WIPRO / CGL / GE / Bajaj/Syska)		80	
31	SITC of LED 5W/6w light & fixture recessed type ROUND DOWNLIGHTER in gypsum cove with all interconnection and fixing arrangements as Required.	No.	50	
	Air conditioning Works			
	Design,Supply , installation, testing & commissioning of airconditioning units (including MS frames/stands for standard installation of indoor and outdoor units)as per the details of scope of work, specifications and components given else where in the tender. (please read before quoting)Note:The contractor will attend to all defects noticed during defect liability period. Within 24 hours from the time of complain If the contractor fails to attend to the defects within 24 hours time these defects will be rectified by the Bank and the expenditure incurred on this account will be recovered from security deposit, or any other money due on to time. The Entire Job Shall be Executed in Total Co. Ordination with the Other Agencies Working on this Project more particlulary with the False Ceiling. The quantities as mentioned of AC are provisional may increase/decrease/withdrawn as per requirement of site or instruction of Bank. High Side Items			
32	Supply of following Ceiling Mounted 4-way Cassette type AC with scroll / Rotary / Twin rotary / Reciprocating compressor, having R 32/R-410A eco friendly gas. Including indoor unit & outdoor unit decorative grille and cordless remote Machine shall have copper condenser Unit. (The positions must be designed in an apt away as per site conditions) (Make: LG/Daikin / Carrier / Hitachi / Mitsubishi / Bluestar)			
32.1	Supply of single phase 2.0 TR or nearest higher rating Capacity Copper (inverter technology) Cassette type split air conditioners with Copper Condensor Coil and eco friendly refrigerants (R32 or R 410A). (Make: LG/ Daikin / Carrier / Hitachi / Mitsubishi / Bluestar) FOR HALL AREA		5	
	Low Side Works			
33	Refrigerant copper piping both in and out, laid between indoor & outdoor unit as per OEM's specifications duly insulated with Class "O" fire retardant 6 mm sleeve type elastomeric nitrite rubber insulation. It shall be in total clamping manner above false ceiling & in total concealed manner below false ceiling level. From the structural ceiling it should hang or shall be fixed on wall / beam etc. with clamps & the distance between two clamp shall be less than 1 meter. It shall not be placed over the false ceiling nor it shall be fixed with false ceiling members. The diameter / gauge of the ref.pipe shall be as per the specifications of the Manufacturing company (OEM) only for each type of machine.			
33.1	For Cassette AC (2.0TR)	Rmt	70	
35	Drain Piping: Insulated Condensate Water Drain piping constructed out of PVC / HDPE hard pipes, fitting, accessories, bends, elbows, tees, flanges, tappings, wall sleeves, hangers, supports, anchors Fastners.			

2F 4	Drain nino	Drot	00		
ან.1	Drain pipe	Rmt	80		
	SITC of Electrical Power Cabling between indoor unit &outdoor unit as per OEM's design & specifications in 25mm dia conduits with				
	as per OEM's design & specifications in 25mm dia., conduits with accessories The power shall be made available at 1 place & single				
36	core wire shall not be used. It shall be in clamping manner above				
	false ceiling & in concealed manner below false ceiling level.From				
	structural ceiling it should hange or shall be fixed on wall/beam etc. with clamps at distance not more than 1 meter. It shall not be				
	placed over the false ceiling nor shall be fixed with false ceiling				
	members.				
36.1	Control cable between indoor & outdoor unit for cassette AC	Rmt	90		
		1 (111)			
	Installation charges of the 2.0 TR/1.5TR Copper Cassette Type/		_		
	Split AC including outdoor frame / stands to withstand the full load	No.	5		
	of outdoor units and making good all the damage.				
	SUPPLY & INSTALLATION OF STABILISERS				
38	For 2 ton cassette AC (5 KVA) stabiliser with metal body	No.	5		
	For 1.5 ton/ 1 ton Cassette AC/split stabiliser with metal body (4				
39	KVA)	No.	2		
	All sort of Civil work required to be executed in order to make the				
	Air-conditioning system installed & put in working condition. The				
40	item includes, making holes / gaps in walls to pass duct & pipes,	Job	1		
	making zaries required for various types of drain, refrigerant & drain	300	1		
	water pipes / lines in walls, floor etc. using cutter machine, including				
	core cutting , wall cutting etc as required.				
	Dismantling of Existing Air Conditioners and removing ,relocation,		,		
41	refixing and reinstalltion of of Existing AC as per site requirement.	Job	1		
	3 - 1 - 1				
			TOTAL (n . \	
			TOTAL (RS.)	
	Grand Total				
	Grand Total (GST will be extra as applicable)				
	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances				
NOTE:	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances				
NOTE:	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess,transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per				
NOTE:	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances				
NOTE:	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement.				
NOTE:	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance				
NOTE:	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be				
NOTE:	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately.				
1	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw				
1	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point.				
1 2	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess,transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided				
1 2	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer				
1 2	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess,transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided				
1 2	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess,transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD				
1 2	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT BS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, TELE. KRONE				
1 2	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess,transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD				
2 3	The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT BS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope				
2 3	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel .THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor.				
3	The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT BS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope				
1 2 3 3 4 5 5	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel .THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. RRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be				
1 2 3 3 4 5 5	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. – 2 SETS OFCOPIES – 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling				
1 2 3 3 5 6 6	The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TELE. AFTER EXECUTION OF THE BRANCH 2 SETS OFCOPIES - 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be				
1 2 3 3 4 5 5	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. – 2 SETS OFCOPIES – 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling				
1 2 3 3 5 6 6	The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT OP OPINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. – 2 SETS OFCOPIES – 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be explosion proof only. Additional inter-connections within the main panel and TPN SFU has been included in the rate of main panel.				
1 2 3 3 4 5 6 6 7	The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT BS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be explosion proof only. Additional inter-connections within the main panel and TPN SFU has been included in the rate of main panel. Distance between power and electronic earthings must be at least 3.5 Mtr.				
1 2 3 4 5 6 7 8 9	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel .THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be explosion proof only. Additional inter-connections within the main panel and TPN SFU has been included in the rate of main panel. Distance between power and electronic earthings must be at least 3.5 Mtr.				
1 2 3 4 5 6 7	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DATARACK TO DIFFERENT WITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT WIPS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TEC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be explosion proof only. Additional inter-connections within the main panel and TPN SFU has been included in the rate of main panel. Distance between power and electronic earthings must be at least 3.5 Mtr.				
1 2 3 4 5 6 7 8 9	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel .THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be explosion proof only. Additional inter-connections within the main panel and TPN SFU has been included in their relevant sections. Proper load distribution is to be done by the vendor. Load variation over 10% will be unacceptable.				
1 2 3 4 5 6 7 8 9	The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel. THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT FOINTS WITH NUMBERING, TELE. KROND BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, TELE. KROND FOR BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be explosion proof only. Additional inter-connections within the main panel and TPN SFU has been included in the rate of main panel. Distance between power and electronic earthings must be at least 3.5 Mtr. All cables except the ones mentioned separately in the estimation have been included in their relevant sections. Proper load distribution is to be done by the vendor. Load variation over 10% will be unacceptable				
1 2 3 4 5 6 7 8 9	(GST will be extra as applicable) The rate quoted shall be firm and shall include all costs, allowances, Charges, levies, Royalties, Cess, transportation etc. but excluding GST as applicable which will be reimbursed by the Bank as per Government norms prevailing from time to time. Contractor's are advised to visit the site before quoting. The quantities are tentative may increase or decrease as per site requirement. The work must be guaranteed for a period of 12 months for its satisfactory performance from the date of completion and all defects cropping up within this period must be rectified at contractor's cost immediately. In electrical room, ups room, there must be one emergency light point other than raw light point. Earthing test report, Meggar test report & test certificates for the cables will be provided to the Electrical Engineer Measurement sheet for the work done, load calculation sheet, GA drawing for Main panel .THE CONTRACTOR SHOULD SUBMIT THE BUILTUP SLD OF PANEL, SLD OF DIFFERENT DBS TO DIFFERENT SWITCHBOARDS WITH NUMBERING, SLD OF DATARACK TO DIFFERENT I/O POINTS WITH NUMBERING, TELE. KRONE BOX TO DIFFERENT TELE. POINTS WITH NUMBERING, ETC. AFTER EXECUTION OF THE BRANCH. — 2 SETS OFCOPIES — 1 WITH LAMINATION. All work to be carried without hampering banking operations. Dismantling wherever required in scope of vendor. Work completion certificate including required dismantling work if any will be provided by the branch manager. All cable and wire terminations must be proper with suitable lugging. There must not be any loose wiring/ cabling There should not be any jointing in the cables/wires. All wiring accessories should be explosion proof only. Additional inter-connections within the main panel and TPN SFU has been included in their relevant sections. Proper load distribution is to be done by the vendor. Load variation over 10% will be unacceptable.				