

**BOQ ( PRICE BID)**

<b><u>INTERIOR FURNISHING WITH ALLIED CIVIL WORKS OF CIRCLE AUDIT OFFICE IN LCPC BUILDING, ALIGANJ EXTN., LUCKNOW.</u></b>					
<b>S. No</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate (Excluding GST)</b>	<b>Amount</b>
	<b>RCC Work</b>				
1	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of cantering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum	0.75		
2	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	Sqm	8.25		
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	Kg	60.00		
	<b>Brick Work</b>				
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	15.00		
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : Cement mortar 1:4 (1 cement : 4 coarse sand)	Sqm	67.00		
6	Extra for half brick masonry in superstructure, above floor V level for every four floors or part thereof by mechanical means.	Sqm	0		
	<b>Stone Work</b>				
7	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre moulded and pre polished, machine cut for kitchen platforms, vanity counters, window sills, facia and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black, Cherry/Ruby red Area of slab up to 0.50 Sqm	Sqm	1.25		

Bidder's signature

8	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre moulded and pre polished, machine cut for kitchen platforms, vanity counters, window sills, facia and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black, Cherry/Ruby red Area of slab over 0.50 sqm	Sqm	7.25		
9	Extra for fixing marble /granite stone, over and above corresponding basic item, in facia and drops of width up to 150 mm with epoxy resin based adhesive, including cleaning etc. complete.	Metre	12.00		
10	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble / Granite / stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Each	3.00		
<b>FRP Door &amp; Window Work</b>					
11	Providing and fixing Fibre Glass Reinforced plastic (FRP) Door Frames of cross-section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness. The laminate shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fibre glass from all sides. M.S. stay shall be provided at the bottom to steady the frame.	Metre	15.00		
12	Providing and fixing to existing door frames.30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames.	Sqm	5.25		
<b>Flooring &amp; Cladding Work</b>					
13	Providing and fixing 1st quality rectified ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. Size 600x450 mm	Sqm	32.00		

Bidder's signature

14	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, levelling system and rubber mallet for placing the tiles gently and easily. Glazed <b>Vitrified tiles Matt/Antiskid finish</b> of size of Tile 600 x 600 mm	Sqm	22.50		
15	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, levelling system and rubber mallet for placing the tiles gently and easily. <b>Double charge vitrified tile polished finish</b> of size of Tile 800 x 1600 mm	Sqm	380.50		
16	Deduct for not using 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) bedding in laying of floor tiles and jointing with grey cement slurry @ 3.3 kg/ sqm.	Sqm	-403.00		
17	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.	Sqm	403.00		
18	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, <b>in skirting, riser of steps</b> , over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigmented complete. Size of Tile 600x600 mm	Sqm	20.00		
19	Providing & fixing WPC (Wood Plastic Composite) Plank fixed with adhesive over levelled 50 mm (average) thick cement concrete all complete as specified and as directed by the Bank's Engineer/ Architect. Wooden Flooring as per design (Basic Rate minimum Rs. 200 sq.ft)	Sqm	85.50		
<b>Sanitary &amp; Plumbing Works</b>					

Bidder's signature

20	Providing and fixing White vitreous wash basin Make- Kohler Cat No. K-76601IN-7 Size - 375x475x130 with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:	Each	1.00		
21	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge/ Consultant.	Each	4.00		
22	Providing & fixing electronic Sensor Faucet for wash basin deck mounted.	Each	1.00		
23	Providing and fixing <b>Braided Hoses</b> with Two 15mm CP Brass Nuts & Rubber Washers Without Nipple (Suitable for Geysers and basins), all complete as per the direction of Engineer-in-charge/ Consultant.45 cm length 15 mm nominal bore	Each	4.00		
24	Providing & fixing of <b>Wall Mounted Paper towel dispensers</b> towels with C/Z folds capacity: 400-600 C/Z towels made of AISI 304 Stainless Steel with Satin finished. The towel tray opening has bound edges to minimise tearing of paper towels. Door fixed to the body with two rivets, allowing it to be swung open for replenishment. Slot for viewing content level on the front, all complete as per the direction of Engineer-in-charge/ Consultant.	Each	1.00		
25	Providing and Fixing of <b>Health Faucet Kit (Flexible Chrome Hose, Handset &amp; Bracket)</b> all complete including CP flange etc. all complete as per the direction of Engineer-in-charge/ Consultant, all complete as per the direction of Engineer-in-charge/ Consultant.	Each	1.00		
26	Providing & fixing Towel Ring Square with C.P. brass wall brackets & C.P brass screws complete as required, all complete as per the direction of Engineer-in-charge/ Consultant. Size 600 x 20 mm size	Each	1.00		
27	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS: 8931 a) 15 mm nominal bore.	Each	3.00		
28	Providing and fixing of Sensor Operated Optimum Hand Dryers - Weld-free cover fixed to the base with 4 Allen bolts. Base in ABS thermoplastic UL 94-V0. Thermoplastic fan wheel PA6 UL 94-V0. Class F induction motor incorporating a safety thermal cut-off. PP UL 94-V0 aluminium centrifugal single inlet fan wheel. Heating element incorporating a safety thermal cut-off. Electronic infrared detection sensor. Adjustable detection adjustable (15-25 cm), all complete as per direction of Engineer - in - charge / Consultant.	Each	1.00		
29	Providing & Fixing <b>Automatic soap dispenser</b> Capacity-0.8 L. made by aluminium / ABS with Chrome finished, all complete as per the direction of Engineer-in-charge/ Consultant.	Each	1.00		

Bidder's signature

30	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/6 litre (adjustable to 4 litre/8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc. complete.	Each	1.00		
31	Providing & fixing white vitreous china Touchless urinal with rear inlet in white 1L Make - Kohler K-16321IN-SS-0 with integrated sensor Make - Kohler K-24199IN-C01-CP having antibacterial /germs free ceramic surface, fixed with cartridge having debris catcher and hygiene seal, all complete as per the direction of Engineer-in-charge/ Consultant.	Each	1.00		
32	Providing and fixing C.P. brass extension nipple (size 15mm x 50mm) of approved make and quality as per direction of engineer-in-charge	Each	2.00		
33	Providing and fixing horizontal/vertical Hot water geyser made of MS body with copper jacket inside with necessary inlet, outlet, drain, overflow, vent and all safety accessories etc. complete including cutting and making good the walls, wherever required, all complete as per the direction of Engineer-in-charge/ Consultant. 15 litre for Toilet	Each	2.00		
34	Providing & fixing Curved shape chrome finished urinal partition with 10mm thick frosted glass size- (900mm x 450mm), all complete as per the direction of Engineer-in-charge/ Consultant.	Each	1.00		
35	Providing and fixing 600 x 450 mm bevelled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Each	1.00		
36	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge (Cement shall be free issue material): Concealed work including cutting chases and making good the walls etc: 15 mm nominal outer dia Pipes	Metre	50.00		
37	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge (Cement shall be free issue material): Concealed work including cutting chases and making good the walls etc: 20 mm nominal outer dia Pipes	Metre	50.00		

Bidder's signature

38	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge (Cement shall be free issue material): Concealed work including cutting chases and making good the walls etc.: 25 mm nominal outer dia Pipes	Metre	50.00		
39	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge (Cement shall be free issue material): Concealed work including cutting chases and making good the walls etc.: 32 mm nominal outer dia Pipes	Metre	50.00		
40	Providing & fixing UPVC soil, waste, vent pipework comprising UPVC pipe conforming to IS :4985-1983 and of required class as specified below and fittings (moulded as well as fabricated) like elbows, bends, reducers, threaded tail pieces, caps and other specials jointing with cement solvent, chasing, cutting and making good the walls, complete in all respects including testing of complete installation. 75 mm dia	Metre	50.00		
41	Providing & fixing UPVC soil, waste, vent pipework comprising UPVC pipe conforming to IS :4985-1983 and of required class as specified below and fittings (moulded as well as fabricated) like elbows, bends, reducers, threaded tail pieces, caps and other specials jointing with cement solvent, chasing, cutting and making good the walls, complete in all respects including testing of complete installation. 100mm dia	Metre	50.00		
<b>False ceiling</b>					

Bidder's signature

42	<p><b>PLAIN CEILING</b> : Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms / sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts &amp; bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification 12.5 mm thick tapered edge gypsum moisture resistant board</p>	Sqm.	231.00		
----	---	------	--------	--	--

Bidder's signature

43	<p><b>GRID CEILING</b> :Providing and fixing mineral fibre false ceiling tiles at all heights of size 595 X595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflectance 85%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Fire Performance as per (BS 476 pt - 6 &amp;7)in true horizontal level suspended on interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32 mm of length 3000 mm, cross T of size 15x32mm of length 1200 mm and secondary intermediate cross T of size 15x32 mm of length 600 mm to form grid module of size 600x600 mm suspended from ceiling using galvanized mild steel item (galvanised @ 80 gsm) 50 mm long 8mm outer diameter M-6 dash fasteners, 6 mm dia meter fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200 mm centre to centre along main 'T'. The system should rest on periphery walls /partitions with the help of GI perimeter wall angle of size24x24X3000 mm made of 0.40 mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450 mm centre to centre &amp; 40 mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights. The work shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge.</p> <p>With 16 mm thick bevelled tegular mineral fibre false ceiling tile (NRC 0.55 to 0.6)</p>	Sqm.	194.00		
44	<p><b>WPC Ceiling</b> :- Providing and fixing in position Moisture proof, Anti Corrosion &amp; Anti skid Wood Plastic Composite board size- 2900x150x25 mm or customized size as per site ceiling over MS Frame Size -50x50x2 mm Hollow Square Section, all complete as per direction of Engineer-in- charge/ Consultant.</p>	Sqm.	34.00		
<b>Partition of different heights</b>					
45	<p>Providing and fixing <b>solid partition</b> , the framing shall made out of aluminium hollow section of 47mm x 40mm size 2.15mm thick as internal frame structure placed horizontally &amp; vertically at max distance of 2'-0" x 2'-0" centre to centre. Fixing 8+6 mm thick commercial ply on one sides with 1.0mm thick laminate both side of approved shade with groove pattern as per instructions of Architect. The shade of laminate finish to be got approved by Engineer -in-Charge /Consultant. The skirting should be as per approved laminate/ Veneer as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine polish if required, frame work above false ceiling done shall not be measured but contractor may factor</p>	Sqm.	347.00		

Bidder's signature



	it while quoting there rates as measurement up to false ceiling . All complete as per direction of the BANK'S ENGINEER/ Architect.				
46	Providing, fabricating & fixing of partition made out of <b>aluminium hollow section</b> of 38.1mm x 25.4mm size 1.44mm thick placed at min 2'x2' horizontally & vertically (as per site requirement ) with 12mm thick commercial grade ply finished with 1mm thick high gloss laminates ( of approved shade ) on both sides. The sides / top shall be finished with teak wood beading (3" x 1") with high gloss PU finish. This partition will be up to 3' ht. with 18" ht. 12mm thick toughened clear glass / aqua blue shade (approved make). The partition shall also be provided with 12mm toughened glass partition between counter up to 4'-6" ht. with 6" x 3" x15" pillar. (Partition in sqft. including glass ht. & width will be measured for payment ).All complete as per direction of the BANK'S ENGINEER/ Architect	Sqm	106.00		
	Finishing all wood surfaces with PU matt polish as per standard practices and specification complete.				
	<b>Note:.. All partition frame work shall be fixed to beam / slab soffit. Measurement shall be paid up to finished partition level only.</b>				
47	<b>Toughened glass partition</b> 12mm thick clear glass between customer & staff / officer up to 15" ht. for transaction area including fixing with SS bracket complete. The rates to include providing of 3M film as per approved pattern/ Design.				
	Toughened glass as above in Sqm.	Sqm.	3.00		
<b>Wall Finishing / Panelling</b>					
48	Fabricating and fixing wall/column panelling, the framing shall made out of aluminium hollow section of 38.1mm x 25.4mm size 1.44mm thick at spacing not exceeding 600mm both ways (horizontal and vertical). Panelling framework to be secured to wall surface/column surface. Panelling framework to be clad on one side with 8+6 mm thick ply board finished with 1.0mm thk laminate including skirting of 100mm high & 06mm x 06mm groove at skirting level. All complete as per direction of the Bank's Engineer/ Engineer's Representative.	Sqm.	133.00		
49	Fabricating and fixing <b>wall/column panelling</b> , the framing shall made out of aluminium hollow section of 38.1mm x 25.4mm size 1.44mm thick at spacing not exceeding 600mm both ways (horizontal and vertical). Panelling framework to be secured to wall surface/column surface. Panelling framework to be clad on one side with 8mm thick ply board finished with premium Veneer & melamine polish over 6 mm ply including skirting of 300mm high & 6mm x 6mm groove at skirting level. All complete as per direction of the Bank's Engineer/ Engineer's Representative.	Sqm.	26.00		

Bidder's signature

50	Supply and application of POP punning to a thickness of 10-12 mm. Application after cleaning the wall surface to get a seamless finish. Application to be done as per manufacturers' specifications etc. all complete.	Sqm.	309.00		
51	Supply and application of washable interior grade Dulux 3-in-1 plastic emulsion paint on walls with 1 coat of wall primer and 2 or more coats of plastic emulsion paint as per manufacturer's specifications etc. all complete. All painting final coats to be done after removal of face plates of switch boards in coordination with the electrical contractor and face plates to be fixed only after satisfactory completion of painting.	Sqm.	309.00		
<b>STORAGE CABINET</b>					
52	Providing ,& placing in position 2'-6" High & 1'-6" deep box type <b>Side</b> cabinet made out of 19 mm BWR board with white 1.5 mm thick High gloss Laminate top. Outside edge of the working top shall be provided with blue lacquered gloss /blue shade high gloss PU Coating facia. Inside edge finished with 1.00 mm thick laminate with side hinged shutter complete with handles, locks etc. complete. (for the purpose of contractor's payment only front elevation area will be measured).	Sqm	10.00		
53	Providing and fixing wooden storage 450 mm wide having sides, partitions shelves and shutter made of 19 mm thk. Board with 1 mm thk. High gloss laminate with all other exposed internal / external surface provided with Duco paint with melamine coating complete with side hinged shutter complete with handles , locks etc. ( for the purpose of contractor's payment only front elevation area of a cabinet will be measured .	Sqm	35.00		
<b>TABLE/ COUNTERS &amp; RACKS</b>					
54	<b>Repairing &amp; re-polishing of GM table-</b> Re lamination of table top and all exposed area and re polishing by melamine polish with smooth finished over all wooden surface including minor repairs and replacing accessories as required, all complete as per direction of Engineer-in-charge / Consultant. 8mm thick Toughened glass on top to be provided as per the shape of the table.	No.	1.00		
55	Supplying tables (2575mmX7065mm) made of 25mm thick commercial board with top having 1.5mm thick High gloss laminate. Edges shall have esteem beach moulding made out of 55mm x 40mm section with groove and finished in melamine polish. Base of table shall be made out of 40mm x40mm teak wood section finished in melamine polish.	RM	17.00		

Bidder's signature

56	Supply & fixing in position AGM table (size 750mmX2000mm) made out of 19 mm thick BWR board with 1.5 mm thick High gloss Laminate top with high gloss PU finished moulded edges on table top. Drawers shall have ball bearing slides & locks etc. complete internal surface shall be finished with 1.00 mm thk laminated with high gloss white laminate. each table shall have the provision of key board with ball bearing slides Arrangement 8mm thick Toughened glass on top .Providing of side track ( 4' 0"x 2'6" x 1'6") is included in the rate .	No.	3.00		
57	<b>Repairing &amp; re-polishing of CAMP/CM table-</b> Re lamination of table top and all exposed area and re polishing by melamine polish with smooth finished over all wooden surface including minor repairs and replacing accessories as required, all complete as per direction of Engineer-in-charge / Consultant . 8mm thick Toughened glass on top of the tables to be provided as per the required size & shape	No.	10.00		
58	Supply & fixing in position <b>officer's table</b> (size 600mm X 1500mm) made out of 19 mm thick board with 1.5 mm white High gloss Laminate table top at 2'6" ht. curved in front & sloping downwards upto 1;3" & laminated glass below with LED light in groove with drawer , CPU & keyboard tray as per single window counter & shutters complete as for single window cabinets completed in all respects . The table top & side table will have glass of 10 mm thk with 1" bevelling is also included in the rate .	No.	6.00		
59	Supply & fixing in position <b>officer's table</b> (size 600mm X 1200mm) made out of 19 mm thick board with 1 mm white laminate top at 2'6" ht. curved in front & sloping downwards up to 1;3" & laminated glass below with LED light in groove with drawer , CPU & keyboard tray as per single window counter & shutters complete as for single window cabinets completed in all respects . .	No.	1.00		
60	<b>WORK STATION / COUNTER:</b> Providing and fixing counter 2'-3" wide comprising of following complete in all respects. Officer / staff working counter top 2'3" deep with 1.5 mm thick high gloss laminate top including officer / staff working top at 2'6" ht. as per approved drawing. Back portion behind front laminate shall be provided with blue Lacquered gloss 1.5 mm thick on 19mm thk BWR board finished with blue shade high glass PU Coating on exposed portions inside edge finished with 1.0 mm thick high gloss laminate complete LED strip complete with driver will be provided as drawing complete . The top & side table will have glass of 10 mm thk. with 1" bevelling is also included in the rate				
	The exposed edges of the glass shall be finished with necessary grinding & mirror polish.				
	Telescopic CPU stand & key board. Tray shall be provided made out of 19 mm board. Laminate & ball bearing slides. All remaining exposed surfaces will be finished with Duco paint with melamine coating complete .Footrest made with T.W member of size 4" x 1 1/2" finished with Duco paint complete.				

Bidder's signature

	The drawer unit of Godrej, D-tel depository cabinet should be provided duly anchored to the floor/ sides with locking arrangements etc. complete.				
	Boxing made with 12mm thick plywood finished with Duco paint shall be provided below the table top for electrical conduit and at the bottom for the LAN cabling / Telephonic wire conduit. The item to include all necessary hardware & fittings in stainless steel finish to all edges & making provision only for electrical fitting. Counter no duly engraved in SS 304 Plate of size 10" x10" duly hanging form ceiling.				
	Counter as above in Running meter	RM	15.00		
61	Supply & fabricating fixing of (Size.- <b>(600mm X 750 mm) table/ counter in Lunch room</b> made out of 19mm BWR board top ,vertical supports , intermediate partition below. counter top shall be finished 1mm th. laminate.	No.	2.00		
62	<b>Repairing &amp; re-polishing of Dining table</b> - Re lamination of table top and re polishing by melamine polish with smooth finished over wooden surface including re sizing and replacing accessories as required, all complete as per direction of Engineer-in-charge/ Consultant.	No.	1.00		
63	Supply & fabricating fixing of <b>900mm Dia. wide table/ counter</b> made out of 19mm BWR board top, vertical supports, intermediate partition below. counter top shall be finished 1mm thk laminate.	No.	1.00		
64	Providing & Keeping <b>Side table</b> made out of 18/12 mm thick plywood & 6/12 mm thick the flexiPLY as per design. The top should be finished with edges of 2" thick the vertical support should be of 24" dia. Etc. complete with necessary hardware. The top surface with edges should be finished with 12 mm thk salt colour DuPont Corian solid surface etc. complete as per detailed drawing & instruction of Architect / engineer.	No.	7.00		
	<b>TOUGHENED GLASS WORK</b>				
65	12 MM TH. TOUGHENED GLASS Cabin door providing & fixing main doors/cabin made out of/cabin door made out of HNG/ Asahi India MAKE 12 MM TH. toughened plain glass in single piece with computerised diamond cut & diamond edge polish including making required cut-out holes for lock , handles , pivot patch fitting , corner fitting hinges etc. the rate is inclusive of patch fitting of DORMA make floor spring ,pivot patch fitting with cover plate locks handles , hinges with necessary hardware etc. as per instructions of Architect/Engineer.	sqm	20.00		
	<b>FINISHING WORKS</b>				
66	Providing & fixing wall paper on wall / partition as per approval of Architect & Engineer. Wall paper basic rate : Rs 1000/- per sqm	Sqm	7.00		

Bidder's signature

67	Providing & fixing in position '3M' make frosted glass film in stardust range fixed to glass as per pattern. Area of application to be measured as maximum length x maximum height of application on that particular piece of glass.	Sqm	20.00		
68	Providing & placing Decorative Painting framed with necessary beadings and glass as per Architect / Bank's Engineer approval Base price Rs.5000/-	Nos	5.00		
69	Providing and fixing Roller blinds of required width & Length quality of approved make fabric made of 100% polyester thickness 0.30mm with Acrylic coating resistance to Cracking & Fraying and treated for dust repellence, UV proof , virtually maintenance free having plastic bottom chain thickness of chain 0.50mm and diameter-3mm, weight per sqm 201g, Degree of opacity 100%, Light fastness 4/6, Plastic with metal bottom weight - 116.20mmX48.30mm and suitable coating on exterior, including all fixtures and fittings complete in all respect as per design/color/shade including requisite installation brackets etc as required for installation at site with anchoring arrangements complete as directed.	Sqm	45.00		
<b>MISCELLANEOUS WORKS</b>					
70	Providing and fixing <b>flush door</b> with 35mm water proof door with 1mm high glass laminate ( of approved shade ) on both sides The item includes 75C50mm TW choukhat , 7 lever mortise lock, SS handle, stopper hinges, paint/polish etc. complete	Sqm.	9.00		
71	Providing & fixing door closure of Godrej/ Dorma/ Ozone of two speed (heavy duty, light weight thin. Type code : 3976) as approved by etc.	No.	5.00		
72	Notice Board -600 X 1200 MM	No.	1.00		
73	Notice board - 600 x 457 mm	No.	1.00		
74	Providing & applying POP cornice over false ceiling & wall junction, Size- 75mm x 75mm triangular cross section, even & smooth finished, all complete as per direction of the Bank/ Architect.	Metre	75.00		
75	Providing & fixing second class teakwood wooden cornice over false ceiling & partition wall junction, Size-65mm x 65mm triangular cross section, with melamine polished, all complete as per direction of the Bank/ Architect.	Metre	125.00		
				<b>Total</b>	
<b>RUPEES .....</b>					

**NOTES :-**

The following tables available in the existing building of Circle Audit Office will be reused after Re-lamination, Re-polishing and shifting from, transportation with due care to new premises at LCPC building, Aliganj Extn.

**GM Table -01 No, CM Table -10 Nos, PS Table -01 No and Dining Table -01 No.**

Bidder's signature

=====E N D=====

Bidder's signature