

PRICE BID FOR INTERIOR FURNISHING WORKS AT AT 6th FLOOR OF LHO, POOJAPPURA					
S.No	Description	Qty	Unit	Rate	Amount
1	Tables 150X75X75	12	Nos		
	Dismantling and reinstaling the existing tables including keyboard tray, drawer units, CPU trolley etc in same floor to a new location as per the plan with necesssary minor repair works, The rate is inclusive of all material, labour charge, disposal of debris etc, complete.				
2	Side Tables 100X45X72.50	6	Nos		
	Dismantling and reinstaling the existing side tables in same floor to a new location as per the plan with necesssary minor repair works, The rate is inclusive of all material, labour charge, disposal of debris etc, complete.				
3	Partly glazed & partly solid partition 120 cm Ht.	72	Sq M		
	Supplying and installing double skin wooden partitions for a height of 75cm from finished floor level with 63.5x38.1x1.2 mm thick hollow Aluminium Sections of make Indal/Jindal for horizontals at floor level and 75cm ht. and verticals @ 75 cm c/c and 8 mm marine ply on both sides finished with 1mm laminate . Between 750 mm and 120mm level, 12 mm thick glass with etching pattern (permanent) fixed with necessary D brackets of make Dorma or equivalent of SS finish. The glass opening 'Jamp' portion is to be finished with laminate. The rate is inclusive of all material, labour charge, disposal of debris etc, complete.				
4	Cement Board partition	55	Sqm		
	The partitions are of double skin type. The partition should be firmly fixed on floor/ counter/ wall made out of aluminium section of 50x50x1.2 mm thick of INDAL/JINDAL as internal frame structure placed horizontally & vertically in 60x60 cm interval as shown in the drawing which is covered with 9 mm thick cement board on both sides and finished with one coat of putty and two coats of emulsion paint. The rate is inclusive of all material, labour charge, disposal of debris etc, complete.				
5	Dismantling Existing Cement Board Patition	70	Sqm		
	Dismantling existing Cement Board Partition and removing the debris as directed by the Engineer in charge. The rate is inclusive of all material, labour charge, disposal of debris etc, complete.				
6	Aluminium sliding window	12	Sqm		
	Supplying & fixing powder coated aluminum openable sliding windows and ventilators using aluminium 34 series z,j,gullian glacing clips section S,S friction hinges locking handles rubber beedings etc glazed with 4 mm clear glasses.				
7	Full Height Storage :	27	SqM		
	Providing and fixing Full height storage to detail about 450mm wide, comprising. 18 mm Plywood with 1 mm laminate for top, bottom, rear, sides and four intermediate with necessary TW reeper.All the edges shall be finished with 3 mm PVC edge Band				
8	Putty Painting	220	Sqm		
	Plain painting with one coat putty - Two coats of plastic emulsion paint to be applied on wall / ceiling using roller brush, after preparation of the surface after scrubbing and cleaning, applying one coat of primer and one coat of putty, including all staging work etc complete.				
9	Interior Painting	20	Sqm		
	Plain painting with one coat putty - Two coats of plastic emulsion paint to be applied on wall / ceiling using roller brush, after preparation of the surface after scrubbing and cleaning, applying one coat of primer including all staging work etc complete.				

10	False Ceiling Grid system	140	Sqm		
	Provide and fix false ceiling with 60 x60 cms size Armstrong/ Saintgobain/ USG / other approved makes 15mm thick accoustic mineral fibre boards with reveal edges, framework with Powder coated GI tee 25mm wide sections, all fittings and fixtures etc complete including providing cutouts for light fittings, AC diffusers, smoke detectors etc complete as per specifications.				
11	Cement Board partition with one side lacquered glass cladding	75	Sq.M.		
	The partitions are of double skin type. The partition should be firmly fixed on floor/ counter/ wall made out of aluminium section of 50x50x1.2 mm thick of INDAL/JINDAL as internal frame structure placed horizontally & vertically in 60x60 cm interval as shown in the drawing which is covered with 9 mm thick cement board on both sides and finished with one coat of putty and two coats of emulsion paint on one side and 4 mm lacquered glass cladding on other side. The work includes providing glass strip / mirror strips for the fixed partition & door, to match with the existing ambience of the premises.Necessary hardwares such as SS hinges, SS handles, 1 Nos godrej lock of approved make etc to be provided.. The rate is inclusive of all material, labour charge, disposal of debris etc, complete.				
12	Dismantling Existing Cement Board Patition with one side lacquered glass cladding	75	Sq.M.		
	Dismantling existing Cement Board Partition with lacquered glass cladding on one side wherever required and removing the debris as directed by the Engineer in charge. The rate is inclusive of all material, labour charge, disposal of debris etc, complete.				
13	Table - 140X60X75 cm	24	nos		
	Supplying and fixing table made out of 25mm marine plywood and finished with 1 mm thick laminate and exposed top edges lipped with 2mm thick PVC edgeband applied with hot melt glue and other edges with 0.5mm thick PVC edge band all round panel, hardwares like minifix powder coated clipboard screws, PVC right angle block, level adjustes, Keyboard tray made out of powder coated MS sheet mounted under the worktop with telescopic sliding channels etc. Foot rest are made of 18mm thick prelminate particle board with 0.5 mm PVC egde band knock down type bottom bush etc. 30cm wide and 15 cm height at one end and the other end is zero 50cm length on the bottom side of the table etc. complete.CPU stand is to be provided in the table. 12 mm thick glass is to be provided on table top and the edges of glass to be polished.				
14	Drawer Unit	24	nos		
	Supplying and fixing Drawer unit made out of 19mm thick marine plywood edgeband with 1mm laminate. 4 drawer pullouts mounted on sliders, with exposed edges lipped with PVC edge band 0.5mm thick central locking system for drawer pullouts (Ebco/Doorset/Hetich/Ozone), with bottom bush with necessary shutters to be provided.				
15	Door	4	nos		
	Dismantling the existing door and refixing the same at a separate location in the same floor as per the direction of Engineer in Charge.				
16	Dismantling and stacking usable items	1	LS		
	Dismantling and Removing the demolished items belonging to the branch and stacking the same at site identified by the Bank.				
17	Disposal of debris	1	LS		
	Disposing off the debris away from the site as per direction of Engineer in Charge.				
18	Gypsum Board Ceiling	10	SqM		
	Repairs / replace of existing Gypsum board false ceiling including two coats painting				
	TOTAL				
	GST extra				