

PRICE BID OF FURNISHING WORK OF KABATABANDHA BRANCH

No	Description	Unit	Qty	Rate	Amount
1	SWO Counter(5'x3'x2'6" and side unit of 3' to 3'6"x16"x30") : Made with 19mm MR grade BB table top, sides and 12mm thick ply on front modesty panel; with three equal depth drawer units (400x450 with depth as directed by engineer) with auto locking system, telescopic sliding channels, one PVC KBT, cable manager. Customer side shall be rounded with 6mm flexi ply (350 to 400mm depth) followed by 6mm ply duly supported on each side by a profile frame of 19mm BB and as directed by engineer. Round / curve shape shall be made after 3' width of table top. 12mm glass shall be provided at 2'6" distance thus leaving 6" for customer desk space. (Cost of glass shall be paid extra). All the exposed surfaces shall be finished with 1mm thick laminate bi-colour as directed by engineer.	No	3		
2	P&F 6mm thick white or frosty white colour Corian solid surface duly mirror polished and jointing base material with adhesives as per manufacturers specification to the satisfaction of engineer ; Make: Du point/ Marino/ Green / as approved	Sqm	12.00		
3	BM table 6'x3'00"x2'6"along with side unit of 18"x42": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side unit shall have one shutter with provision of storage units . All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be polished.	No	1.00		
4	Officers table 5'x2'6"x2'6"along with side unit of 18"x36": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side unit shall have one shutter with provision of storage units . All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be polished.	No	2		
5	Staff Table 4'x2 x2'6": Made with 19mm MR grade block board in table top, sides with one drawer unit of 400x450x150mm with one drawer along with sliding channels and one cup board with shutter. All necessary hardware, locks, hinges handles, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table units shall be polished. Edges shall be finished with 6mm teak wood lipping and polished for smoothness. Drawers shall be finished with lipping polished.	No	3.00		
6	Full height and Low height Partition: (64mm thick) Providing and fixing solid and glazed partition made with GI Channel section 50mmx25mmx0.55mm thick spaced at 600mmx600mm grid and duly finished with 6 mm MR grade ply and 1mm thick laminate (colour & shade approved by engineer as solid/ teak wood / texture premium quality on each side. The frame shall be properly anchored at true ceiling, wall/ column sides and floor with long screws at 900mm centres. The glass panel shall be 5.5 to 6 mm thick duly supported by 6 mm MR ply and finished with laminate.	Sqm	70		

7	Column and Wall panelling: P&F 12mm MR grade BB on all sides of column with full threaded screws and pasting 1mm thick laminated with premium quality textured finish bi colour as approved by engineer. Make: MDF interior grade: century/Green/ Kit ply, Laminate: Century/ Marino/Green/ equiv as approved.	Sqm	20.00
8	Wall panelling with Ply board: Providing and fixing 6mm ply on aluminium frame work 25x40x0.80mmthk box section on walls with screws anchored properly in line and level and finished 1mm thick laminate of approved colour and shade. Wooden clits shall be provided to make the frame in line and level (True plumb bob line). A teak wood beading shall be provided on wall panelling of 4 ' height (Top edge) duly polished).	Sqm	85.00
9	Wall panelling with Ply board on main entrance section (Glass section door): Providing and fixing 12mm ply on walls with screws anchored properly in line and level and finished 1mm thick laminate of approved colour and shade.	Sqm	15
10	Storage units 450mm deep: Made with 19mm MR grade Block board on all five sides and 6mm backing ply. Vertical separators shall be provided at each 3' Centres with door leaf of each shutter of 18" wide supported by auto closing hinges. All inside surface shall be finished with 0.80mm thick laminate. Exposed surface including shutter edges shall be finished 1mm laminate of approved shade. Hardware like locks, handles shall be provided.	Sqm	20
11	P&F 12.5mm thick Gypsum false ceiling of India Gypsum / Saint gobain make which includes G I perimeter channels , GI runners with perimeter of ceiling, screw fixed to brick work/ partition with the help of Nylon sleeves and screws at specified enters. Then suspending GI intermediate channels from the soffit at specified centres with ceiling angle fixed to soffit with GI cleat and steel expansion fasteners, ceiling section having knurled web etc complete. GI channels, runners etc shall be IS marked. Ceiling frame shall be rigidly fixed to the wall, RCC rigidly so that it will not fall down while fixing boards, providing lights, electrical cables, pipes etc.	Sqm	110
12	P&F modular grid PVC LAMINATED GYPSUM CEILING TILES of Indian Gypsum make/ saintgobai/equiv as approved of 600x600 x8mm as specified by manufacturer with black reveal groove channel . Installation to comprise main runner at 1200 centres fixed to structural outfits and peremeter channe as per manufacturers specification and it hall be rigidly fixed to the wall, RCC rigidly so that it will not fall down while fixing boards, providing lights, electrical cables, pipes etc. Provision shall be made for light fitting, fire equipment, CCTV equipment. Extra support shall be given if necessary as per site requirement.	Sqm	110
13	P&F 30mm thickness MR grade flush door finished with 6mm thick teak wood lipping on all edges duly polished, three SS Hinges for each door, one door stopper, one cylindrical lock per door finished with 1mm thickness laminates on both sides of approved shade and colour as approved.	Sqm	22
14	putty to wall and ceilings including gyp ceilings with a minimum of 1m thickness in a line and level and scrapping the surface to make it good adhesion for paints.	Sqm	500

15	Finishing the wall surface with tractor emulsion paint of Asian/ equiv as approved by engineer in charge with roller finish in two or more coats	Sqm	500		
16	Enamel paint with primer in two or more coats	Sqm	20		
17	P&F 12mm thick pre polished Toughned glass to swo counters and ATM	sqm	9		
18	P&F 12mm toughened glass in fixed position with patch fittings, duly supported at top, bottom and sides as directed by engineer with edge polish. Cost of extra member for fixing glass (Aluminium sections, ply, door frames shall be paid extra.	Sqm	10		
19	P&F 12mm toughened glass in Main entrance door with patch fittings , SS handles of 200mm duly supported by pivot at top and bottom with floor springs and top chord aluminium powder coated section as directed by engineer with edge polish. Cost of floor spring and alu section shall be paid extra.	Sqm	8		
20	P&F black color anodized aluminium glazed door with sections of 100mmx30mm wide stiles two nos)and 150mmx30mm wide lock rails (middles and 100x30mm rails top and borrom parts) and 6mm glass with gaskets,handles etc all accessoried etc complete	Sqm	2.3		
21	Aluminium fixed glazed panels with same specifiation as in item no 32	Sqm	5		
22	ACP panelling with 3mm thick ACP fixed with aluminium section of 25mx25mm to 40mmx25mm box sections of shade and colour as approved with all accessoried etc complete	sqm	60		
23	P&F frosted film of Garware make of approved design pattern, shade and colour to glass panels including cleaning glass panels etc complete.	Sqm	20.00		
24	P&F floor springs to glass door including cutting the floors (granite/ tiles/ concrete floors) and embedding the floor springs and grouting the area by approved tile adhesive matching with existing floors complete.	No	3.00		
25	P&F door closer two speed of Godrej/Dorma/Ebco/Dorset as approved with all accessories to the doors.	No	2		
26	P&F mortise lock with handles, with all fixed accessories (SS colour) to the doors. Make: Godrej/Dorma/ Dorset(Alpine series) as approved	No	4		
27	Supplying and Fixing Godrej Night Latch for SWO Doors outside opening 7 lever brown colour	No	2		
28	P&L 18mm thick granite of approved shade and colour for kitchen slab, basing counters, steps etc laid over 20mm thick base cement mixed with matching pigment epoxy touch up including rubbing, curing moulding etc complete	Sqm	6		
29	P&F aluminium section door with 6mm cement board as shutter including aluminium frame work, handles, etc complete for UPS room	sqm	2.10		
30	Foot rest made of 19mm ply as per engineers instruction	No	9		
31	CPU Trolley of ebco make	No	7		
32	P&F Zebra blinds of approved brand and colour in all windows and BM chambers of standrard make with all accessories	Sqm	16		
33	Preparation of in-built layout drawing & mentioning the dimension of partitions, counters, panelling and marking locational reference in the measurement sheet and submission of drawing in PDF format along with the bill	No	1	5000	5000

- 34 P&F pin up notice board made of 12mm backing ply duly laminated on one side and other sided sandwiched with 12mm soft board. The soft board is covered by a light blue fabric (Rs 250 per rm) and the stripped with teak wood lipping all-around include edges with hooks for hanging. *sqm* 1.20
- 35 Complain box of standar sizs 12"x16"x8" with shutters made with 19mm ply and laminates, locks etc complete No 2
- 36 Cover to electric panle roomwith 12mm ply and laminayes with 12m dia holes *Sqm* 6

Total cost excluding GST

5000

No	Material Recommended	Brand Recommended
1	Block Board, Ply, MDF, Flush door	Archid / Kitply/ Green ply ecotech MR / BWP / BWR as per item's Description
2	Zebra Blinds	Marvel, Vista, Deco
3	Gypsum ceiling	India Gypsum, Saint-Gobain,
4	Grid ceiling	Armstrong, Saingobain /India gypsum
5	Hardware fittings	Ebco, Godrej, Hettich, Hafle
6	Plumbing materials	Hindware, Parryware, Cera, Jaquar
7	Tiles	Johnson, Nitco, Kajaria, Somany,
8	Corian Solid surface	Marino, LG, Green
9	Miscellaneous materials	Engineer's Discretion

If required brands are not available, contractor may use other equiv brand available for use at site.