

Price Bid

Proposed revamping of seats at second floor C wing, SBI GITC CBD Belapur

Sr.no	Description	Qty	Unit	Rate	Amount
1	Carefully removing & shifting existing old modular Work station clearing the debris out of Banks premises	22.00	nos		
2	Providing and fixing of linear workstation made out with a combination of 18 mm thick MR plywood confirming to IS 303 of approved makes. The dimension of the workstation to be (1300- 1330mm *750mm) three sides covered by 1150 mm height partition and side credenza of size 450mm*450mm. The exposed sides of the tables to be finished with 1 mm thick plain or textured laminate of approved make and shades and internal surfaces to be finished with 0.7 mm thick laminate of approved make and shades. All vertical edge of the table & storage units should be finished by 19 mm wide PVC patti and no edge should be left sharp. Rate are inclusive of 1 nos cable manager and 600 mm wide aluminium power coated MS key board tray. All the edges of the MR plywood in contact with floor also to be provided with teak wood lipping of size 20 x 6 mm. complete the work as per site conditions and instructions of engineer incharge.	24.00	nos		
3	Providing and fixing of L-shaped workstation made out with a combination of 18 mm thick MR plywood confirming to IS 303 of approved makes. The dimension of the workstation to be (1300- 1330mm *750mm) three sides covered by 1150 mm height partition and side credenza of size 450mm*450mm. The exposed sides of the tables to be finished with 1 mm thick plain or textured laminate of approved make and shades and internal surfaces to be finished with 0.7 mm thick laminate of approved make and shades. All vertical edge of the table & storage units should be finished by 19 mm wide PVC patti and no edge should be left sharp. Rate are inclusive of 1 nos cable manager and 600 mm wide aluminium power coated MS key board tray. All the edges of the MR plywood in contact with floor also to be provided with teak wood lipping of size 20 x 6 mm. complete the work as per site conditions and instructions of engineer incharge.	24.00	nos		
4	Providing & Fixing new low height partition with Aluminium frame covered by 8 mm ply from both side, and surface finished with both side laminate, matched with existing surrounding after approval of shade from the Bank, along with wooden moulding at the top with suitable polish work complete as per site conditions and instructions of the Bank.	400.00	sft		
5	Providing & Fixing Soft Board with Cloth of approved make and colour (Size4.5"x1.3") complete the work as per site conditions and instructions of the Bank	300.00	sft		
6	Repairs to gypsum false ceiling if required as per the site conditions and instructions of the Bank	500.00	sft		
7	Providing and applying one or more coat plastic paint to walls, columns, ceiling etc on all surfaces after suitable surface preparation Putty, POP etc. complete the work as per site conditions & instructions of the Bank	6,000.00	sft		
8	Providing and fixing double charged vitrified tiles of Kajaria, Johnson, or equivalent etc. make (size 600mm x 600mm) flooring, matching with existing flooring in cement sand mortar (1:4) bedding including removal of existing damaged flooring, & removing debris out of Banks premises to NMMC approved dumping area etc. complete as per site condition & instructions of the Bank	200.00	sft		
9	Repairs to the column, storage with 1mm laminate after removal and shifting storage unit with matching laminate with the surrounding	1,000.00	sft		
10	Repairing, cutting and altering the existing L shaped existing table to linear table as per site conditions and matching finishing it with surrounding area & as per instruction of the Bank	2.00	Nos		
				Total :	
Plus 18% GST					