

SCHEDULE OF WORKS

S.No	Description	Qty	Unit	Rate	Amount
1	Providing and fixing 4"X2" and 3"X2" 16 gauge GI sections as per drawing for receiving ACP sheet.	250	Kg		
2	Providing and fixing good quality ACP sheets 3mm thk. over GI framework with necessary aluminium framework of size 1"X1" and 1.2mm thk. Proper fixtures to be provided at intervals and joints to be finished off with matching sealant.	50	Sq.M		
3	FALSE CEILING:				
	NOTE:The false ceiling area will be measured in flat area only.				
	Gypsum Board False Ceiling	50	Sq M		
	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising				
	Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids with 2 coats of plastic emulsion paint of approved color and one coat of putty over a coat primer etc, complete.				

4	<p>Supplying and fixing running counters 75cm ht.and 65 cm width inside the office room for given length. Each seat having width of 120cm. Each seat to have a computer key board tray, CPU stand, footrest etc.with seperations of 18mm py with 1mm laminate on both sides and along the front and sides of individual seats as per the <u>sketch</u> enclosed. Table top to be provided with 18mm marine ply finished with 1 mm laminate of approved make. 3 mm thick PVC Edge band to be provided on all exposed edges. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.</p>	8	Rmt.		
5	<p>Supplying and fixing running counters 75cm ht.and 75 cm width inside the office room for given length. Each seat having width of 160cm. Each seat to have a computer key board tray, CPU stand, footrest etc.with seperations of 18mm py with 1mm laminate on both sides and along the front and sides of individual seats as per the <u>sketch</u> enclosed. Table top to be provided with 18mm marine ply finished with 1 mm laminate of approved make. 3 mm thick PVC Edge band to be provided on all exposed edges. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.</p>	8	Rmt		
6	Officers Table	1	Nos.		
	<p>Providing and fixing Officer Table of size 1200 x 650 X 750 mm high to detail as shown in drg. Comprising table top out of 25mm thick Plywood Board post formed with 1mm thick flexy laminate of approved color and brand with both side half rounded edge and another two side edges with 3mm thick band strip.12 mm glass with edge rounded to be provided for the table top. Aqua blue shade of saint Gobain (or) equivalent toughened glass panel fixed on the 18mm thick to be fixed on front vertical laminated Plywood Board with SS studs.</p>				

	On front and side of drawer finished with 1mm thk laminate and additional 18mm Plywood is fixed on front side to pattern with necessary grooves and finished with 1mm thick laminate.				
	MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality .				
	One set of 4 drawers about 450mm wide, 712.5 mm high and 600mm deep to shape supported with 18 mm Plywood at bottom, sides and rear. 4 nos. of drawers out of which 3 nos. of equal height and 1 no. drawer at the top most of 75mm high made out of 12 mm thick				
	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach beading polished to the satisfaction of the Bank. The inside faces of drawer should be waxed and finished with varnish of app color and shade				
7	High Level Storage :	3.5	Sq.M		
	Providing and fixing high level storage to detail as shown in the drg. Size about 450mm wide, 210mm high comprising. 18 mm Plywood for top, bottom, rear, sides and One intermediate with necessary TW reeper. The unit top shall be with 25mm thick Plywood Board of approved make with 1mm thickness flexy laminate of approved color and brand with front side half rounded edge and all the edges and all the three sides with 3mm thick band strip.				
	Exposed faces of Plywood at top and sides of unit to be finished with 1mm thick laminate of approved color and shade.				
	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved color and shade.				
8	Custom Made Low Height Partition:	20	Sq.M		
	Providing and fixing in position of custom made low height partitions of the height 1500 mm as per shape shown in the drawing. ie. (750mm solid partition and 750mm glass above)				

	Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure vertically and 3 nos. horizontally of the same section at floor level, 750mm level and at 1200mm level. Same size at 375 mm level all framed and fixed in position, 8 mm Plywood of approved quality finished with 1mm Laminate with grooves on both sides of approved color and shade. Top of the partition finished with laminate and 12mm thick glass with etching is fixed over the partition with Dorma make (or) Equivalent make 'D' bracket of SS finish of 12mm thick. Around the partition 75mm thick Dark color laminate is provided as show in the drawing and pattern.				
9	Vitrified Tile Flooring – Providing and fixing best quality doubly charged 60cmX60cm white vitrified tile over existing vitrified tile flooring (only in Banking Hall as per instructions of EIC) after necessary preparatory works over it with T5 grade tile adhesive and pointing with approved quality compound, cleaning the surface after laying including labour charges, transportation of materials etc. complete. Baic price of tile Rs.60/sq.ft.	50	Sq M		
10	Applying two coat of emulsion for the walls in banking hall	55	Sq M		
GRAND TOTAL (EXCLUDING GST)					

* GST as applicable will be paid extra