SCHEDULE OF QUANTITIES FOR AIR CONDITIONING WORKS AT STATE BANK OF INDIA, AT IST FLOOR LCPC BUILDING FOR SHIFTING OF CAO LUCKNOW

<u> </u>	BUILDING FOR SHIFTING O			
	AIR CONDITIONING (Super Energy efficient AC)			
1	Supply of Ceiling mounted Cassette type AC machines with cordless remote. Indoor and outdoor in specified capacity as detailed condensing unit shall be complete thermatically sealed with rotary compressor, air cooled condenser with fan evapo- rative unit shall consist of a fan section with dynamically bal- anced centrifugal fan driven by FHP motor, multi rows deep cooling coil of copper tubes with aluminium fins. the evapor-ing unit shall be equipped with synthetic fiber filter, insulated drain pan, safety control thermostat complete in all respects. 5 star Make following below mentioned technical qualification. Power Supply : 1 Phase, 220-240 Volt or 3-phase 400V, 50 HZ Cooling capacity rated : 10.40-10.60 Kw ISEER Rank- 4.51/4.37 Rated Power Consumption : 2420-3140 watts Compressor Type : Twin Rotary / Rotary Refrigerant : R-32/ R410 A Comprehensive Product warranty : 3 Years Compressor Warranty : 5 Years			
a	Minimum 3.0 tr /4 HP Cassette Split Inverter AC as per above mentioned Specification (Hitachi/Toshiba/ Daikin/ Mitsubishi Heavy Electrical/O General/Voltas/ Bluestar/ Carrier)	Nos.	9	
2	Supply of HIGH WALL mounted SPLIT INVERTER AC ma- chines with cordless remote. Indoor and outdoor in specified capacity as detailed condensing unit shall be complete thermat- ically sealed with rotary DC Invertor compressor, air cooled condenser with fan evaporative unit shall consist of a fan sec-tion with dynamically balanced centrifugal fan driven by FHP motor, multi rows deep cooling coil of copper tubes with alu-minium fins. the evaporing unit shall be equipped with syn-thetic fiber filter, insulated drain pan, safety control thermostat complete in all respects. Copper condenser coils and Copper cooling coils company provided copper refrigerant pipe complete in all respects. 5 star Make following below men-tioned technical qualification. Power Supply: 1 Phase, 220-240 Volt, 50 HZ Cooling capacity rated full/ Half : 3.5-3.7 Kw/ Tonne Rated Power Consumption : 925-1150 watts/ tonne Annual Power Consumption : 525-600 kWH/ Tonne ISEER : 5-5.2 Star Rating : 5 Star Voltage Range: 187-265 Volt Operating Voltage : 5.5-7.0 amps Compressor Type : Hermetic Rotary / Rotary/ Hyper Rotary/ Swing			
	Refrigerant : R290 or R410 A or R32 Operating Range: *CDB : 16/18-52 Operating sound Indoor: 48-52 DB Operating sound Outdoor: : 55-58 DB Comprehensive Product warranty : 3 Years Compressor Warranty : 5 Years			
a	Minimum 2.0/1.8 tr High Wall Split inverter AC (Hitachi/ Daikin/ Mitsubishi Heavy Electrical/O General/Toshiba/Voltas/ Bluestar/ Carrier)	Nos.	4	
b	Minimum 1.5 tr High Wall Split inverter AC (Hitachi/ Daikin/ Mitsubishi Heavy Electrical/O General/Toshiba/ Voltas/ Bluestar/Carrier)	Nos.	3	

	1			r	
	· · · · · · ·				
3	Installation			-	
а	Installation, testing and commissioning of above specified cassette		-		
	type air-conditioner with wall cutting/ mounting including making	Nos.	9		
	good of damages complete in all respects.				
b	Installation, testing and commissioning of above specified hi wall				
	type air-conditioner(including old Acs) with wall cutting/	Nos.	9		
	mounting including making good of damages complete in all	1403.	,		
	respects.				
4	Copper refrigerant pipe				
а	P & F Copper refigerant piping for split units duly insulated with				
	elastometric nitrile rubber tubular insulation (9mm) between each				
	set of indoor & out door unit (suction and discharge) for above				
	mentioned cassette units to interconnect indoor unit and outdoor				
	unit, relevant sizes as per manufactures specifications including	Rmt.	220		
	cutting and chiselling and repairing of wall / designated areas	KIIII.	220		
	complete fine finish.(MAKE :Padliwal/ Hitachi/Totaline/ Met				
	Tube/ Diamond/ Star/ Camipro.) suitable for upto 3.0 Tr capacity				
	Tube/ Diamonu/ Star/ Campro.) suitable for upto 5.0 11 capacity				
b	P & F Copper refigerant piping for split units duly insulated with				
	elastometric nitrile rubber tubular insulation (9mm) between each				
	set of indoor & out door unit (suction and discharge) for above				
	mentioned Hi wall split units to interconnect indoor unit and				
	outdoor unit, relevant sizes as per manufactures specifications				
	including cutting and chiselling and repairing of wall / designated	Rmt.	130		
	areas complete fine finish.(MAKE: Padliwal/ Hitachi/Totaline/				
	Met Tube/ Diamond/ Star/ Camipro.) suitable for upto 2.0 Tr				
	capacity				
5	Communication wire				
а	Supply, installation, testing and commissioning of inter				
	connecting wiring/ cabling between indoor and outdoor of				
	Cassette AC (power supply will be made available at the outdoor				
	unit, please quote accordingly) in concealed manner with	Rmt.	240		
	chiseling either on wall or under floor including making good of				
	damages with plaster, putty and paint.				
b	Supply, installation, testing and commissioning of inter				
	connecting wiring/ cabling between indoor and outdoor of hi wall				
	split AC (power supply will be made available at the outdoor unit,			1	
	please quote accordingly) in concealed manner with chiseling	Rmt.	150		
	either on wall or under floor including making good of damages				
	with plaster, putty and paint.			1	
	* · · · * · · · · * · · · ·				
6	Drain Pipe				
а	P & F INSULATED condensate drain water piping flexible PVC				
	with all bends, junctions and accessories approved make duly				
	insulated to nearest drain trap including cutting and repairing the	Rmt.	100	1	
	wall to the existing situation complete - 32mm dia. (Kissan/				
	National/Supreme/Finolex/Prakash)			1	
	P & F INSULATED condensate drain water piping flexible PVC			1	1
Ь			1	1	1
b					
b	with all bends, junctions and accessories approved make duly	Rmt	100		
b	with all bends, junctions and accessories approved make duly insulated to nearest drain trap including cutting and repairing the	Rmt.	100		
b	with all bends, junctions and accessories approved make duly	Rmt.	100		

7	P & F MS stand (A.C.) for condenser made of as design MS angle section fixed on the wall complete with welding. Grinding and painting with redoxide paint complete (all above AC)			
a	MS stand 'L' angle frame or terrace/wall mounted company make for Casseette AC	Nos.	9	
b	MS stand 'L' angle frame or terrace/wall mounted for hi wallAcs	Nos.	9	
8	P & F VOLTAGE STABLIZERS with 3 step relay and TDR with input voltage range of 140-280 and output to be 230 v (MAKE: Servel/ V Gaurd/ Marc/ Inmag/Microtek/ Servocon) copper winding stablizers			
i	7.5 KVA	Nos.	9	
ii	5 KVA	Nos.	4	
iii	4 KVA	Nos.	5	
9	Dismanteling of 1.5 Tr split AC from existing premises of CAO including gas backing, shifting and re-installtion at new location with servicing, necessary repairs, if any and gas refilling.	Nos.	2	
	Total			
				Including GST

Note: Rates are considered inclusive of all including GST. However, bill is to be raised showing GST at prevalent rates/ rules.