

PRICE BID FOR INTERIOR & FURNITURE WORK AT					
STATE BANK OF INDIA, NEW GUEST HOUSE, TEZPUR, ASSAM					
SI.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	<p>Fabricating and fixing <b>Wall Panelling in VIP Rooms at walls behind beds</b> (Room No. 1,3 &amp; 4) with 12 mm thick ply finished with not less than 1 mm thick laminate over aluminium framework made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. Framework to be secured to wall surface / column surface. Back of 900 mm height from Bed top level Bedroom Headrest wall.</p> <p>Ply/Block Board Make: BWP Grade of Century/ Green/Gattani/ or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/ or equivalent (Wooden texture colour as per Bank's direction)</p>	SQM	25.00		
2	<p>Providing and fixing suspended 12 mm thick <b>Gypsum Board False Ceiling</b> with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include making necessary design,pattern &amp; cut outs for light fittings, tray cove light etc. complete as per design and Bank's direction. The rate also includes ceiling to be painted with minimum two coats of plastic emulsion paint including base preparation. etc. complete.</p>	SQM	193.00		
3	<p>Fabricating and fixing <b>Wall T.V. unit 1000 mm x 2100 mm size</b> with two drawers &amp; one open box as per design, 12 mm thick ply finished with not less than 1 mm thick laminate, over framework made out of 50 mm x 25 mm x 1.2 mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall, in bed room. All internal surface will have min. 0.80 mm thick balancing laminate. The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, etc.</p> <p>Ply/Block Board Make: BWP Grade of Century/ Green/Archid or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/ or equivalent.</p>	SQM	10.00		
4	<p>Providing and fixing at site <b>Full Height Cub-board/ Storage Cabinet</b> fully covered from all sides with <b>size 450 mm (W) x 2100 mm (H)</b> including necessary shelves as per the design and specifications with openable shutters made up of 18 mm BWP ply. The rear portion is to be closed with 0.8 mm ply. Front of the cabinet is to be finished with 1.0 mm thick laminate &amp; inside 8mm laminate with approved pattern with different colour laminated finish of approved shade &amp; colour with Proper Steam Beach moulding, beadings, and different colour laminate as per pattern in shutters and in skirting strictly as per the design, pattern, including all necessary fittings, such as locks,handles, magnetic cature. The cost shall include all materials, labour, accessories etc complete.</p> <p>Ply/Block Board Make: BWP Grade of Century/ Green/Archid or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam or equivalent.</p>	RM	6.00		
5	<p>Providing and fixing <b>Storage Units under Kitchen Granite Slab of size 600 mm (W) x 750 mm (H) as Modular units</b>, made up of 19 mm thick block board of approved brand on top &amp; vertical support and finished with not less than 1 mm thick laminate of approved brand on side and top. The storage units shall have <b>telescopic drawers, openable and sliding shutters</b> at alternate location for given length made up of 19mm thick plywood and finished in 1 mm thick laminate of approved shade along with SS base mesh. The storage units shall have intermediate horizontal and vertical shelves made in 19 mm thick plywood. All exposed edges to have teak wood lipping/bidding of requierd size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish 0.8 mm laminate. The works to include all hardwares such as: castors, brass hinges, ball catchers, handles, drawer channels etc. of Godrej or approved make.</p> <p>Ply/Block Board Make: BWP Grade of Century/ Green/Archid or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/ or equivalent</p>	RM	10.00		
<b>Total Cost (Excluding GST)</b>					