SR. No.	Description of Item	Unit	Qty	Rate	Amount
NO.				Rs.	Rs.
A)	PART 'A'				
Í	Variable Refrigerant Volume (VRV/VRF) System				
	Supply, Installation, Testing and Commissioning of Variable				
	refrigerant volume type air-conditioning system suitable for				
	cooling using 100 % Fully Inverter compressors based of R-				
	410A refrigerant gas complete as per specifications with the				
	condensing unit shall be complete with refrigeration				
1	compressors, condenser coils, electronic expansion				
	valve, solenoid valves, 4 way valve, shut down valves, service ports, accumulator and all other				
	components which are essential for safe and satisfactory				
	operation of the system.				
	The ODU shall have maximum external static pressure 80 Pa				
	to achieve installation flexibility. ESP must be selectable in				
	minimum 3 steps to select as per requirement to optimize				
	energy, capital cost, building aesthetics & noise level. Outdoor				
	unit heat exchanger coil should be accommodated within 3				
	sides of outdoor unit. The 4th side to be freely available for				
	ease of maintenance and safety of the person.				
	VRF system shall have auto Restart function i.e. In case of				
	power failure, units should restart automatic when power resume.				
	VRF system shall have auto bypass i.e. If any one IDU have				
	any electric or PCB failure, rest of the system should continue				
	to operate.				
	The VRF system shall have three phase technology, which				
	shall correct phases automatically in case of phase reversal.				
	The VRF has above 3.5 cop at 100% load @35 deg c outside				
	and 27 deg c inside				
	Units shall be provided with builting microproseser control				
	panel, for automatic opration capacity control machine shall be shuitable for working BMS system.				
	It should be with latest technology and highest efficiency unit.				
	in should be with latest teenhology and highest emolency unit.				
	MAKE: DAIKIN/ HITACHI /MITSUBISHI ELECTRIC /MITSUBISHI HEAVY /O GENRAL / TOSHIBA				
1.1	Supply of Outdoor Unit				
	Supply of 24 HP Unit ( ODU combination as per OEM	NL	4.00		
1.1.1	technology)	Nos.	1.00		
1.2	Supply of Indoor Unit				

SR.	Description of Item	Unit	Qty	Rate	Amount
No.					
				Rs.	Rs.
а	<b>4 Way Round/Reguler Flow CASSATTE TYPE</b> Indoor Unit with fittings,Consisting of fan,Four speed motor,Panel,coil section with DX coil, outer cabinet,filter,insulated drain pan(with inbuilt drain pump),provision for fresh air,Including all accessories etc.				
1.2.1	4.0 TR CASSETTE UNIT	Nos.	3.00		
1.2.3	2.4 TR CASSETTE UNIT	Nos.	2.00		
b	Hi Wall Split Typr INDOOR UNIT withIncluding all accessories etc.				
1.2.4	1.6 TR HI-WALL TYPE SPLIT UNIT	Nos.	4.00		
1.2.5	0.8 TR HI-WALL TYPE SPLIT UNIT	Nos.	2.00		
1.3	CORDLESS REMOTE CONTROLLER with Receiver kit				
1.3.1	CORDLESS REMOTE CONTROLLER with receiver kit for Cassette & Hi-Wall Split	Nos.	11.00		
1.4	REF NET joints and Accessories				
1.4.1	Ref-Net joints and Accessories for IDU & ODU	Pair	11.00		
1.5	Supply and Installation of Drain Pump for Split AC	Nos.	2.00		
	TOTAL PART 'A'				

SR.	Description of Item	Unit	Qty	Rate	Amount
No.				Rs.	Rs.
				1.3.	113.
B)	PART 'B'				
1	Refrigerant Piping and Ref Joint				
	All detailed drawings should be made by the vendor as Mfg. Company norms. Work shall be started after the submission of the drawing by the authorized person of Mfg. Company with covering letter				
	Supply & Installation of interconnecting Refrigerant copper pipe size approved by O&M Comapny,insulated with <b>19 mm</b> thick closed cell electrometric nitrile <b>class 'O'</b> type rubber tubular insulation between each set of indoor & outdoor units ,all piping inside the room shall be properly fixed/supported with suitable size of clamp/ M.S. hanger and all external/ exposed to sun piping shall run in M.S. painted cable tray etc. as required.				
2.1.1	Supply and Installtion of approved Copper Pipe with Insulation as per the specifications, The piping Length will be measured as single length (Indoor to Outdoor)		195.00		
2.1.2	Installation, testing and commissioning of All REF NET joints and Accessories with insulation for above VRF/VRV System (All the Insulation joint must be covered with aerotape.)		1.00		
2	Drain Piping				
2.2.1	Supply & Installation of <b>32/25/19/12 MM</b> Rigid UPVC piping complete with fittings and supports	RMT	150.00		
3	Control & Transmission Wiring				
2.3.1	Providing & fixing control cum transmission wiring of 3 core x 1.5 sqmm Shielded/Seathed flexible control cable between indoor and outdoor unit as per the specifications with necessorry supports and shall be run in pvc conduit.		205.00		
4	MS Stand for Outdoor Units				
2.4.1	M.S Structure duly epoxy painted for installing above VRF outdoor unit, TFA, Split and TFA ODU/Condensor unit on MS HEAVY STURCTUE With MIN. 75 x 40 mm Channel with Angle and Supports including if Scafolding at Basement.		150.00		
5	Installation, Testing & Commissioning of VRV System				
	Handling, lifting & shifting, and installation of all indoor & outdoor units at the site with required anchor bolts, gi threaded rod, etc. As per the site requirement and approved drawing by architect/consultant				
	Pressure testing of complete copper piping network @2 times of working pressure for 24 hours to ensure leakproof piping				

SR. No.	Description of Item	Unit	Qty	Rate	Amount
				Rs.	Rs.
	Reqd. Refrigerant gas charging & topping up as per indoor, outdoor capacity, additional copper piping (additional gas charging sheet should be attached in handing over the report)				
2.5.1	Outdoor Units of 24 HP with all connected indoor Units as per Approved Drawing	lot.	1.00		
6	Civil Work				
2.6.1	MISC. CIVIL WORK LIKE WALL JURRY, R.C.C WALL / SLAB / BEAM CORE CUTTING/ CUT OUTS TO PASS DUCTS & PIPES AND RE FINISHING OF THE SAME TO THE ORIGINAL FINISH	lot.	1.00		
	TOTAL PART 'B'				
	Total PART 'A + B'				