

STATE BANK OF INDIA
SCHEDULE OF QUANTITIES

PRICE BID FOR COMPOSITE INTERIOR WORKS INCLUDING INTERIOR FURNISHING, ELECTRICAL, VOICE & DATA CABLING, FIRE FIGHTING/ALARM/EXTINGUISHER SYSTEMS AND CCTV & SECURITY SYSTEM WORKS FOR LOWER GROUND FLOOR, STILT FLOOR & FOURTH TO FIFTHTEENTH FLOORS OF LHO BUILDING AT KHARADI, PUNE.

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	PART-I : INTERIOR FURNISHING WORKS				
	<p>Preamble:</p> <p>A) The quoted rate should include cost of necessary scaffolding, staging, centring, shuttering etc. as required for execution of the job at any height and location including removal of same. The scaffolding should be erected and anchored into the concrete members with help of expandable bolts, which are to be cut as the scaffolding is removed, no wall is to be punctured, at no extra cost to the Bank. Also, all the holes created needs to filled properly before handing over the project.</p> <p>B) Contractor has to make arrangements at his own cost to tie a safety net around the work so that loose material does not cause damage to the property or any human being, if necessary.</p> <p>C) Contractor has to make arrangements at his own cost to cover entire existing surface/ materials with Hessian cloth curtains so that does not cause any damage to the existing structures/ materials and even take care of dust control and carefully removing them complete.</p> <p>D) Contractor has to make arrangements at his own cost to cover entire existing flooring to avoid any damage. In case of any damage caused, contractor is liable to replace the damaged floor at their cost.</p> <p>E) Necessary care to be taken to avoid any damage to the existing facade, fittings, toilets etc. Any damage caused needs to be replace at Contractor's cost.</p>				
	<p>F) Rate for full height partition to include the cost of framework above false ceiling as required to fix the same to the ceiling slab for which no extra payment shall be made and the rate quoted shall be inclusive of the same. Measurement of Partition & Panelling shall be limited upto the False Ceiling level. However the cost towards frameworks to be continued upto the main ceiling shall be deemed to have been considered in the quoted rates and no separate payment shall be made for the framework or supporting elements of partitions / panelling items, above the false ceiling level unless directed by the Architect / Site Engineer to extend the partition up till the ceiling.</p> <p>G) The rate shall be all inclusive of the necessary hardware, fittings, fixtures & including glass & finishing for the same. The fittings needs to be got finalised by the Architect / Site Engineer before procuring the same. The rate shall be also inclusive of pattas & bands, grooves at any level, any design in veneer, textures etc including the necessary framing/ openings for Electrical, Telephone & AC outlets. Further it is important to note that the Glasses wherever specified for the items of Partitions & Panelling if any shall have bevelled edges as per the direction & thickness as indicated by the Architect or Engineer in charge.</p> <p>H) The Brand should use as per Approved makes given and all Rate shall include scaffolding hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	I) The quoted rate should include cost of preparation of required drawings, completion reports, test reports etc and its submission to Central Electricity Authority (CEA) / Electrical Inspectorate / PWD/ MSEDCL / MIDC for getting approval, arranging their inspection and obtaining of Energisation Sanction Order / final approval for the electrical works of the entire building (15 floors + Stilt Floor + Lower Ground Floor). Also Charges for preparation of Fire alarm / Fire fighting / Fire extinguisher layout drawings for all the floors (Lower ground Floor, Stilt floor and 1 to 15 floors) of the building, completion reports etc and submission to the Chief Fire Officer, MIDC, Mumbai, Maharashtra and obtaining their final approval with all fire safety related works J) Charges for preparation of floor wise data cabling lay out drawing, providing framed (with glass) copies of the same in corresponding floor wise server rooms. Original drawings of all the floors should be submitted to the Bank. After completion of the work, vendor needs to provide 25-year warranty certificate from OEM				
	K) Charges for preparation of CCTV layout drawings of all floors and providing the glass framed copies of the same in the control room, providing Original Drawings, Warranty certificates/Operating manuals of all CCTV equipments to Bank complete. Statutory Charges if any payable in the name of the Bank will be reimbursed on production of Original receipt.				
A	PARTITIONS				
1	SINGLE / DOUBLE SKINNED ALMUMINIUM PARTITIONS (LINEAR)				
1.1	ALMUMINIUM PARTITIONS: Providing and fixing 76 mm thick partition, frame work in 50 X 50 X 1.2 mm Aluminium sections placed at 600 mm center to center both ways (horizontal & vertical) fastened to floor/ceiling using and side vertical boxing with single layer of Ply/Bison/veneer/HDHMR MDF on either side as per architect detail design & drawing.				
a	Aluminium Framing for Linear partition	5,186.00	SQM		
b	Aluminium framing same as above but using 50x25x1.2 mm sections for wall/coloumns panelling	4,625.00	SQM		
c	Horizontal Aluminium Framing for False Ceiling 50x25x1.2 mm	752.00	SQM		
1.2	SKINNING The skins are to be screwed/pasted using suitable size screws/ approved adhesives on to the frame/wall/Coloumn etc as per the directions of Site-Engineer/Architect. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.				
a	Skinning on existing frame with single layer of 9 mm MR Ply	14,019.00	SQM		
b	Skinning on existing frame with single layer of 12 mm MR Ply	110.00	SQM		
c	Skinning on existing frame with single layer of 18 mm MR Ply	110.00	SQM		
d	Skinning on existing frame with single layer of 18 mm Bison board	50.00	SQM		
e	Skinning on existing frame with single layer of 18 mm HDHMR MDF & VEINS COAT BEVELLING and finished with Duco polish	127.00	SQM		
f	Skinning on existing frame with single layer of 12 mm HDHMR MDF & VEINS COAT BEVELLING and finished with Duco polish	33.00	SQM		
g	Skinning on existing frame with single layer of 6 mm HDHMR MDF & VEINS COAT BEVELLING and finished with Duco polish	33.00	SQM		
1.3	Finishes The skins are to be screwed/pasted using suitable size screws/ approved adhesives on to the Ply/HDHMR/Bison/Wall etc as per the directions of Site-Engineer/Architect. The rates shall be inclusive of supply , fixing , carting and finishing/polishing/sanding etc as per drawings and instructions of site-engineer/Architect. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
a	Finishing on existing Ply Partition using 4 mm thick veneer with necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of Semi-matt melamine polish. Basic Cost of veneer - Rs 1250/SQM	1,463.00	SQM		
b	Finishing on existing Ply for ceiling using 4 mm thick veneer with necessary groves/patterns/curves as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of Semi-matt melamine polish. Basic Cost of veneer - Rs 1250/SQM	783.00	SQM		
c	Finishing on existing Ply using 4 mm thick veneer with necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of minimum 1 mm thick PU polish. Basic Cost of veneer - Rs 1250/SQM	190.00	SQM		
d	Finishing on existing Ply using 4 mm Fluted Veneer of approved make and shade. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of Melamine polish. Basic Cost of veneer - Rs 3000/SQM	1,260.00	SQM		
e	Finishing on existing Ply using 4 mm Fluted Veneer of approved make and shade. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of minimum 1 mm thick PU polish. Basic Cost of veneer - Rs 3000/SQM	193.00	SQM		
f	Finishing on existing Ply using 1 mm laminate of approved shade. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. Basic Cost of Laminate - Rs 700/SQM	5,263.00	SQM		
g	Finishing on existing Ply using 1.25 mm Fluted laminate of approved shade. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. Basic Cost of Fluted Laminate - Rs 850/SQM	110.00	SQM		
h	12.5 mm Gypsum skinning. The rate shall be inclusive of making the smooth surfce for application of skins as per architct	867.00	SQM		
i	POP Fluted in double height lobby. The rate shall be inclusive of making the smooth surfce for application of skins as per architct	238.00	SQM		
j	Supply and Installation of POP moulding strip and finishing the same with paint as per architect.	300.00	RMT		
k	Supply and Installation of wooden moulding strip and finishing the same with melamine polish as per architect.	83.00	RMT		
l	Supply and Installation of Veneer L in ceiling of size up to 300x200. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect.	123.00	RMT		
m	Fluted Veneer in Ceiling (double hegiht Lobby). The rate shall be inclusive of melamine polish.). The rate shall be inclusive of making the smooth surfce for application of skins as per architct. Basic Cost of veneer - Rs 3000/SQM	72.00	SQM		
n	Finishing on existing Ply partition using Leatherite of approved shade. Leatherite to be cladded in grid pattern as per design. Cost to be inclusive of MDF and Foam backing for Leatherite. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. Basic Cost of Leatherite - Rs 500/meter	762.00	SQM		
o	Leatherite Cladding on Ceiling. Leatherite to be cladded in pattern as per design. Cost to be inclusive of MDF and Foam backing for Leatheriteite, fixing adhesives, hardware etc. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. Basic Cost of Leatherite - Rs 500/meter	227.00	SQM		
p	Finishing on existing Bison/Ply/Framing using Onyx stuck on Acrylic Sheet for Back lights with all hardware / acrylic etc of approved shade as per the drawings and instructions of site-engineer/Architect. Basic cost of onyx - Rs 10000/sqm	77.00	SQM		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
q	Finishing on existing Partition using Marble with hardware / Adhesives etc of approved shade as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of buffing / polishing Basic rate of marble Rs. 3500/Sqm	321.00	SQM		
r	Finishing on existing Ply using Pin up Board/ Soft Board of 12 mm thickness wrapped around with Fabric of approved shade and make as per the drawings and instructions of site-engineer/Architect.	231.00	SQM		
s	Supply and installation of 12 mm Acoustic Panels (laser cut as per design) for reducing and controlling Reverberated noise with a NRC of 0.50, Panel composition 100 % pet to be minimum 50% Recycled PET with LOW VOC and greentag Level A certification which addresses life cycle impacts such as Toxicity.1550gsm, Density 194kg/m3. Fire Test AS / NZS 1530.3., IOW VOC AND GREEN TAG CERTIFIED, Usage Screens wall & Ceilling Panels.cost to be given for Printed as per architects design. The panels to be fixed over base partition.	77.00	SQM		
t	Finishing on existing Ply using 6 mm thick Solid Acrylic surface/corian. The rate shall be inclusive of Thermoforming and buffing. Acrylic epoxy adhesive cost to be inclusive in the rate. Polishing of All exposed surafce to be done so that there will be no joint visible as required by Architect. For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted. Basic Cost of Solid Acrylic surface/corian - Rs 6500/SQM	11.00	SQM		
u	Finishing with 6 mm thick lacquered glass with all adhesives and hardware as per architect/site - Engineer Basic cost of glass Rs. 2000/Sqm	939.00	SQM		
v	Finishing using 8 mm Mirror on existng ply with all necessary hardwares & adhesives. The rate shall be inclusive of beveling and edge beading. Basic Cost of Mirror Rs. 1500/Sqm	288.00	SQM		
w	Finishing on Existing Surface using Fluted PVC Panels of approved make & thickness LOUVERS ON VERTICAL SURFACE Providing, supplying & fixing 10 mm thick Charcoal/ PVC based Louvers of approved shade with the required groove pattern as approved by the Client on the vertical surface on the predetermined locations. Placing louvers on the 9 thick MR plywood with the approved adhesive so as to fix them properly on the board. The item to include cutting required for electrical DB, MCB, sockets,switches etc. The item to also include wastage of materials and measurement to be done of the visible surface. Basic cost of PVC panel - 1050/SQM	1,471.00	SQM		
	Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.				
	Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.				
2	SINGLE / DOUBLE SKINNED ALMUMINIUM PARTITIONS (CURVED)				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
2.1	ALUMINIUM PARTITIONS: Providing and fixing 50 mm thick partition, frame work in 50 X 25 X 1.5 mm Aluminium sections placed at 600 mm center to center both ways (horizontal & vertical) fastened to floor and side vertical ply boxing with single layer of Ply/Bison/veneer/HDHMR MDF on either side as per architect detail design & drawing. Cost to include hard wood beadings with melamine finish wherever required as per design.				
a	Aluminium Framing for Curved partition	1,318.00	SQM		
b	Aluminium framing For Flase ceiling	55.00	SQM		
2.2	SKINNING The skins are to be screwed/pasted using suitable size screws/ approved adhesives on to the frame/wall/Column etc as per the directions of Site-Engineer/Architect. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.				
a	Skinning on existing frame with single layer of Flexible 9 mm MR Ply	2,074.00	SQM		
b	Skinning on existing frame with single layer of Flexible 12 mm MR Ply	55.00	SQM		
c	Skinning on existing frame with single layer of 18 mm Bison board	215.00	SQM		
d	Skinning on existing frame with single layer of 9 mm HDHMR MDF	211.00	SQM		
2.3	Finishes The skins are to be screwed/pasted using suitable size screws/ approved adhesives on to the Ply/HDHMR/Bison/Wall etc as per the directions of Site-Engineer/Architect. The rates shall be inclusive of supply , fixing , carting and finishing/polishing/sanding etc as per drawings and instructions of site-engineer/Architect. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.				
a	Finishing on existing Ply Partition using 4 mm thick veneer with necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of Semi-matt melamine polish. Basic Cost of veneer - Rs 1250/SQM	132.00	SQM		
b	Finishing on existing Ply using 4 mm Fluted Veneer of approved make and shade. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. The rate shall be inclusive of minimum 1 mm thick PU polish. Basic Cost of veneer - Rs 3000/SQM	523.00	SQM		
c	Finishing on existing Ply using 1 mm laminate of approved shade. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. Basic Cost of Laminate - Rs 700/SQM	138.00	SQM		
d	Finishing on existing Ply partition using Leatherite of approved shade. Leatherite to be clad in grid pattern as per design. Cost to be inclusive of MDF and Foam backing for Leatherite. Making of Necessary groves/patterns as per the drawings and instructions of site-engineer/Architect. Basic Cost of Leatherite - Rs 500/meter	77.00	SQM		
e	Finished with leatherite fixed with foam backing on protruded openable 18mm thick MR ply in V shape (approx size 2600 x 600). The edge of V design shall be provided with V Shape (12x12mm) PVD finished metal strip. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.	55.00	SQM		
f	Finished with back lite ONYX marble on acrylic backing and Marble in alternating pattern at two different levels as per drawings. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site. Basic Rate of ONYX marble Rs. 10,000/ Sqm Basic Rate of Marble Rs. 3000/Sqm	44.00	SQM		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
g	Finished with back lite ONYX marbie on acrylic backing. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site. Basic Rate of ONYX marble Rs. 10,000/ Sqm	21.00	SQM		
h	VERTICAL SOLID FIXED RAFTORS in meeting room partition as per design details. - Dimensions - 75 mm x 50 mm. Raftors Fininshed in DUCO polish on HDHMR as approved by Site-in-charge.	44.00	RMT		
i	Curved glass for meeting room partitions Supply and installation of 12 mm thick toughened curved glass. Cost to inclusive of making template	45.00	SQM		
j	Finishing on existing partition using 18 mm thick Marble as per drawings and instruction of architect. Cost to be inclusive of Buffing/polishin of marble. Basic cost of Marble - Rs 3000/SQM	77.00	SQM		
	Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevalic SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.				
	Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000 / Sq.Mt.				
3	COVES UPTO 250 MM (FOR INDIRECT LIGHTING) as per drawings. The skins and finishes are to be screwed/pasted using suitable size screws/ approved adhesives on to the Frames/Partitions/Wall/Ceiling etc as per the directions of Site-Engineer/Architect. The rates shall be inclusive of supply , fixing , carting and finishing/polishing/sanding etc as per drawings and instructions of site-engineer/Architect. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.				
3.1	Making Corian cove as per drawing and instructions of architect. The rate shall be inclusive of necessary Ply backing, framework, making cutout for light fixtures, bulkheads, internal & external vertical facia,etc. complete. Cove section includes exposed L-Shaped /curved/slant work and circular configurations where ever required as per detail. The rate shall be inclusive of Thermoforming and buffing. Acrylic epoxy adhesive cost to be inclusive in the rate. Polishing of All exposed surafce to be done so that there will be no joint visible as required by Architect. For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted. Basic Cost of Solid Acrylic surface/corian - Rs 6500/SQM	87.00	RMT		
3.2	Making Gypsum cove as per drawing and instructions of architect. The rate shall be inclusive of necessary framework, making cutout for light fixtures, bulkheads, internal & external vertical facia,etc. complete. Cove section includes exposed L-Shaped /curved/slant gyp work and circular configurations where ever required as per detail. Rate shall be inclusive of necessary framework and paint finishing as described in item for gypsum false ceiling. For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted.	2,926.00	RMT		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
3.3	Making Laminate cove as per drawing and instructions of architect. The rate shall be inclusive of necessary Ply backing, framework, making cutout for light fixtures, bulkheads, internal & external vertical facia,etc. complete. Cove section includes exposed L-Shaped /curved/slant work and circular configurations where ever required as per detail. The rate shall be inclusive of providing and fixing 2mm thick PVC edge banding at exposed edges. For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted.	286.00	RMT		
3.4	Making Veneer cove finished with melamine polish as per drawing and instructions of architect. The rate shall be inclusive of necessary Ply backing, framework, making cutout for light fixtures, bulkheads, internal & external vertical facia,etc. complete. Cove section includes exposed L-Shaped /curved/slant work and circular configurations where ever required as per detail. Basic Cost - 1250/- Sqm For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted.	706.00	RMT		
3.5	Making Marble cove finished with polish / buffing as per drawing and instructions of architect. The rate shall be inclusive of necessary Ply backing, framework, making cutout for light fixtures, bulkheads, internal & external vertical facia,etc. complete. Cove section includes exposed L-Shaped /curved/slant work and circular configurations where ever required as per detail. For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted.	179.00	RMT		
	Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.				
	Mode of measurement:- Though Measurement shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000 / Sq.Mt.				
4	Providing and filling of ROCKWOOL INSULATION (48kgm3density x 50mm thick) Bonded in blanket roll or RP tissue roll.	6,083.00	SQM		
5	GLAZED PARTITION: Providing and constructing Glazed Partition with 10mm thk. toughened glass+ using 45 x 25mm thk aluminium sections anodized upto 20 microns in approved shade on all four sides and all interconnections and corners to have necessary "T", "I" and coner profiles. The gaps to be closed by acoustical sealants of approved make. Rate to also include necessary gasket at all edges of glass to be inserted in the section. Rate to also include crystal cut edge for toughened glass and care to be taken to have zero spacing between 2 glass sheets touching each other at the crystal cut edge. All measurements to be confirmed at site before execution.	1,058.00	SQM		
	Approved make:- Aluminum extruded sections: Jeb, Alloy, Bottomeline, Dorma or equivalent approved by the Client. Hardware :- Geze, Hafele, Hattich or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
6	<p>CURVED GLAZED PARTITION: Providing and constructing Glazed Partition with 10mm thk. Curved toughened glass + using 45 x 25mm Curved aluminium sections. Cost to be inclusive of making Template for glass.</p>	116.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jeb, Alloy, Bottomline, Dorma or equivalent approved by the Client. Hardware :- Geze, Hafele, Hattich or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
7	<p>Supplying and fixing of Frosted film of approved equivalent make on Glass Partition in pattern as per drawings as per manufacturer's specifications with 10 years warranty etc. complete.</p> <p>Basic cost of Frosted Film - Rs 1600/SQM Make - 3M/LG/GARWARE or Eqv. approved by client/architect</p>	695.00	SQM		
8	<p>Making Portal upto 100 mm x 100 mm of PLY and taken support from true ceiling finished with approved Laminate as per the drawings and instructions of site-engineer/Architect.</p>	251.00	RMT		
9	<p>Finishing on existing partition using 18 mm thick Marble for Portal as per drawings and instruction of architect. Cost to be inclusive of finishing exposed edges of portal with marble as per drawings. Cost to be inclusive of Buffing/polishin of marble.</p> <p>Basic cost of Marble - Rs 3000/SQM</p>	55.00	SQM		
B	FLOOR FINISHES				
	Carpet Flooring				
1	<p>Providing and fixing 100% Nylon yarn carpet tile on floor as per drawing and manufactures specifications & instructed by PM or engineer in charge without undulation & bubbles with the help of Approved adhesive. manufacturing of tile by loop weaving and to have Non- woven primary backing(base). Size of carpet tile should be 500mm X 500mm. Cost should include house keeping & cleaning for the carpet till the handover (Required material test certificate along with supporting document), material movement & shifting for all the floors. The finished flooring to be covered with the help of thick plastic & masking tape. Make - Interface/Miliken/Shaw Or Eqv. Basic cost - Rs 2000/SQM</p>	579.00	SQM		
2	<p>Same as above with Custom Carpet Rug Basic Cost - Rs. 3500/Sqm</p>	160.00	SQM		
3	<p>Providing and fixing of matt natural Anodised Aluminium skirting profile of 100 mm height inclusive of all accessories and installation as per the manufacturers specifications. Rate should include cost of MR Ply backing of suitable thickness to match the finished surafce level. The skirting shall be fixed as per details & Architects or project managers instructions. Rate should include preparation of surface such as wall chipping, plastering etc. Basic cost of Aluminium skirting - Rs 350/Meter Make - Bottomline/Progress or Eqv.</p>	3,321.00	RMT		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
4	Providing & Fixing 100 mm high Marble Skirting on existing partition. Rate should include cost of Bison backing of suitable thickness to match the finished surface level. The skirting shall be fixed as per details & Architects or project managers instructions. Rate should include preparation of surface such as wall chipping, plastering etc. Basic cost of Marble - Rs 3000/SQM	3,634.00	RMT		
5	Providing & Fixing 100 mm high Tile Skirting on existing partition . Rate should include cost of Bison backing of suitable thickness to match the finished surface level. The skirting shall be fixed as per details & Architects or project managers instructions. Rate should include preparation of surface such as wall chipping, plastering etc. Basic cost of Tile - Rs 1300/SQM	444.00	RMT		
6	Providing and fixing Transition profiles Gradus/Progress surfaces floor trims - adjustable" at junction of various types of floor (joint of carpet with hard floor, joint of carpet with wooden floor, joint of hard floor with wooden floor etc) wherever necessary as per approval.	22.00	RMT		
7	Providing and fixing of Astro Turf Grass: Providing and fixing Artificial grass turf over tiles / plywood base using approved adhesives etc complete. The rate shall be inclusive of transportation, labour, sundries, tools, adhesives and taxes etc, complete as directed by Engineer incharge / Architect.	66.00	SQM		
C	WALL FINISHES				
1	PUTTY & ROYALE EMULSION PAINTING:				
	Providing and laying 2coats of Birla white putty, 1 coat of primer & 2-3 coats of royal emulsion over the walls/ceiling/partition/columns/Coves etc. The surface shall be cleaned, raked out for lumps, dead material, dust etc. The putty shall be applied with blades and the surface to be kept rest for drying. The surface lups shall be raked out with putty blade and the second coat of putty shall be applied and to be left for drying. The surface shall be done with sand paper to get neat and plain surface. One coat of primer shall be applied to the final coat of putty and to be left to dry. After drying the engineer has to check for any undulation. If any undulations found the surface shall be sand papered, levelled with putty and to be left to dry & primer to be applied to the surface. The process has to be done untill the wall surface is even and with out any undulations. The first coat of paint shall be applied and to be dried. At the time of handing over the final coat of paint shall be laid. Rate to be included with the cost of material, labour, transportation, leads, lifts, scaffolding, rectification works,masking and covering of appliances and furnitures using plastic/paper/masking tape etc, cleaning of premises after work completion etc include all upto completion and handing over of the works upto the satisfaction of engineer incharge. Works has to be done as per specifications, drawings and as directed by engineer incharge. Make - Asian/Nerolac/Burger or Eqv.	5,700.00	SQM		
2	SAME AS ABOVE BUT FOR TEXTURE PAINT	550.00	SQM		
3	GRAPHICS: Wallpaper				
	Providing and fixing graphics on smooth surface with adhesive of as per manufactures standard specifications and instructions by architect. Surface to be finished with putty and oil primer to apply the wall paper. Wall paper is applied using water based glue (Water mixed with CNC powder and Fevicol), and should ensure absence of bubbles, scratches ..etc. All inclusive with complete application and protective covering until handover cost to include surface preparation (similar to base preparation for a paint) to receive the wall paper. Complete as per architect instructions. Basic cost - Rs 200 /sft Make - 3M or Eqv.	494.00	SQM		
4	Providing and fixing 12 mm / 18 mm Metal Hat Section of Approved make and shade as per manufacturer's specifications at locations as indicated on the drawings and instructions of the architect. Make - Bottomline/Progress or Eqv.	110.00	RMT		
5	Providing and fixing 12 mm thick Aluminium L Patti of Approved make as per manufacturer's specifications at locations as indicated on the drawings and instructions of the architect. Make - Bottomline/Progress or Eqv.	1,403.00	RMT		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
6	Pen tray - Providing and fixing customised SS brushed steel pen tray on ply backing as per detail. Size -300mm length, 125 mm deep, 10mm thick to be fixed as per detail. Cost to include necessary backing of ply/cutting and finishing of partition etc. Make - Bottomline/Progress or Eqv.	20.00	NOS		
7	Providing and fixing 12 mm thick Brass Hat Section / L Brass Patti / T Brass Patti of Approved make as per manufacturer's specifications at locations as indicated on the drawings and instructions of the architect.	275.00	RMT		
8	Providing and fixing 18 mm thick Brass Hat Section / L Brass Patti / T Brass Patti of Approved make as per manufacturer's specifications at locations as indicated on the drawings and instructions of the architect.	55.00	RMT		
D	CEILING FINISHES				
1	GYPNUM CEILING WITH PAINTING: P & F suspended gypsum plain false ceiling by using standard company sections, which includes providing and fixing g.i. perimeter channels of size 0.55 mm thick having one flange of 20 mm. and screws, at 610 mm centers. then suspending g.i. intermediate channels of size 45 mm, 0.9 mm thick with two flanges of 15 mm each from the soffits at 1220 mm centers with ceiling angle of width 25 mm x 10 mm x 0.55 mm thick fixed to soffits with g.i. cleat and steel expansion fasteners. ceiling section of 0.55 mm. thickness having knurled web of 51.5 mm. and two flanges of 26 mm each with lips of 10.5 mm. area then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm. centers. 12.5 mm tapered edge gyp board (conforming to is - 2095-1982) is then screw fixed to ceiling section with 25 mm drywall screws 230 mm centers.screws fixing is done mechanically either with screwdriver or drilling machine with suitable attachment. Standard company manufactured sections should be used for the entire framework. Finally the board of size 6' x 4' are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edges of the boards with jointing compound, paper tape only and two coats of primer suitable for gyp-board (as per recommended practices of Manufacturer).	8,369.00	SQM		
	The cut outs for variety of light fixtures and other equipments etc. and the same have to be made with the frame of perimeter channels of size:20 mm x 27 mm x 30 mm x 0.55mm. thick , supported suitably. no extra will be paid for this. edge beed has to be used to protect the exposed gypsum core i.e. cut edges of opening for light fixtures. "v" grooves should be cut at every square edge joints and filled with jointing compound and paper tape. additional g.i. or c.p. teakwood supports shall be provided for fixing of variety of light fixtures, a.c. continues grill, diffusers etc.The contractor must co.ordinate with electrical & AC contractor for working out various levels for the false ceiling & make the marking on the walls/ columns before starting the false ceiling work. All sections visible from the ac grill shall be painted in black color.				
	The final visible plan and elevation area will be considered for the measurement purpose. The work shall be executed through authorized applicator of gypsum india. The contractor has to submit the certificate from manufacturer for the use of company sections (all) & boards along with the final bill. The contractor must get the work checked from the company's representative – one on completion of framing work & second on completion of boarding but before putting top coat. The unit measurement will be considered as the sq.mtrs. only. No R.mtr. (running length) measurement will be considered. Providing and laying 2coats of Birla white putty, 1 coat of primer & 2-3 coats of Plastic emulsion to the ceiling. The ceiling shall be cleaned, racked out for lumps, dead material, dust etc. The putty shall be applied with blades and the ceiling to be kept rest for Drying. The surface lumps shall be racked out with putty blade and the second coat of putty shall be applied and to be left for drying. The surface shall be done with sand paper to get neat and plain surface. One coat of primer shall be applied to the final coat of putty and to be left to dry.				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	The first coat of paint shall be applied and to be dried for drying. At the time of handing over the final coat of paint shall be laid. Care shall be taken by engineer that there will be no rectification works to be done after first coat and second coat of paint. Rate to be included with the cost of material, labour, transportation, leads, lifts, scaffolding, rectification works etc include all upto completion and handing over of the works upto the satisfaction of engineer incharge/architect. Works has to be done as per specifications, drawings and as directed by engineer incharge. Note : Marking of Electrical , Fire Alarm & Air-conditioning & co-ordination with marking of fixtures to be considered. The visible surface area will only be considered for measurement. Make - Saint Gobain/USG boral or Eqv.				
2	SAME AS ABOVE FOR DOUBLE HEIGHT LOBBY	165.00	SQM		
3	GRID CEILING:				
	P & F of modular grid type false ceilings at all heights of 600 x 600 x 15mm mineral fiber ceiling tiles of type dune laid on Silhouette 15mm black reveal grid systems. The frame work comprise of main runner of size 15 x 42 x 3000 mm spaced at 600 mm centers securely fixed to the structural soffit by approved hangers at 1200 mm maximum centers. hangers (BUTTER FYLY CLIP) to be fixed by approved roof plug, level adjusters, screws etc. the last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees of size 15 x 42 x 600mm centrally between the main runners. Perimeter wall angle of size 19 x 19 x 3000mm secured to walls at 450mm maximum centers. Finally dune type 15 mm thick (NRC-0.90, light reflectance > 85 %) micro look tilw with Beveled Tegular edge has to be laid on the 600 mm x 600 mm module. (the same ceiling shall be fixed by using full size tiles only & shall be fixed to the gypsum false ceiling) Suspension system: suspension system shall be Metal Grid silhouette 15 mm Black reveal suspension system (hot dipped galvanized steel) section consisting of the following members: main runner: main runner shall be t-shaped section with rotary stitch of size 15 x 42 x 3000 mm long, cross runners: size 15 x 42 x 600 mm long, wall angle of size 19 x 19 x 3000 mm long colour white.	3,262.00	SQM		
	The area of the celing where full tile size light fixtures are installed, will be NOT dededucted from the total quantity executed. However the cost of tiles will be deducted from the bill amount. The work shall be executed through authorized applicator of Grid Ceiling The contractor has to submit the certificate from the company for the use of company sections & boards along with the final bill. Make - Knauf / Armstrong or Eqv.				
4	Same as above but wooden texture finished tile	235.00	SQM		
5	PUTTY AND PAINT ON CEILING	-	SQM		
6	Providing and Fixing PELMET made out of 12 mm thick MR ply of Dimension: upto 300 x 200 mm, For fixing roller blinds. The rate shall be inclusive of finishing the pelmet with 0.8 mm laminate of approved shade as per architect.	1,078.00	RMT		
7	Trap Door with Gypsum Finish (450x450 mm) Modular trap door	88.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
8	<p>Acoustic Baffle ceiling Linear Acoustical Panels Material - 2" thick fiberglass with scrim on face and sides. Surface Finish Colors: Scrim with factory-applied paint on face and sides. Standard White has energy-saving, high light-reflective finish (LR 0.88). Top of panel is unfinished with white embedded hanging clips. Direct to Grid Suspension System to be used for hanging of Panels with a gap of 6" between each panel as per drawing and site-Engineer/architect. Fire Performance SoundScapes® Blades panel material is ASTM E84 Class A: Flame Spread 25 or under and Smoke Developed 50 or less. CAN/ULC S102 surface burning characteristics. Flame Spread Rating 25 or less. Smoke Developed Classification 50 or less. SoundScapes Blades panels, as with other architectural features located in the ceiling plane, may obstruct or skew the existing or planned fire sprinkler water distribution pattern, or possibly delay the activation of the fire sprinkler or fire detection system. Consult a fire protection engineer, NFPA 13, and local codes for guidance on the proper installation techniques where fire detection or suppression systems are present. Make - Continuum/Armstrong/Anutone or Eqv.</p>	722.00	SQM		
9	Metal baffle ceiling - POWDER COATED - 20 MICRON WITH APPROVED SHADE. DIMENSIONS OF 1 BAFFLE UPTO - 100 x 75 MM	220.00	SQM		
10	CLADDING UPTO 400 MM WIDE 18 mm HDHMR AND FINISHING IT IN DUCO POLISH IN DOUBLE HEIGHT LOBBY AS PER DESIGN	44.00	RMT		
11	<p>Stretch ceiling Supply of Barrisol Plain White / Printed membrane. Membrane Std Size : (040XX) series Width Max 3200 mm. No welding joint with Acoustic Property (NRC Up to 0.3) Transmission-39% & Reflection-57%. Thickness :- 0.8 mm. Weight :- 228 g / m2. Dimensional stability :-15 ° to + 45 °. Warrnty 10 years. Profile-Aluminium extruded patented profile by Barrisol. Profile Star BS 350/01 or Equivalent profile finish Silver. Certificate-Fabric Made as per site Dimmension (Any Shape) with star harpoon high Frequency welding.Fabric polyvinyl chloride (PVC) guaranteed without changing color.Non flammable fabric EURO CLASS B-S2 d0 in the European classification of reaction to fire EN 13501-2002 based on the European standard EN 14716 and test methods EN ISO 11925-2 2002 and EN 13823 2002 corresponding to the old standard M1. Led Light- Supply of led light (Non Dimmable). Make Samsung GOQ/ Equivalent with SMPS. Led & Power supply warranty is As per Company Std. Make - Barrisol/Euroceel or Eqv.</p>	76.00	SQM		
12	Supply & Installation of Alabaster ceiling. Cost to be inclusive of metal frame work and supports in ceiling for receiving alabaster sheet. The installation and fixing to be done as per manufacturer standards. Provision to be made for fixing lighting behind alabaster sheets. Basic Cost - Rs. 5000/Sqm	55.00	SQM		
E	ON SITE CARPENTRY				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
1	<p>COUNTER WITH MARBLE TOP (BUFFET COUNTER) Providing and Fixing Storage unit made out of 18 mm thick BWP Ply with storage underneath. Shutters made of 18 mm Thick BWP ply and to be clad with 4mm thick Veneer finished with melamine polish as per approved design. Shutters to have veneer finish on the front side and all edges. back side of the shutter to be finished with 0.8 mm thick laminate. Counter top to be finished with 18 mm thick Marble and polishing of the same. Counter top to have 38 mm thick Marble Facia as per drawings. Marble edge to be rounded as per drawings and site-Engineer/architect. Counter to have adjustable shelves of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make, all exposed edges finished with machine pressed 1 mm PVC edge banding glued with hot melt EVA glue. All the internal surfaces shall be finished with 0.80 mm thick laminate.</p>	11.00	RMT		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/- Sq.Mt.</p>				
2	<p>COUNTER WITH MARBLE TOP (PANTRY COUNTER) - HxD - 850 x 600 mm Providing and Fixing Storage unit made out of 18 mm thick BWP Ply with storage underneath. Shutters made of 18 mm Thick BWP ply and to be finished with 1mm thick Laminate as per approved design. Shutters to have laminate finish on the front side and all edges. back side of the shutter to be finished with 0.8 mm thick laminate and all edges to have 2mm thick PVC edge band. Counter top to be finished with 18 mm thick Marble and polishing of the same. Counter top to have 38 mm thick Marble Facia as per drawings. Marble edge to be rounded as per drawings and site-Engineer/architect. The unit to have 2 x 3 Set of drawers of heights - 150 mm , 300 mm , 300 mm with weight capacity to be 45 kg minimum each. The drawers made out of BWP ply and to be fitted with SS Drawer unit Telescopic sliding channel (of approved makes) and 38 mm finger groove handle for each drawer. The front Facia of drawer to be finished with 1mm thick Laminate finished with melamine polish as per approved design and Back Panel and drawers made of 12 mm thick BWP ply finished with 0.8 mm balancing laminate of selected shade on both sides pressed on hot-press with approved adhesive.</p>	11.00	RMT		
	<p>Counter to have adjustable shelves of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make, all exposed edges finished with machine pressed 1 mm PVC edge banding glued with hot melt EVA glue. All the internal surfaces shall be finished with 0.80 mm thick laminate.</p>				
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/- Sq.Mt.</p>				
3	<p>COUNTER WITH GRANITE TOP (HOT PLATE COUNTER) - HxD - 900 x 600 mm</p> <p>Providing and Fixing Storage unit made out of 18 mm thick BWP Ply with storage underneath. Shutters made of 18 mm Thick BWP ply and to be clad with 4mm thick Veneer finished with melamine polish as per approved design. Shutters to have veneer finish on the front side and all edges. back side of the shutter to be finished with 0.8 mm thick laminate. Counter top to be finished with 18 mm thick Marble and polishing of the same. Counter top to have 38 mm thick Marble Facia as per drawings. Marble edge to be rounded as per drawings and site-Engineer/architect. The unit to have 3 x 3 Set of drawers of heights - 150 mm , 300 mm , 300 mm with weight capacity to be 45 kg minimum each. The drawers made out of BWP ply and to be fitted with Tandem Drawer unit Telescopic soft close sliding channel (of approved makes) and 38 mm finger groove handle for each drawer. The front Facia of drawer to be finished with 4mm thick Veneer finished with melamine polish as per approved design and Back Panel and drawers made of 12 mm thick BWP ply finished with 0.8 mm balancing laminate of selected shade on both sides pressed on hot-press with approved adhesive.</p>	14.00	SQM		
	<p>Remaining length of the counter to have adjustable shelves of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make, all exposed edges finished with machine pressed 1 mm PVC edge banding glued with hot melt EVA glue. All the internal surfaces shall be finished with 0.80 mm thick laminate.</p>				
	<p>The rate shall include cost of required hardware ,locks , necessary transportaiton, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. As per drawing and instruction of Architect/Client.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/- Sq.Mt.</p>				
4	<p>LIBRARY UNIT / DISPLAY UNIT / TROPHY UNII- FULL HEIGHT (LIBRARY UNIT)</p> <p>Full Height Cupboard with HDHMR finished with DUCO polish and Profile Glass Shutters: Providing & fixing Full Height Storage Cupboard of height 2700 mm and 450mm deep</p> <p>Outer exposed structure with to be made with 18mm thick HDHMR and back side using 8mm thick HDHMR. All shelves to be made with 10 mm thk. toughened glass and fixed using shelf brackets/studds as per drawings. All the internal, edges and external exposed surfaces to be finished with HDHMR finished with DUCO polish.</p> <p>Shutters to be made of aluminium profile of approved anodized coating and Toughened glass as per drawings.</p> <p>Shutters to be provided with approved handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to to be made overlapping the frame.</p> <p>Only front elevation will be considered for area calculation.</p>	119.00	SQM		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. HDHMR- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard. DUCO - Asian/Dulux/Nerolac or Eqv.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p>				
5	<p>LINEAR PODIUM TABLE - 6 SEATER. Providing and fixing Conference table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and Facia Border to be finished in 18mm marble. Ledge of 250mm height to be fixed on the table top using 18mm ply finished with 18mm marble on the top and moulding on the front fascia. Arrangement for in-direct lighting to be considered as per the design / drawing. The front (200mm) will be finished with 4mm thick veneer and finished with melamine Polish . Apron of table (Modesty Panel) including the two ends to be made from 18mm thick MR grade plywood finished with 4mm thick veneer and finished with melamine Polish & 38 x 38 mm PVD metal L strip on all edges as per drawing. 0.8 mm thick laminate matching to veneer finish for inner surfaces shall be provided as per drawing. Skirting - Unit to have 3 Step Moulded Marble skirting as per drawing. The table top is to be supported using necessary understructure at regular intervals (max 1800mm) using the aluminum section covered with 12mm MR ply finished with 1mm thick leather finish laminate and exposed edge to be covered with SS U cap.</p>	7.00	RMT		
	<p>Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound,claening the site etc. complete as per the detail drawing and instruction of Engineer. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/- Sq.Mt.</p>				
6	<p>Water Fountain - Supply and installation of water fountain (min 1500mm dia) made of marble. The fountain to have recirculation water pump. Self priming pump with built in strainer, ABS body, complete in all respect. The rate shall be inclusive of vaccum, nozzle, PVC value, conduits, plumbing fittings, etc complete. Rest as per architect. Basic rate of fountain Rs. 3,00,000/-</p>	1.00	SQM		
7	<p>Cash Counter for Branch - 1600 x 900 x 750 with side unit 1050 x 450 x 750 Supplying & fixing single window counter as per design and drawing made out of 18 mm thick IS 303 MR grade ply wood boxing of approved make, complete with 18 X 6 mm Teak wood beading on all edges wherever required. Table top made out of 12mm thick ISI 303 MR-grade flexi ply. The counter top to be finished with 6mm thk. sparkle white Corian sheet with 1.5" Thk. Bull Nose Moulding from inside and Curved Machine polished edge from outside dropped down to form light pelmet on front Apron as per detail drawing. The vertical surface below the apron to be finished with blue lacquered glass. Working table top and edges shall be finished with 6 mm thick sparkle white acrylic solid surface of approved make) as per drawing and direction with all labour and material. 12mm thick toughened glass of 1600 x 750 with necessary cut outs as per the instructions of the Architect to be fixed on the table using suitable brackets</p>	3.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit (in place of bottom 2 drawers) made of 18 mm thick MR grade plywood and with approved make multipurpose Auto Lock in drawer and group lock in shelf unit. Inner width of drawer box be 400mm, one side of box is leg panel, upper side of box is table top, back side modesty panel and Bottom of Box is of 18 mm thick ply. 4 Nos drawers shall be 525 mm deep (inner dimension), First (Top) drawer 100mm height (facia) & rest 3 of equal size. Top two drawers shall be Cash drawer having 6 equal compartments for currency notes.</p> <p>Side Storage cabinet: Box of 1500 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of 2 nos drawers and shutters to be made of 18 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade plywood. Ply to be finished with 6mm thick corain sheet on top and 1 mm thick laminate on all other exposed surfaces.</p>				
	<p>Foot rest of 75 mm X 38 mm (3" x 1.5") in Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 400 mm X 375 mm. Key board tray of approved make of size 450 mm X 375 mm to be fixed.</p> <p>All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.</p> <p>All fittings like 75 mm long S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.</p>				
	<p>Heavy duty telescopic full extension sliding channel of approved make shall be used in all drawers.</p> <p>All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate of approved shade etc. complete</p> <p>Counter shall be made independent in Length of 1600 mm and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid.</p> <p>FINISHING DETAILS</p> <p>"1) Table Top: 6 mm thick white acrylic solid surface 2) Front Apron: Round 6 mm thick white acrylic solid surface and 6 mm thick blue lacquered glass fixed with Natural Silicon 3) Facing of Drawers: 1.00 mm thick laminate finish 4) All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate"</p>				
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Solid Acrylic surface/corain - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
8	<p>DGM BACK DISPLAY UNIT - FULL HEIGHT 1</p> <p>Full Height Cupboard with Veneer Finish: Providing & fixing Full Height Storage Cupboard of height 2700 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters and shelves to be made with 18 mm thk. Block board finished with 4mm thick veneer and finished with melamine polish. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4mm thick VENEER with 4 mm grooves as per drawings to be finished with melamine polish. Vertical Grooves after every 50 mm on shutters as per drawings. All internal surfaces to be provided with 0.8 mm laminate. All edges of the cupboard should be finished with 4 mm thick veneer finished with melamine polish. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks, SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	67.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
9	<p>DGM BACK DISPLAY UNIT - FULL HEIGHT 2</p> <p>Full Height Cupboard with Veneer Finish: Providing & fixing Full Height Storage Cupboard of height 2700 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters and shelves to be made with 18 mm thk. block board finished with 4mm thick veneer and finished with melamine polish. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4mm thick VENEER with 4 mm grooves as per drawings to be finished with melamine polish. Veneer Shutters to have 12 mm wide veins coating (moulding patti) made out of solid wood finished with melamine polish all around as per drawings. All internal surfaces to be provided with 0.8 mm laminate. All edges of the cupboard should be finished with 4 mm thick veneer finished with melamine polish. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	58.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
10	<p>DGM BACK DISPLAY UNIT - LOW HEIGHT</p> <p>Low Height Cupboard with Veneer Finish: Providing & fixing Full Height Storage Cupboard of height 900 mm and 450mm deep</p> <p>Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters and shelves to be made with 18 mm thick MR ply.</p> <p>Top Facia of the unit will be made with 38 mm thick MR ply finished with 4mm thick veneer finished with melamine polish.</p> <p>All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4mm thick VENEER with 4 mm grooves as per drawings to be finished with melamine polish.</p> <p>Vertical Grooves after every 50 mm on shutters as per drawings.</p> <p>All internal surfaces to be provided with 0.8 mm laminate.</p> <p>All edges of the cupboard should be finished with 4 mm thick veneer finished with melamine polish.</p> <p>Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks, SS towerbolts etc. All shutters to be made overlapping the frame.</p> <p>Only front elevation will be considered for area calculation</p>	40.00	SQM		
	<p>Approved make:-</p> <p>Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client.</p> <p>Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client.</p> <p>Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client.</p> <p>Veneer- Green/Jalaram/ Merino or equivalent approved by the Client.</p> <p>Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.</p> <p>Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
11	<p>CGM BACK DISPLAY UNIT - FULL HEIGHT 1</p> <p>Full Height Cupboard with HDHMR finished with DUCO polish: Providing & fixing Full Height Storage Cupboard of height 2700 mm and 450mm deep</p> <p>Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters to be made with 18 mm thk. Block board finished with HDHMR to achieve required bevelled surface as per drawings and instructions of site-engineer/Architect.</p> <p>All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with HDHMR finished with DUCO polish.</p> <p>All shelves to be made of 18 mm thick ply and All internal surfaces to be finished with 0.8 mm laminate and 1 mm thick PVC edge banding on all edges.</p> <p>All edges of the cupboard should be finished with HDHMR finished with DUCO polish.</p> <p>Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to be made overlapping the frame.</p> <p>Only front elevation will be considered for area calculation</p>	2.00	SQM		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. HDHMR - Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
12	<p>CGM BACK DISPLAY UNIT - FULL HEIGHT 2 (LIBRARY UNIT) Full Height Cupboard with HDHMR finished with DUCO polish and Profile Glass Shutters: Providing & fixing Full Height Storage Cupboard of height 2700 mm and 450mm deep Outer exposed structure with to be made with 18mm thick HDHMR and back side using 8mm thick HDHMR. All shelves to be made with 10 mm thk. toughened glass and fixed using shelf brackets/studds as per drawings. All the internal, edges and external exposed surfaces to be finished with HDHMR finished with DUCO polish. Shutters to be made of aluminium profile of approved anodized coating and Toughened glass as per drawings. Shutters to be provided with approved handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	2.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. HDHMR - Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
13	<p>CGM BACK DISPLAY UNIT - LOW HEIGHT Low Height Cupboard with HDHMR finished with DUCO polish: Providing & fixing Low Height Storage Cupboard of height 900 mm and 450mm deep Top of the unit to be finished with 18 mm Marble as per approval of architect/Site-Engineer Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters to be made with 18 mm thk. MR ply finished with HDHMR to achieve required bevelled surface as per drawings and instructions of site-engineer/Architect. Top Facia of the unit will be 38 mm thick Marble and edge to be cut and polished as per drawings. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with HDHMR finished with DUCO polish. All shelves to be made of 18 mm thick ply and All internal surfaces to be finished with 0.8 mm laminate and 1 mm thick PVC edge banding on all edges. All edges of the cupboard should be finished with HDHMR finished with DUCO polish. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation.</p>	2.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. HDHMR - Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
14	<p>GM TABLE - MARBLE AND LEATHERITE AND VENEER GM TABLE 2700 x 1200 x 750 mm with side table 1050 x 450 x 750 mm Manufacturing, assembling, transporting & placing / fixing in position with Marble, Veener and Leatherite finish. Supplying and installation of Table as per the following description : Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and 38 mm thick bevelled Marble for Facia Border with necessary intermediate support and under structure. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with combination of Leatherite and 4 mm thick veneer with melamine Finish & 10 mm brass strip in groove pattern and Leatherite finish panels with foam backing as per drawing. Table sides, back & intermediate panels (at 50cm from each sides) made from 18 mm thick MR ply finished with 4 thick veneer with melamine finish for exposed surfaces (4 faces) and 0.8 mm thick laminate matching to venner for inner surfaces shall be provided as per drawing. Side storage unit:</p>	4.00	NOS		
	<p>Side Storage cabinet: Box of 1050 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of 2 nos drawers and shutters to be made of 18 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade plywood. Ply to be finished with 4 mm thick veneer finished with melamine polish on top and all other exposed surfaces finished with melamine polish. The drawers and shutters to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	Drawer / Storage cabinet: One Box of 450 X 600 X 640 mm shall be provided using 18 mm thick MR grade ply wood on either side on which table top will be fixed. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of drawers be made of 12 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade ply wood. The drawer unit box and individual drawers to be fixed with 4mm thick Veneer finished with melamine polish on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick laminate matching to the veneer. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer.				
	Computer Key board (550 x 375 mm) of metal / PVC of approved make shall be provided. Foot rest of 38 x 76 MM T.W members shall be provided. Metallic cable Manager shall be provided in table top.				
15	<p>GM BACK DISPLAY UNIT - LOW HEIGHT</p> <p>Low Height Cupboard with Fluted Veneer Finish: Providing & fixing Full Height Storage Cupboard of height 900 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters and shelves to be made with 18 mm thick MR ply. Top of the unit to be finished with 18 mm Marble as per approval of architect/Site-Engineer Top Facia of the unit will be 38 mm thick Marble and edge to be cut and polished as per drawings. The front shutters to be finished fluted veneer and with melamine polish. All internal surfaces to be provided with 0.8 mm laminate. All edges of the cupboard should be finished with 4 mm thick fluted veneer finished with melamine polish. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	15.00	SQM		
	<p>Approved make:-</p> <p>Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-3000 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/ Sq.Mt.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
16	<p>GM BACK DISPLAY UNIT - FULL HEIGHT (LIBRARY UNIT) Full Height Cupboard with 4mm thick veneer finished with melamine polish and Profile Glass Shutters: Providing & fixing Full Height Storage Cupboard of height 2700 mm and 450mm deep Outer exposed structure with to be made with 18mm thick MR ply and back side using 8mm thick HDHMR. All shelves to be made with 10 mm thk. toughened glass and fixed using shelf brackets/studds as per drawings. All the internal, edges and external exposed surfaces to be finished with 4mm thick fluted veneer and with melamine polish. Shutters to be made of aluminium profile of approved anodized coating and Toughened glass as per drawings. Shutters to be provided with approved handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	14.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. HDHMR - Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt.</p>				
17	<p>MD AND DMD TABLE - MARBLE AND DUCO MD AND DMD TABLE - 2400 x 1050 x 750 mm. Manufacturing, assembling, transporting & placing / fixing in position, with 18 mm thick Marble top and Apron to have DUCO finished HDHMR to achieve required bevelled surface as per drawings and instructions of site-engineer/Architect. Supplying and installation of Table as per the following description : Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and 38 mm thick bevelled Marble for Facia Border with necessary intermediate support and under structure. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with bevelled HDHMR finished with DUCO polish & 38 x 38 mm PVD metal L strip on all edges as per drawing. Table sides, back & intermediate panels (at 50cm from each sides) made from 18 mm thick MR ply finished with bevelled HDHMR finished with DUCO polish for exposed surfaces and 0.8 mm thick laminate matching to Duco finish for inner surfaces shall be provided as per drawing. Skirting - Unit to have 3 Step Moulded Marble skirting as per drawing.</p>	3.00	NOS		
	<p>Drawer / Storage cabinet: Two Box of 450 X 600 X 640 mm shall be provided using 18 mm thick MR grade ply wood on either side on which table top will be fixed. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of drawers be made of 12 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade ply wood. The drawer unit box and individual drawers Facia to be finished with HDHMR finished with DUCO polish on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick laminate of approved shade. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer.</p>				
	<p>Computer Key board (550 x 375 mm) of metal / PVC of approved make shall be provided. Foot rest of 38 x 76 MM T.W members shall be provided. Metallic cable Manager shall be provided in table top.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/ Sq.Mt.</p>				
18	<p>MD & DMD BACK DISPLAY UNIT - LOW HEIGHT</p> <p>Low Height Cupboard with HDHMR finished with DUCO polish: Providing & fixing Low Height Storage Cupboard of height 900 mm and 450mm deep Top of the unit to be finished with 18 mm Marble as per approval of architect/Site-Engineer</p> <p>Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters to be made with 18 mm thk. MR ply finished with HDHMR to achieve required bevelled surface as per drawings and instructions of site-engineer/Architect.</p> <p>Top Facia of the unit will be 38 mm thick Marble and edge to be cut and polished as per drawings.</p> <p>All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with HDHMR finished with DUCO polish.</p> <p>All shelves to be made of 18 mm thick ply and All internal surfaces to be finished with 0.8 mm laminate and 1 mm thick PVC edge banding on all edges.</p> <p>All edges of the cupboard should be finished with HDHMR finished with DUCO polish.</p> <p>Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to to be made overlapping the frame.</p> <p>Only front elevation will be considered for area calculation.</p>	7.00	SQM		
	<p>Approved make:-</p> <p>Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client.</p> <p>Plywood/HDHMR:- Greenply, Century, Samrat, Duro or equivalent approved by the Client.</p> <p>Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client.</p> <p>Veneer- Green/Jalaram/ Merino or equivalent approved by the Client.</p> <p>Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.</p> <p>Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/ Sq.Mt.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
19	<p>CGM AND CHAIRMAN TABLE - MARBLE AND DUCO FINISH CGM TABLE 3000 x 1200 x 750 mm with side table 1050 x 450 x 750 mm Manufacturing, assembling, transporting & placing / fixing in position, with 18 mm thick Marble top and Apron to have DUCO finished HDHMR to achieve required bevelled surface as per drawings and instructions of site-engineer/Architect. Supplying and installation of Table as per the following description : Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and 38 mm thick bevelled Marble for Facia Border with necessary intermediate support and under structure. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with bevelled HDHMR finished with DUCO polish & 38 x 38 mm PVD metal L strip on all edges as per drawing. Table sides, back & intermediate panels (at 50cm from each sides) made from 18 mm thick MR ply finished with bevelled HDHMR finished with DUCO polish for exposed surfaces and 0.8 mm thick laminate matching to Duco finish for inner surfaces shall be provided as per drawing. Skirting - Unit to have 3 Step Moulded Marble skirting as per drawing.</p>	2.00	NOS		
	<p>Side storage unit: Side Storage cabinet: Box of 1050 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of 2 nos drawers and shutters to be made of 18 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade plywood. Ply to be finished with HDHMR finished with DUCO polish and 18 mm thick Marble on top. All exposed surfaces finished with bevelled HDHMR finished with DUCO polish. The drawers and shutters to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer. Drawer / Storage cabinet: One Box of 450 X 600 X 640 mm shall be provided using 18 mm thick MR grade ply wood on either side on which table top will be fixed. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of drawers be made of 12 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade ply wood. The drawer unit box and individual drawers Facia to be finished with HDHMR finished with DUCO polish on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick laminate of approved shade.</p>				
	The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer.				
	Computer Key board (550 x 375 mm) of metal / PVC of approved make shall be provided. Foot rest of 38 x 76 MM T.W members shall be provided. Metallic cable Manager shall be provided in table top.				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted Veneer - 3000/- Sq Mt. 4. Marble - 3000/ Sq.Mt</p>				
20	6 SEATER LINEAR TABLE WITH FINISHING DETAILS MATCHING TO BELOW TABLE - 5 M LONG	4.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
21	<p>CONFERENCE TABLE - 53 M LINEAR (14th floor) Providing and fixing Conference table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and Facia Border to be finished in 18mm marble. Ledge of 250mm height to be fixed on the table top using 18mm ply finished with 18mm marble on the top and moulding on the front fascia. Arrangement for in-direct lighting to be considered as per the design / drawing. The front (200mm) will be finished with 12mm fluted MDF finished with Duco paint. Apron of table (Modesty Panel) including the two ends to be made from 18mm thick MR grade plywood finished with bevelled HDHMR finished with DUCO polish & 38 x 38 mm PVD metal L strip on all edges as per drawing. 0.8 mm thick laminate matching to Duco finish for inner surfaces shall be provided as per drawing. Skirting - Unit to have 3 Step Moulded Marble skirting as per drawing. The table top is to be supported using necessary understructure at regular intervals (max 1800mm) using the aluminum section covered with 12mm MR ply finished with 1mm thick leather finish laminate and exposed edge to be covered with SS U cap.</p>	59.00	RMT		
	Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound, cleaning the site etc. complete as per the detail drawing and instruction of Engineer.				
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood/HDHMR:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Laminate - 700 / Sq.Mt. 2. Marble - 3000/ Sq.Mt.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
22	<p>CONFERENCE TABLE - 18 M LINEAR (13th floor) Providing and fixing Conference table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and Facia Border to be finished in 18mm marble. Ledge of 250mm height to be fixed on the table top using 18mm ply finished with 18mm marble on the top. Apron of table (Modesty Panel) including the Ledge and two ends to be made from 18mm thick MR grade plywood finished with 18mm marble in 3 down steps. Provision for indirect light with proper cloves to be considered after every step of marble as per the drawing. 0.8 mm thick laminate matching to marble finish for inner surfaces shall be provided as per drawing. Skirting - SS finish skirting of 100mm to be provided. The table top is to be supported using necessary understructure at regular intervals (max 1800mm) using the suitable aluminum section covered with 12mm MR ply finished with 1mm thick leather finish laminate and exposed edge to be covered with SS U cap. Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound, cleaning the site etc. complete as per the detail drawing and instruction of Engineer.</p>	20.00	RMT		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/ Sq.Mt.</p>				
23	<p>CONFERENCE TABLE - OVAL CENTRE UNIT (2400mm long) (13th floor) Providing and fixing Conference table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 18 mm oval Marble over 18 mm thick MR grade ply and Facia Border to be finished in 18mm marble. Ledge of 250mm height to be fixed on the table top using 18mm ply finished with 18mm marble on the top. Apron of table (Modesty Panel) (max 4 feet long and 900 mm height) including the Ledge to be made from 18mm thick MR grade plywood finished with 18mm marble in 3 down steps. Provision for indirect light with proper cloves to be considered after every step of marble as per the drawing. 0.8 mm thick laminate matching to marble finish for inner surfaces shall be provided as per drawing. Skirting - SS finish skirting of 100mm to be provided. The table top is to be supported using necessary understructure using two SS round pole as per the drawing and instructions of Architect. Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound, cleaning the site etc. complete as per the detail drawing and instruction of Engineer.</p>	1.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/ Sq.Mt.</p>				
24	<p>BOARD ROOM TABLE (7000 x 1800) (14th floor) Providing and fixing board room table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and Facia Border to be finished in 18mm marble. Centre cut out as per the design needs to be created and finished with 4mm thick veneer of approved shade and make as per the instructions of the Architect / Engineer. 0.8 mm thick laminate matching to Duco finish for inner surfaces shall be provided as per drawing. Skirting - Unit to have SS skirting of 100mm as per drawing. The table top is to be supported using necessary understructure at regular intervals (max 1800mm) using the aluminum section covered with 12mm MR ply finished with 4mm thick veneer and exposed edge to be covered with SS U cap. Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound,claening the site etc. complete as per the detail drawing and instruction of Engineer.</p>	1.00	NOS		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Marble - 3000/ Sq.Mt.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
25	<p>CONFERENCE TABLE - 24 M LINEAR (11th floor) Providing and fixing Conference table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 12 mm Solid surface / corian over 18 mm thick MR grade ply and Facia Border to be finished in 6mm corian. Ledge of 250mm height to be fixed on the table top using 18mm ply finished with 12 mm Solid surface / corian on the top. Apron of table (Modesty Panel) including the Ledge and two ends to be made from 18mm thick MR grade plywood finished with 6 mm Solid surface / corian in 3 down steps. Provision for indirect light with proper cloves to be considered after every step of marble as per the drawing. Also 4mm thick fluted veneer as per the design to be considered. 0.8 mm thick laminate matching to marble finish for inner surfaces shall be provided as per drawing. Skirting - SS finish skirting of 100mm to be provided. The table top is to be supported using necessary understructure at regular intervals (max 1800mm) using the suitable aluminum section covered with 12mm MR ply finished with 1mm thick leather finish laminate and exposed edge to be covered with SS U cap. Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound,claening the site etc. complete as per the detail drawing and instruction of Engineer</p>	27.00	RMT		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. fluted veneer Rs-3000 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Solid Acrylic surface/corian - Rs 6500/SQM</p>				
26	<p>MEETING ROOM BOAT SHAPE TABLE (7000 x 1800) (Stilt floor) Providing and fixing board room table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 25 mm thick MR grade ply and Facia Border to be finished with 4mm thick veneer with PU polish. 0.8 mm thick laminate matching to Veneer finish for inner surfaces shall be provided as per drawing. Skirting - Unit to have SS skirting of 100mm as per drawing. The table top is to be supported using necessary understructure at regular intervals (max 1800mm) using the aluminum section covered with 12mm MR ply finished with 4mm thick veneer and exposed edge to be covered with SS U cap. Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound,claening the site etc. complete as per the detail drawing and instruction of Engineer</p>	1.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt.</p>				
27	<p>14 th floor Cafeteria Marble Table 7000 x 1800 mm Providing and fixing board room table as per the drawing and directions of the Architect / Site Engineer Table Top: Providing and fixing 18 mm Marble over 18 mm thick MR grade ply and Facia Border to be finished in 18mm marble. 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. Skirting - Unit to have SS skirting of 100mm as per drawing. The table top is to be supported using necessary understructure at regular intervals (max 1800mm) using the aluminum section covered with 12mm MR ply finished with 4mm thick veneer and exposed edge to be covered with SS U cap. Rate shall be inclusive of cable tray, wire manager, Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, switch boards, mikes etc, carting away unserviceable materials out of the compound, cleaning the site etc. complete as per the detail drawing and instruction of Engineer.</p>	1.00	NOS		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corian - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
28	<p>CURVED RECEPTION TABLE - MARBLE TOP WITH PEDESTAL - 2600 x 1050 x500 MM (Typical floors) Providing & Fixing Reception Table made out of 18mm thk MR Ply framework. Top finished with 18 mm thick Marble of approved shade at 750mm height from the bottom. Table front and sides to be cladded with alternating vertical bands made of MR Ply of 18 mm and 12 mm with approved shades of 1 mm thick laminates on all sides. All Internal areas to be finished with 0.8mm thick approved laminate. 100 MM high recessed 304 SS brush finish skirting to be fixed at the bottom as per drawing. Reception to have elevated L shaped writing deck fixed to the table top of 2600 x 230 x 300 mm made of 18mm thick ply finished with 18mm thick marble on top and leather finished laminate on all other exposed surfaces and 0.8mm thick laminate from inside as per the drawing & directions of Architect. The table to have provision for Cove light as per drawing. The Pedestal/ Drawer unit box 450 x 400 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer</p>	9.00	NOS		
	The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Table to be made as per drawings.				
	The rate shall be inclusive of all the required polishing, suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corian - Rs 6500/SQM</p>				
29	<p>CURVED RECEPTION TABLE - MARBLE TOP WITH PEDESTAL - 2600 x 1050 x500 MM (13th and 14th) Providing & Fixing Reception Table made out of 18mm thk MR Ply framework. Top finished with 18 mm thick Marble of approved shade. Table front and sides to be cladded with alternating vertical bands made of MR Ply of 18 mm and 12 mm finished with approved shades of 4 mm thick veneer with melamine polish and 6mm HDHMR with Duco paint respectively. All Internal areas to be finished with 0.8mm thick approved laminate. 12x25 mm SS pati to be considered on all the alternate joints as per the desin and drawing. 100 MM high recessed 304 SS brush finish skirting to be fixed at the bottom as per drawing. Reception to have elevated L shaped writing deck / ledge fixed to the table top of 2600 x 230 x 300 mm made of 18mm thick ply finished with 18mm thick marble all exposed surfaces and 0.8mm thick laminate from inside as per the drawing & directions of Architect. Reception to have provision for Cove light as per drawing. The Pedestal/ Drawer unit box 450 x 400 x 720 mm with 3 individual drawers to be made in MR ply fininished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate.</p>	1.00	NOS		
	The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Table to be made as per drawings.				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	The rate shall be inclusive of all the required polishing, suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
30	<p>CURVED RECEPTION TABLE - MARBLE TOP WITH PEDESTAL - 2600 x 1050 x500 MM (13th and 14th)</p> <p>Providing & Fixing Reception Table made out of 18mm thk MR Ply framework. Top finished with 18 mm thick Marble of approved shade. Table front and sides to be clad with alternating vertical bands made of MR Ply of 18 mm and 12 mm finished with approved shades of 4 mm thick veneer with melamine polish and 6mm HDHMR with Duco paint respectively. All Internal areas to be finished with 0.8mm thick approved laminate. 12x25 mm SS pati to be considered on all the alternate joints as per the desin and drawing.</p> <p>100 MM high recessed 304 SS brush finish skirting to be fixed at the bottom as per drawing.</p> <p>Reception to have elevated L shaped writing deck fixed to the table top of 2600 x 230 x 300 mm made of 18mm thick ply finished with 8mm thick solid surface / corion on all exposed surfaces and 0.8mm thick laminate from inside as per the drawing & directions of Architect.</p> <p>Reception to have provision for Cove light as per drawing.</p> <p>The Pedestal/ Drawer unit box 450 x 400 x 720 mm with 3 individual drawers to be made in MR ply fininshed with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate.</p>	1.00	NOS		
	The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Table to be made as per drawings.				
	The rate shall be inclusive of all the required polishing, suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
31	<p>STRAIGHT RECEPTION TABLE - MARBLE WITH PEDESTAL - 5200 x 750-1200 x 600 MM (Entrance Lobby)</p> <p>Providing & Fixing Reception Table made out of 50X25X1.2 aluminium framework finished with 18mm MR ply to support 18mm thick marble on all exposed surfaces (top, front and sides). The front fascia to be provided with 18mm thick marble in step down design as shown in the drawing.</p> <p>All Internal areas to be finished with 0.8mm thick approved laminate.</p> <p>100 MM high recessed marble finish skirting to be fixed at the bottom as per drawing.</p> <p>Reception to have elevated L shaped writing deck fixed to the table top of 5200 x 230 x 450 mm made of 18mm thick ply with required understructure support finished with 18mm thick marble on all exposed surfaces and 0.8mm thick laminate from inside as per the drawing & directions of Architect.</p> <p>Front fascia to have provision for Cove light in marble after every step down as per drawing.</p> <p>The 3 nos of Pedestal/ Drawer unit box 450 x 400 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate.</p>	1.00	NOS		
	The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Table to be made as per drawings.				
	The rate shall be inclusive of all the required polishing, suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
32	<p>BRANCH MANAGER TABLE WITH PEDESTAL - 2100 x 900 x 750 MM WITH SIDE UNIT 1500 X 450 X 750</p> <p>Providing & Fixing BM Table made out of 18mm thk MR Ply framework. Top finished with 6 mm thick solid surface / corian of approved shade. Table front and sides to be finished with approved shades of 4 mm thick veneer with melamine polish. All Internal areas to be finished with 0.8mm thick approved laminate.</p> <p>The Pedestal/ Drawer unit box 450 x 400 x 720 mm with 3 individual drawers to be made in 18mm MR ply finished with 4mm thick veneer on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. Table to be made as per drawings.</p> <p>Side Storage cabinet: Box of 1500 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of 2 nos drawers and shutters to be made of 18 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade plywood. Ply to be finished with 4 mm thick veneer finished with melamine polish on top and all other exposed surfaces finished with melamine polish.</p>	1.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	The drawers and shutters to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer. Computer Keyboard drawer (550 x 375 mm) of metal of approved make shall be provided. Footrest (400 x 400) made of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. The rate shall be inclusive of all the required polishing, suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.				
	Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.				
	Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM				
33	DGM TABLE 2700 x 900 x 750 mm with side table 1050 x 450 x 750 mm Manufacturing, assembling, transporting & placing / fixing in position, with Veneer finish and Leatherite finish side table with adjustable side top. Supplying and installation of Table as per the following description : Table Top: Providing and fixing 38 mm thick IS 303 MR grade plywood with 4mm thick Veneer with melamine polish with necessary intermediate support. Table top shall be supported by 50mm using SS stud fasteners. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with 4 mm thick veneer with melamine Finish & 10 mm brass strip in groove pattern and Leatherite finish panels with foam backing as per drawing. Table sides, back & intermediate panels (at 50cm from each sides) made from 18 mm thick MR ply wood finished with 4 thick veneer with melamine finish for exposed surfaces (4 faces) and 0.8 mm thick laminate matching to veneer for inner surfaces shall be provided as per drawing. Side storage unit: Side Storage cabinet: Box of 1050 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of 2 nos drawers and shutters to be made of 18 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade plywood.	16.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Ply to be finished with 4 mm thick veneer finished with melamine polish on top and all other exposed surfaces finished with melamine polish. The drawers and shutters to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer.</p> <p>Drawer / Storage cabinet: One Box of 450 X 600 X 640 mm shall be provided using 18 mm thick MR grade ply wood on either side on which table top will be fixed. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of drawers be made of 12 mm thick MR ply & bottom of drawers shall be of 8 mm thick MR grade ply wood. The drawer unit box and individual drawers to be fixed with 4mm thick Veneer finished with melamine polish on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick laminate matching to the veneer. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer. Computer Key board (550 x 375 mm) of metal / PVC of approved make shall be provided. Foot rest of 38 x 76 MM T.W members shall be provided. Metalic cable Manager shall be provided in table top.</p>				
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
34	<p>11 MEETING ROOM TABLE - 3000(L) X 1200 (W) X 750(H): Veneer</p> <ul style="list-style-type: none"> • WORKTOP to be made of with 28mm thk. MR ply finished with 4 mm thick veneer finished with melamine polish, Work surface HT shall be 750mm • STRUCTURAL SUPPORT SYSTEM:- 2 nos. 600 x 900 mm box made out of 18 mm MR ply and finished with veneer. Both boxes to be connected using Horizontal modesty panel of size 400 mm for best stability. Modesty panel to be made out of 18 mm ply finished with veneer. <p>All Veneer finished with melamine polish.</p> <ul style="list-style-type: none"> • WIRE MANAGEMENT:- The Vertical (Vertical Duct) & Horizontal (1 tier cable tray) wire carriers are placed below worktop, made up of CRCA with Powder Coating & Fixed to the understructure with specially designed brackets. A Metal Separator within the wire carrier is provided to separate electrical & data cables. Switch plates to be in the cable tray, easily accessible through a ACCESS FLAP. <p>Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.</p>	8.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
35	<p>11 MEETING ROOM TABLE - 3000(L) X 1200 (W) X 750(H): Marble • WORKTOP to be made of with 38 mm thk. MR ply finished with 18 mm thick MARBLE and polishing and buffing ther same, Work surface HT shall be 750mm • STRUCTURAL SUPPORT SYSTEM:- 2 nos. 600 x 900 mm box made out of 18 mm MR ply and finished with veneer. Both boxes to be connected using Horizontal modesty panel of size 400 mm for best stability. Modesty panel to be made out of 18 mm ply finished with veneer. All Veneer finished with melamine polish. • WIRE MANAGEMENT:- The Vertical (Vertical Duct) & Horizontal (1 tier cable tray) wire carriers are placed below worktop, made up of CRCA with Powder Coating & Fixed to the understructure with specially designed brackets. A Metal Seperator within the wire carrier is provided to separate electrical & data cables. Switch plates to be in the cable tray, easily accessible through a ACCESS FLAP. Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.</p>	4.00	NOS		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
36	<p>11 MEETING ROOM TABLE - 2400(L) X 1000 (W) X 750(H): LGG BACK OFFICE</p> <ul style="list-style-type: none"> • WORKTOP to be made of with 28mm thk. MR ply finished with 1 mm thick laminate , Work surface HT shall be 750mm • STRUCTURAL SUPPORT SYSTEM:- 2 nos. 600 x 900 mm box made out of 18 mm MR ply and finished with veneer. Both boxes to be connected using Horizontal modesty panel of size 400 mm for best stability. Modesty panel to be made out of 18 mm ply finished with laminate. • WIRE MANAGEMENT:- The Vertical (Vertical Duct) & Horizontal (1 tier cable tray) wire carriers are placed below worktop, made up of CRCA with Powder Coating & Fixed to the understructure with specially designed brackets. A Metal Seperator within the wire carrier is provided to separate electrical & data cables. Switch plates to be in the cable tray, easily accessible through a ACCESS FLAP. <p>Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.</p>	1.00	NOS		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
37	<p>VENEER PARTITION AS PORTAL - DxW - 475 x 51 mm</p> <p>Supplying and installation of 25 x 50 mm aluminium sections to be clad with 9 mm MR ply. All exposed surfaces to be finished with 4mm thick veneer and finished with melamine polish. Portal to be fixed on wall and ceiling as per drawings. (+/- 1 MM variation in thickness based on availability of raw material)</p>	325.00	RMT		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
38	<p>VENEER PARTITION AS PORTAL - DxW - 75 x 51 mm Supplying and installation of 25 x 50 mm aluminium sections to be cladded with 9 mm MR ply. All exposed surfaces to be finished with 4mm thick veneer and finished with melamine polish. Portal to be fixed on wall and ceiling as per drawings. (+/- 1 MM variation in thickness based on availability of raw material)</p>	17.00	RMT		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
39	<p>LAMINATE PARTITION AS PORTAL - DxW - 75 x 51 mm Supplying and installation of 25 x 50 mm aluminium sections to be cladded with 9 mm MR ply. All exposed surfaces to be finished with 1mm thick laminate and 2mm thick PVC edge banding as per drawings.. Portal to be fixed on wall and ceiling as per drawings. (+/- 1 MM variation in thickness based on availability of raw material) Baic Rate of laminate - Rs 700/SQM</p>	220.00	RMT		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
40	<p>LAMINATE PARTITION AS PORTAL - DxW - upto 375 x 51 mm Supplying and installation of 25 x 50 mm aluminium sections to be cladded with 9 mm MR ply. All exposed surfaces to be finished with 1 mm thick laminate . Portal to be fixed on wall and ceiling as per drawings. (+/- 1 MM variation in thickness based on availability of raw material)</p>	150.00	RMT		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
41	<p>STORAGE UNIT - LOW HEIGHT (VENEER) Low Height Cupboard with Veneer Finish: Providing & fixing Low Height Storage Cupboard of height 750 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR ply. All shutters to be made with 18 mm thick MR ply and finished with 4 mm thick Veneer with melamine polish of approved shade. All exposed edges finished with machine pressed with matching 2mm PVC edge banding glued with hot melt EVA glue. All Shelves to be made with 18 mm thick MR ply and finished with 0.8 mm thick laminate of approved shade. All exposed edges finished with machine pressed 1 mm PVC edge banding glued with hot melt EVA glue. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4 mm thick Veneer with melamine polish of approved shade. All internal surfaces to be provided with 0.8 mm laminate. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks, SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	33.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
42	<p>STORAGE UNIT - FULL HEIGHT FOR WARDROBE (VENEER) FULL Height Cupboard with Veneer Finish: Providing & fixing full Height Storage Cupboard of height 2700 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR ply. All shutters to be made with 18 mm thick MR ply and finished with 4 mm thick Veneer with melamine polish of approved shade. All exposed edges finished with machine pressed with matching 2mm PVC edge banding glued with hot melt EVA glue. All Shelves to be made with 18 mm thick MR ply and finished with 0.8 mm thick laminate of approved shade. All exposed edges finished with machine pressed 1 mm PVC edge banding glued with hot melt EVA glue. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4 mm thick Veneer with melamine polish of approved shade. All internal surfaces to be provided with 0.8 mm laminate. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks, SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	28.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
43	<p>Open shelf display unit - GLASS SHELVES Providing and fixing 10 mm thick toughened glass Shelves of size 300 mm deep and fixed using shelf brackets/studds as per drawings.</p>	99.00	RMT		
	<p>Approved make:- Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
44	<p>Open shelf display unit - VENEER SHELVES Providing and fixing 25 mm thick Shelves of size 300 x 600 mm made out of 18 mm MR ply and finished with 4 mm thick veneer on all sides and edges. Veneer to be finished with melamine polish. Fixing of shelf using Tongue and lip joint on existing wall/partition as per drawings.</p>	10.00	SQM		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
45	<p>Open shelf disply unit - LAMINATED SHELVES Providing and fixing 20 mm thick Shelves of size up to 300 x 900 mm made out of 18 mm MR ply and finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Fixing of shelf using Tongue and lip joint on exisitng wall/partition as per drawings.</p>	105.00	RMT		
	<p>Approved make:- Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
46	<p>VERTICAL SOLID FIXED RAFTORS in GYM partition as per design details. - Dimensions - 150 mm x 85 mm. Raftors Finished in approved by Site-in-charge.</p>	239.00	RMT		
F	MODULAR FURNITURE				
1	<p>MESSENGER TABLE 1200 x 700 x 750 Table Top: Providing and fixing 18 mm thick MR grade plywood with 1mm thick laminate. Table top shall be supported by 18 mm thick MR grade plywood with plywood framing. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with 1mm laminate. Table to have 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The Pedestal/ Drawer unit box 450 x 450 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Computer Keyboard drawer (550 x 375 mm) of metal of approved make shall be provided. Footrest (400 x 400) made of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make.</p>	2.00	NOS		
	The rate shall include cost of required hardware, necessary transportaiton, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
2	<p>PA/PS/OFFICER TABLE 1500 x 750 x 750 including side unit of 900 x 450 x 750 Table Top: Providing and fixing 18 mm thick MR grade plywood with 1mm thick laminate. Table top shall be supported by 18 mm thick MR grade plywood with plywood framing. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with 1mm laminate. Table to have 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Side Storage cabinet: Box of 900 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of 2 nos drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick MR grade plywood. The cabinet to have 1 nos adjustable shelf 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The Pedestal/ Drawer unit box 450 x 450 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate.</p>	28.00	NOS		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
3	<p>AGM TABLE 1800 x 750 x 750 including side unit of 900 x 450 x 750</p> <p>Table Top: Providing and fixing 18 mm thick MR grade plywood with 1mm thick laminate. Table top shall be supported by 18 mm thick MR grade plywood with plywood framing. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with 1mm laminate. Table to have 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>Side Storage cabinet: Box of 900 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of 2 nos drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick MR grade plywood. The cabinet to have 1 nos adjustable shelf 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>The Pedestal/ Drawer unit box 450 x 450 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate.</p>	88.00	NOS		
	<p>The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Computer Keyboard drawer (550 x 375 mm) of metal of approved make shall be provided. Footrest (400 x 400) made of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p>				
	<p>Approved make:-</p> <p>Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client.</p> <p>Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client.</p> <p>Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client.</p> <p>Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.</p> <p>Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
4	<p>AGM BACK STORAGE UNIT - LOW HEIGHT Low Height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of height 750 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR ply. All shutters to be made with 18 mm thick MR ply and finished with 1 mm thick laminate of approved shade. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. All Shelves to be made with 18 mm thick MR ply and finished with 0.8 mm thick laminate of approved shade. All exposed edges finished with machine pressed 1 mm PVC edge banding glued with hot melt EVA glue. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 1 mm thick laminate of approved shade. All internal surfaces to be provided with 0.8 mm laminate. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks, SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	273.00	SQM		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. <u>Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</u></p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
5	<p>AGM BACK STORAGE UNIT - FULL HEIGHT FULL Height Cupboard with Laminate Finish: Providing & fixing full Height Storage Cupboard of height 2700 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR ply. All shutters to be made with 18 mm thick MR ply and finished with 1 mm thick laminate of approved shade. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. All Shelves to be made with 18 mm thick MR ply and finished with 0.8 mm thick laminate of approved shade. All exposed edges finished with machine pressed 1 mm PVC edge banding glued with hot melt EVA glue. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 1 mm thick laminate of approved shade. All internal surfaces to be provided with 0.8 mm laminate. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks, SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation</p>	973.00	SQM		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corian - Rs 6500/SQM</p>				
6	<p>PHONE BOOTH Supply and Installation of phone booth with aluminium section of 25 x 50 mm ; clad with HDHMR/PLY as per drawing details. Cost to include - Acoustic Pet Panel, back painted glass, Door, Table & chair as approved by architect / site-in-charge. Vendor to include cost of Door Closer, mortise lock, door handle etc and all allied hardware for the same. MAX L POD FABRIC OUT SIDE INSIDE WOOD Size : 2200L x 1200W x 2250H Booth Facilities - Interior / Exterior Fixtures,Fixed center discussion table, Serene sofa and Netbow power Furniture : Table and Comes with sofa Dimensions External with x depth : L2200mm x D1200mm x Ht2250 Internal width x depth : L2030mm x D1140mm X Ht2117 Room height required on site : 2400mm Note : Marking of Electrical , Fire Alarm & Air-conditioning & co-ordination with marking of fixtures to be considered.</p>	10.00	NOS		
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Veneer- Green/Jalaram/ Merino or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard. Pet Panel - Continnum or Eqv.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corian - Rs 6500/SQM</p>				
7	<p>120 DEGREE DESKING SYSTEM WORKSTATIONS ---- V SHAPED WORKSTATION 1350 1350 x 600. with pedestals</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Providing and fixing factory finished modular, curved shaped 120 degree(3 Desk system) desking system.</p> <p>Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with Providing and fixing factory finished modular, curved shaped 120 degree(3 Desk system) desking system.</p> <p>Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>The table top will be placed on MS powder coated under structure with legs total height 750 mm and fixed to partition using L clamps and allied hardware.</p> <p>120 degree aluminium partition of 1200 mm (+/- 50 mm) height and maximum 50 mm Thickness connected with triangular post , finished with combination of soft board, lacquered glass and MR ply covered with Fabric of approved make and shade, above table top and MR ply with laminate below the table top. All the exposed edges of the partition to be finished with extruded aluminium trim.</p>	163.00	NOS		
	<p>Frames: The frame verticals are fabricated in 1.2mm CRCA sheet. All CRCA sheets confirm to IS – 513.The horizontal members are fabricated with welded joints to the vertical which makes the frames sturdy and facilitates carriage of cables at different levels. All the frames are fitted with M10 leveling bolts to adjust to ground undulations. Can be adjusted +/- 20mm. Frames can be provided with anchoring arrangement if required. All the Frames are duly powder coated in charcoal black color or color of choice to a thickness of 50-60 microns confirming to ASTM B – 117, ISO – 1520 and ISO – 1518 & ASTM D - 2794. The powder coating will be done with NANO Ceramic coating to the extent possible.</p>				
	<p>The partition will be provided with adjustable leveller at the bottom.</p> <p>Cost to be inclusive of 2 Nos Pedestal for each desk (6 nos) LxHxD - 720x450x450 mm(front and side using 18 mm thick MR ply and back side and bottom using 8mm MR ply)-The Pedestal unit box with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame.</p> <p>MS powder coated raceway to accommodate minimum 40 nos of CAT 6 cables to be considered for wiring. Partition to be considered using 25 mm thick MR ply finished with 1mm laminate and 2 mm PVC edge band for each end of approved make and shade as per drawing.</p> <p>Metal powder coated CPU trolley, telescopic keyboard tray to be considered for each desk (3 nos each) , and PVC wire manager of approved makes.</p> <p>Rest details and items to be followed as per drawings. (+/- 1MM variation in thickness based on availability of raw material) Size of each seat/ table will be LxD - 1350x1350x600</p>				
	<p>Approved make:- Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client. Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client. Adhesive: Fevical SH/Vamicol or equivalent approved by the Client. Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
8	<p>Providing and fixing factory finished modular, curved shaped 120 degree(2 Desk system) desking system.</p> <p>Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>The table top will be placed on MS powder coated under structure with legs total height 750 mm and fixed to partition using L clamps and allied hardware.</p> <p>120 degree aluminium partition of 1200 mm (+/- 50 mm) height and maximum 50 mm Thickness connected with 2 way triangular post , finished with combination of soft board, lacquered glass and MR ply covered with Fabric of approved make and shade, above table top and MR ply with laminate below the table top. All the exposed edges of the partition to be finished with extruded aluminium trim.</p> <p>Frames: The frame verticals are fabricated in 1.2mm CRCA sheet. All CRCA sheets confirm to IS – 513.The horizontal members are fabricated with welded joints to the vertical which makes the frames sturdy and facilitates carriage of cables at different levels. All the frames are fitted with M10 leveling bolts to adjust to ground undulations. Can be adjusted +/- 20mm. Frames can be provided with anchoring arrangement if required.</p>	27.00	NOS		
	<p>The partition will be provided with adjustable leveller at the bottom.</p> <p>Cost to be inclusive of 2 Nos Pedestal for each desk (4 nos) LxHxD - 720x450x450 mm(front and side using 12 mm thick MR ply and back side and bottom using 8mm MR ply)-The Pedestal unit box with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame.</p> <p>All the Frames are duly powder coated in charcoal black color or color of choice to a thickness of 50-60 microns confirming to ASTM B – 117, ISO – 1520 and ISO – 1518 & ASTM D - 2794. The powder coating will be done with NANO Ceramic coating to the extent possible.MS powder coated raceway to accommodate minimum 40 nos of CAT 6 cables to be considered for wiring. Partition to be considered using 25 mm thick MR ply finished with 1mm laminate and 2 mm PVC edge band for each end of approved make and shade as per drawing.Metal powder coated CPU trolley, telescopic keyboard tray to be considered for each desk (2 nos each) , and PVC wire manager of approved makes.</p>				
	<p>Rest details and items to be followed as per drawings.(+/- 1 MM variation in thickness based on availability of raw material) Size of each seat/ table will be LxD - 1350x1350x600</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
9	<p>Providing and fixing factory finished modular, curved shaped 120 degree(1 Desk system) desking system.</p> <p>Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>The table top will be placed on MS powder coated under structure with legs total height 750 mm and fixed to partition using L clamps and allied hardware.</p> <p>120 degree aluminium partition of 1200 mm (+/- 50 mm) height and maximum 50 mm Thickness connected with 1 way triangular post , finished with combination of soft board, lacquered glass and MR ply covered with Fabric of approved make and shade, above table top and MR ply with laminate below the table top. All the exposed edges of the partition to be finished with extruded aluminium trim.</p> <p>Frames: The frame verticals are fabricated in 1.2mm CRCA sheet. All CRCA sheets confirm to IS – 513.The horizontal members are fabricated with welded joints to the vertical which makes the frames sturdy and facilitates carriage of cables at different levels. All the frames are fitted with M10 leveling bolts to adjust to ground undulations. Can be adjusted +/- 20mm. Frames can be provided with anchoring arrangement if required. All the Frames are duly powder coated in charcoal black color or color of choice to a thickness of 50-60 microns confirming to ASTM – 117, ISO – 1520 and ISO – 1518 & ASTM D - 2794. The powder coating will be done with NANO Ceramic coating to the extent possible.</p> <p>The partition will be provided with adjustable leveller at the bottom.</p> <p>Cost to be inclusive of 2 Nos Pedestal for each desk (2 nos) LxHxD - 720x450x450 mm(front and side using 12 mm thick MR ply and back side</p>	5.00	NOS		
10	<p>SPLITTER BETWEEN WORKSTATIONS</p> <p>Providing and Fixing 25 mm thick MR ply 1200 mm height finished with 1 mm thick laminate on both sides and all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The same shall be fixed to the table top of workstation using L clamps. The rate shall be inclusive of providing necessary cut outs , transportation, carting etc complete. The rest shall be as per drawings.</p>	128.00	NOS		
11	<p>EDGE PARTITION</p> <p>Providing & fixing in position 70 mm thick +/- 2mm 1200 mm height solid/opaque wooden partitions finished with 1.25 mm fluted laminate (Matt) on one sides and 1mm thick laminate on other side. 75 mm top and sides to be finished with 18 mm HDHMR finished with DUCO polish of approved shade, as per Architectural drawing or as directed by the Engineer-in-charge using approve Quality adhesive complete.</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling.</p> <p>(ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood side of the framework only.</p> <p>(iii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>(iv) The rate shall be inclusive of 100 mm aluminium skirting with approved shade of powder coating.</p>	138.00	NOS		
	<p>Approved make:-</p> <p>Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client.</p> <p>Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client.</p> <p>Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client.</p> <p>MDF- Green/ Merino/Euro or equivalent approved by the Client.</p> <p>Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.</p> <p>Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate -</p> <ol style="list-style-type: none"> 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM 				
12	<p>DESKING SYSTEM WORKSTATIONS ---- 90 degree L SHAPED WORKSTATION 1500 x 1500 x 600 with pedestal</p> <p>Providing and fixing factory finished modular, curved shaped 90 degree(4 Desk system) desking system.</p> <p>Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The table top will be placed on MS powder coated under structure with legs total height 750 mm and fixed to partition using L clamps and allied hardware.</p> <p>90 degree aluminium partition of 1200 mm (+/- 50 mm) height and maximum 50 mm Thickness connected with 4 way post , finished with combination of soft board, lacquered glass and MR ply covered with Fabric of approved make and shade, above table top and MR ply with laminate below the table top. All the exposed edges of the partition to be finished with extruded aluminium trim.</p> <p>Frames: The frame verticals are fabricated in 1.2mm CRCA sheet. All CRCA sheets confirm to IS – 513.The horizontal members are fabricated with welded joints to the vertical which makes the frames sturdy and facilitates carriage of cables at different levels. All the frames are fitted with M10 leveling bolts to adjust to ground undulations. Can be adjusted +/- 20mm.</p>	4.00	NOS		
	<p>The partition will be provided with adjustable leveller at the bottom.</p> <p>Cost to be inclusive of 2 Nos Pedestal for each desk (8 nos) LxHxD - 720x450x450 mm(front and side using 18 mm thick MR ply and back side and bottom using 8mm MR ply)-The Pedestal unit box with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame.</p> <p>MS powder coated raceway to accommodate minimum 40 nos of CAT 6 cables to be considered for wiring. Partition to be considered using 25 mm thick MR ply finished with 1mm laminate and 2 mm PVC edge band for each end of approved make and shade as per drawing.</p> <p>Metal powder coated CPU trolley, telescopic keyboard tray to be considered for each desk (3 nos each) , and PVC wire manager of approved makes.</p> <p>Rest details and items to be followed as per drawings. (+/- 1 MM variation in thickness based on availability of raw material) Size of each seat/ table will be LxD - 1500x1500x600</p>				
	<p>Frames can be provided with anchoring arrangement if required. All the Frames are duly powder coated in charcoal black color or color of choice to a thickness of 50-60 microns confirming to ASTM B – 117, ISO – 1520 and ISO – 1518 & ASTM D - 2794. The powder coating will be done with NANO Ceramic coating to the extent possible.</p>				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
13	<p>Providing and fixing Linear Table having width of 600 mm using 18 mm thick MR grade plywood confirming to IS 303 for table top and verticle supports at 1350 mm c/c.</p> <p>Modesty panel to be made</p> <p>Drawer / Storage cabinet of 720x450x450 mm shall be provided using 18 mm thick MR grade ply wood. Each Drawer Fascia made out of 18 mm thick MR plywood and all sides of drawers be made of 12 mm thick MR ply wood & bottom of drawers shall be of 8 mm thick MR grade ply wood. The drawer unit box and individual drawers to be fixed with 1mm laminate on exposed sides and all the internal surfaces shall be 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer.</p> <p>1.0 mm thick Laminate finish on table Top, all the internal surfaces shall be finished with 0.80 mm thick white laminate , all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>Providing Foot rest of 76x38 MM (3" x 1.5") in Teak wood with melamine polish, keyboard tray and metallic CPU stand.</p>	22.00	RMT		
14	<p>LOW HEIGHT PLANTER STORAGE 400 MM DEPTH FOR KEEPING PLANTS</p> <p>Low Height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of 1200 mm height and 450mm deep. Planter box of 150 mm depth to be considered on the top part of the storage as per drawing.</p> <p>Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply.</p> <p>All shutters and shelves to be made with 18 mm thk.MR ply.</p> <p>The front surface to be finished with 1.2 mm thick fluted laminate of approved shade and make. All other external surfaces to be finished with 1mm laminate of approved shade and make and internal surfaces to be finished with 0.8 mm laminate of approved shade and make.</p> <p>The rate shall be inclusive of 100 mm aluminium skirting with approved shade of powder coating.</p> <p>All edges of the cupboard should be edgebanded using PVC edgebanding tape of approved shade.</p> <p>Shutters to be provided with 38 mm finger groove handle for each shutter , magnetic catchers, self closing SS hinges, locks , SS towerbolts etc.</p> <p>Only front elevation will be considered for area calculation.</p>	113.00	NOS		
	<p>Approved make:-</p> <p>Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Client.</p> <p>Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Client.</p> <p>Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Client.</p> <p>Veneer- Green/Jalaram/ Merino or equivalent approved by the Client.</p> <p>Adhesive: Fevical SH/Vamicol or equivalent approved by the Client.</p> <p>Toughened glass - Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>Base Rate - 1. Veneer Rs-1250 / Sq.Mt. 2. Laminate - 700 / Sq.Mt. 3. Fluted veneer - 3000/ Sq.Mt. 4. Marble - 3000/ Sq.Mt 5. Solid Acrylic surface/corion - Rs 6500/SQM</p>				
15	<p>Supply & Installation of SS Coat Hanger as per drawings or architect instructions. The Coat hanger to be free standing with the Powder Coated heavy metal base. Coat hanger to accommodate at list 3 coats.</p>	3.00	NOS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
16	Supply & Installation of SS BENCH FOR VISIOTRS (3 SEATER) as per drawings or architect instructions.	3.00	NOS		
17	Supply & Installation of ANTE ROOM BED (CHAIRMAN & CGM) as per drawings or architect instructions. Made out of MR ply finished with 1mm thick laminate of approved make. Cost to be inclusive of laminate finished head board upto false ceiling with foam cushion wrapped in approved fabric and fixed in pattern as per architect. Cost to be inclusive of 2 nos side unit with 1 drawer finished with 1mm thick laminate on all exposed surfaces and 0.8 mm laminate on all internal surfaces. Top of both side tables to be finished with marble. Cost to be inclusive of buffing/polishing the marble.	2.00	NOS		
18	Supply & Installation of ANTE ROOM BED (GM , MD , CGM , DGM) as per drawings or architect instructions. Made out of MR ply finished with 1mm thick laminate of approved make. Cost to be inclusive of laminate finished head board upto false ceiling with foam cushion wrapped in approved fabric and fixed in pattern as per architect. Cost to be inclusive of 2 now side unit with 1 drawer finished with 1mm thick laminate on all exposed surfaces and 0.8 mm laminate on all internal surfaces.	11.00	NOS		
19	Supply & Installation of DOCTOR TABLE (L-shape- 1500x 600/side storage 900 x 400) as per drawings or architect instructions. Table Top: Providing and fixing 18 mm thick MR grade plywood with 1mm thick laminate. Table top shall be supported by 18 mm thick MR grade plywood with plywood framing. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with 1mm laminate. Table to have 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Side Storage cabinet: Box of 900 x 450 x 750 mm shall be provided using 18 mm thick MR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of 2 nos drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick MR grade plywood. The cabinet to have 1 nos adjustable shelf 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The Pedestal/ Drawer unit box 450 x 450 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate.	6.00	NOS		
	The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Computer Keyboard drawer (550 x 375 mm) of metal of approved make shall be provided. Footrest (400 x 400) made of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make.				
	The rate shall include cost of required hardware, necessary transportaiton, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.				
20	Supply & Installation of Round Coffee Table / Tea Poy (400mm) as per drawings or architect instructions. Top to be made out of 18mm thic MR Ply finished with 18 mm thick marble & 2mm thick Edge Banding. Table to have MS Poeder Coated Stand	17.00	NOS		
21	Supply & Installation of Square Coffee Table / Tea Poy (450 x 450mm) as per drawings or architect instructions. Top to be made out of 18mm thic MR Ply finished with 18 mm thick marble & 2mm thick Edge Banding. Table to have MS Poeder Coated Stand	5.00	NOS		
22	Supply & Installation of Linear 2 seater Sofa as per drawings or architect instructions. Modular sofa, Inner in wood and padded in high density Polyurethane foam. Elastic belts to enhance comfort and flexibility. Cushions are made of multifill and covered in a protective cotton lining. Set should also include cushions of 0.4x0.4 cm size, color scheme and texture to be approved.	150.00	RMT		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
23	Supply & Installation of Linear 3 seater Sofa as per drawings or architect instructions. Modular sofa, Inner in wood and padded in high density Polyurethane foam. Elastic belts to enhance comfort and flexibility. Cushions are made of multifill and covered in a protective cotton lining. Set should also include cushions of 0.4x0.4 cm size, color scheme and texture to be approved.	10.00	RMT		
24	Supply & Installation of Curved Custum L shaped Sofa as per drawings (3D View) or architect instructions. Modular sofa, Inner in wood and padded in high density Polyurethane foam. Elastic belts to enhance comfort and flexibility. Cushions are made of multifill and covered in a protective cotton lining. Set should also include cushions of 0.4x0.4 cm size, color scheme and texture to be approved.	2.00	RMT		
	Supply & Installation of Single seater Sofa as per drawings or architect instructions. Modular sofa, Inner in wood and padded in high density Polyurethane foam. Elastic belts to enhance comfort and flexibility. Cushions are made of multifill and covered in a protective cotton lining. Set should also include cushions of 0.4x0.4 cm size, color scheme and texture to be approved.	24.00	RMT		
26	Supply and installation of Centre table for Sofa. Table to be made out of 18mm thick MR ply and finished with approved 4 mm thick veneer finished with melamine polish. Dimensions LxBxH - upto 900 x 600 x 450 mm	10.00	NOS		
27	Supply and installation of Centre table for Sofa. Table to be made out of 18mm thick MR ply and 18 mm thick marble top and other exposed surfaces finished with approved 4 mm thick veneer finished with melamine polish. Dimensions LxBxH - upto 900 x 600 x 450 mm	5.00	NOS		
G	JOINERY				
	Doors				
1	Flush Door with viewing glass panel Flush Door with following finishes. Door frame:- Providing and fixing door frames using teakwood members of size 100mm x 50mm and finished with melamine polish. Shutter:- Providing and fixing block board shutters of 35mm thick . Skin:- will be paid extra The Doors to have all hardware such as 125mm SS hinges, 450 m long SS handles, SS tower bolts, Mortice Locks (of approved make), concealed door closer, clear glass viewing panel of 300mm dia. Exposed edges of shutter shall be provided with 2mm thick PVC edge banding matching with the color of door as per the direction of Architect Size of Door : upto 1000 x2100mm including frames.	112.00	Nos		
2	Flush Door with eye hole Flush Door with following finishes. Door frame:- Providing and fixing door frames using teakwood members of size 100mm x 50mm and finished with melamine polish. Shutter:- Providing and fixing block board shutters of 35mm thick . Skin:- will be paid extra The Doors to have all hardware such as 125mm SS hinges, 450 m long SS handles, SS tower bolts, Mortice Locks (of approved make), concealed door closer, eye piece(key hole). Exposed edges of shutter shall be provided with 2mm thick PVC edge banding matching with the color of door as per the direction of Architect Size of Door : upto 1000 x2100mm including frames.	45.00	Nos		
3	Fully Glazed Door Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to floor and ceiling / Partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures & hardwares. Approved make: Standard,Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) as per sample approved by the Client. Mode of Measurement: Door opening size shall be measured.	106.00	SQM		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
H	BLINDS				
1	Manual Roller Blinds Supply & installation of Zebra roller blinds (150 GSM) Providing, supplying & fixing Zebra Blinds of approved make, shade etc as per the directions of the Client at the predetermined locations. The fabric used should be dust, moisture resistant as approved from the Architect before supplying the items. Shade : Colors would be as approved by Architect Composition of Yarn : Glass Fiber (30% minimum) & Bulk dyed Polymer compound. Fire resistance : confirming to NFPA 701 (USA) / NF P92-503 Thickness of Fabric : minimum 0.5mm thk Durability : water proof, anti-microbial, corrosion resistant washable, flame retardant, fade resistant & stain guarded. Roller Tube of SS Thickness : minimum 0.5mm with minimum 25mm Bottom Rail Ball Chain SS coated on Brass as per manufacturer without connecting cap. Chain to be continuous & fixed while installing chain drive unit. Chain drive unit & idler end Manufactured of moulded plastic with steel support pin. It shall be driven by ball chain pulley. The shade shall be automatically locked in any position. Make - Vista/Hunter Douglas or Eqv.	2,807.00	SQM		
2	Normal Roller Blinds in branch. Basic cost - 1500/sqm	255.00	SQM		
3	Motorised Roller Blind	-	SQM		
I	MISCELLANIOUS				
1	MS Fabricated Divider/Partition in cafeteria still as per drawings/3D Views Cost to be inclusive of fabrication as per design and powder coating. Basic Rate - 9,000/-	14.00	NOS		
2	MS Fabricated U BackDrop in cafeteria still as per drawings/3D Views Cost to be inclusive of fabrication as per design and powder coating. Basic Rate - 16,650/-	10.00	NOS		
3	Supply and Installation of Marble Portal - upto 300 mm x 150 mm Cost to be inclusive of Aluminium framing , bison backing and buffing/polishing of marble as per architect Basic Rate - 3,600/-	47.00	RMT		
4	Cafeteria tree coloumns. Cost to be inclusive of fabrication as per design and powder coating. Basic Rate - 90,000/-	2.00	NOS		
5	Cafeteria MS hanging shelf. Cost to be inclusive of fabrication as per design and powder coating. Basic Rate - 1,80,000/-	1.00	NOS		
6	Cafeteria back display storage. Cost to be inclusive of fabrication as per design and powder coating. Basic Rate - 1,80,000/-	1.00	NOS		
7	Synthetic planters with pots for Workstation area	452.00	NOS		
8	Synthetic planters with pots for Passage areas	150.00	NOS		
9	Canvas printed Painting with Frames. (Size upto - 1200 x 1200 mm) Basic Rate - 6500	100.00	NOS		
10	Canvas printed Painting with Frames. (Size upto - 900 x 750 mm) Basic Rate - 5500	100.00	NOS		
J	CHAIRS				
1	Workstation Chairs - * Back Mesh Chair * AN 70 Mesh * Self Calibrating Multilock Mechanism * Adjustable Lumbar Support * One Way Adjustable Arms (Height) * Nylon Base * Fabric Upholstered Cushion Seat Make Model - Featherlite Amaze / Wipro Adapt / Bosq Performance / Godrej Or Eqv.	682.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
2	AGM High Back - * Grey High Back Mesh Chair * AN 70 Mesh * Self Calibrating Multilock Mechanism * Adjustable Lumbar Support * One Way Adjustable Arms (Height) * Metal Base * Fabric Upholstered Cushion Seat Make Model - Featherlite Amaze Gray / Wipro Adapt / Bosq Executive Chair / Godrej Or Eqv.	104.00	Nos		
3	AGM Mid Back - * Grey Medium Back Chair * AN 75 Mesh * Self Calibrating Multilock Mechanism * Adjustable Lumbar Support * Grey One Way Adjustable Arms (Height) * Metal Base * Fabric Upholstered Cushion Seat Make Model - Featherlite Amaze / Wipro Adapt / Bosq Performance / Godrej Or Eqv.	209.00	Nos		
4	DGM High Back - * High Back Mesh Chair * Fabric Upholstered Cushion Seat * Multi Lock Synchro Mechanism * Adjustable Lumbar Support * Seat Sliding * Four Way (4D) Adjustable Arms * Nylon Base Make Model - Featherlite Helix / Wipro Absolute / Bosq Executive Chair / Godrej Or Eqv.	26.00	Nos		
5	DGM Mid Back - * Medium Back Mesh Chair * Fabric Upholstered Cushion Seat * Multi Lock Synchro Mechanism * Adjustable Lumbar Support * Seat Sliding * Four Way (4D) Adjustable Arms * Nylon Base Make Model - Featherlite Helix / Wipro Absolute / Bosq Executive Chair / Godrej Or Eqv.	174.00	Nos		
6	GM High Back - * High Back Mesh Chair * Optima Mesh Standard (black) * With Headrest * Multilock With Seat Sliding Mechanism * Three Way Adjustable Arms (Height & Swivel) * Chrome Magna Base * Fabric Upholstered Cushion Seat Make Model - Featherlite Optima / Wipro Amplify / Bosq Executive Chair / Godrej Or Eqv.	5.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
7	<p>GM Mid Back - * Medium Back Mesh Chair *Optima Mesh Standard (black) * Multilock With Seat Sliding Mechanism * Three Way Adjustable Arms (Height & Swivel) * Chrome Magna Base * Fabric Upholstered Cushion Seat</p> <p>Make Model - Featherlite Optima / Wipro Amplify / Bosq Performance / Godrej Or Eqv.</p>	12.00	Nos		
8	<p>DMD/MD/Chairman / CGM - chair with Italian genuine leather with stitch finishing Aluminium base & armrest with cushion, seat height adjustable Strong tread stitching with a soft cushion to enhance the comfort Stage less memory position locking on backrest Lumbar support adjustable function</p> <p>Make Model - Featherlite Ultra Premium / Wipro Trophy / Bosq Vagha / Godrej Or Eqv.</p>	5.00	Nos		
9	<p>Visitor - Mid Back Chair Seat PU Mould, S curved Back with 40 DC Supersoft Foam Curved High Glossy Veneer Finish Outer Arms with Cushioned Grip Knee tilt Synchro Mechanism with Any Position Back Lock System Hydraulic Gas Lift for Height Adjustment, Aluminium Base with Veneer Finish Cladding, 60mm Nylon Casto</p> <p>Make Model - Featherlite Premium Revolving / Wipro Power Up / Bosq Upholster / Godrej Or Eqv.</p>	21.00	Nos		
10	<p>Super High Conference - High Back Chair Seat PU Mould, S curved Back with 40 DC Supersoft Foam Curved High Glossy Veneer Finish Outer Arms with Cushioned Grip Knee tilt Synchro Mechanism with Any Position Back Lock System Hydraulic Gas Lift for Height Adjustment, Aluminium Base with Veneer Finish Cladding, 60mm Nylon Castors</p> <p>Make Model - Featherlite Premium Revolving / Wipro Trophy / Bosq Upholster / Godrej Or Eqv.</p>	1.00	Nos		
11	<p>High Conference - High Back Executive Revolving Chair Centre Tilt mechanism with a single back lock Anti-topple MS Chrome base with 50mm nylon castors Curved veneer finish polished arms with cushion grip Seat-P U mould, S' Curve back design for better back support With Zebra finish Natural polished Arms</p> <p>Make Model - Featherlite Luzo Elite / Wipro Define / Bosq Executive / Godrej Or Eqv.</p>	3.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
12	<p>Mid Conference - (High Back) Chair Aluminium die-casted base with Synchro Mechanism with multi Position back Lock, Seat & Back - Made from High Density U - FOAM, Arms - S.S. pipe with pu pad.</p> <p>Make Model - Featherlite Revolving / Wipro Define / Bosq Executive / Godrej Or Eqv.</p>	56.00	Nos		
13	<p>Super High Board - High Back Chair Seat PU Mould, S curved Back with 40 DC Supersoft Foam Curved High Glossy Veneer Finish Outer Arms with Cushioned Grip Knee tilt Synchro Mechanism with Any Position Back Lock System Hydraulic Gas Lift for Height Adjustment, Aluminium Base with Veneer Finish Cladding, 60mm Nylon Castors</p> <p>Make Model - Featherlite Premium Revolving / Wipro Trophy / Bosq Upholste / Godrej Or Eqv.</p>	2.00	Nos		
14	<p>High Board - High Back Executive Revolving Chair Centre Tilt mechanism with a single back lock Anti-topple MS Chrome base with 50mm nylon castors Curved veneer finish polished arms with cushion grip Seat-P U mould, S' Curve back design for better back support With Zebra finish Natural polished Arms</p> <p>Make Model - Featherlite Luzo Elite / Wipro Power Up / Bosq Executive / Godrej Or Eqv.</p>	5.00	Nos		
15	<p>Mid Board - (High Back) Chair Aluminium die-casted base with Synchro Mechanism with multi Position back Lock, Seat & Back - Made from High Density U - FOAM, Arms - S.S. pipe with pu pad.</p> <p>Make Model - Featherlite Revolving / Wipro Define / Bosq Executive / Godrej Or Eqv.</p>	55.00	Nos		
16	<p>Conference - High - (High Back) Chair- Centre Tilt mechanism with single back lock, anti topple Aluminium base, veneer finish polished arms with Aluminium die casted handle, Seat-P U mould, S' Curve back design for better back support</p> <p>Make Model - Featherlite Premium Executive / Wipro Define / Bosq Executive / Godrej Or Eqv.</p>	4.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
17	<p>Conference - Mid - (Mid Back) Chair - Centre Tilt mechanism with single back lock, anti topple Aluminium base, veneer finish polished arms with Aluminium die casted handle, Seat-P U mould, S' Curve back design for better back support</p> <p>Make Model - Featherlite Premium Executive / Wipro Define / Bosq Executive / Godrej Or Eqv.</p>	55.00	Nos		
18	<p>Conference All Floor - High - Seat Chair & Back Cushioned on 12 mm. Hot pressed ply, Chrome Base, Synchro tilt Mechanism with multy Position back Lock, Seat & Back - Made from High Density U - FOAM, Alluminium n ms PC armrest with cushion pad.</p> <p>Make Model - Featherlite Executive Revolving / Wipro Define / Bosq Performance / Godrej Or Eqv.</p>	10.00	Nos		
19	<p>Conference Chairs All Floor - Mid - (Med Back) Seat & Back Cushioned on 12 mm. Hot pressed ply, Chrome Base, Synchro tilt Mechanism with single Position back Lock, Seat & Back - Made from High Density U - FOAM, Alluminium n ms PC armrest with cushion pad.</p> <p>Make Model - Featherlite Executive Revolving / Wipro Define / Bosq Performance / Godrej Or Eqv.</p>	106.00	Nos		
20	<p>Auditorium - High - MID BACK CHAIR, TORSION MECHANISM,ALUMINIUM BASE, ALMINIUM +CUSHIONED ARMS,</p> <p>Make Model - Featherlite Paradise Pmp 2037 / Wipro Adapt Silver / Bosq Performance / Godrej Or Eqv.</p>	6.00	Nos		
21	<p>Auditorium - Mid - * Grey Medium Back Chair * AN 75 Mesh * Self Calibrating Multilock Mechanism * Adjustable Lumbar Support * Grey One Way Adjustable Arms (Height) * Metal Base * Fabric Upholstered Cushion Seat</p> <p>Make Model - Featherlite Amaze Grey / Wipro Adapt / Bosq Performance / Godrej Or Eqv.</p>	96.00	Nos		
22	<p>Cafeteria Chairs - * Lounge Single Seater Sofa * Fabric /Leatherette Upholstered Cushion Seat & Bac * Aluminium Base</p> <p>Make Model - Featherlite Designer Chair / Wipro Paradise PI- 9035 / Bosq / Godrej Or Eqv.</p>	81.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
23	<p>Bar Stool - Understructure in Silver Grey powder coating and Laminate in 04 colours as below: 1) Hickory Oak 2) Horizontal Ebony Edges in melamine lacquered finish. Material :ERW CR Tube and 12mm thk Post Laminated Plywood</p> <p>Make Model - Featherlite Zella Barstool / Albans / Coaster Design / Godrej Or Eqv.</p>	9.00	Nos		
24	<p>Centre Table - Providing and making center tables of above mentioned size as per drg (1200mm dia / 1200x1200mm). Table top shall consist of 12 mm. Thk.float glass with chamfered edge with approved quality etching. The base shall be made up of CP Teak wood frame /19mm thk. marine Ply as directed by the Architect. Allexposed faces finished with natural polish (if wood frames are used) or with 1.0mm Thk laminate for ply. All inner surfaces will be finished with natural french polish.</p> <p>Make Model - Featherlite Fetherlite / Albans / Coaster Design / Godrej Or Eqv.</p>	40.00	Nos		
25	<p>Fixed Chairs - SS LEG WITH 40 DENCITY FOAM.</p> <p>Make Model - Featherlite Paradise 1905 / Albans / Coaster Design / Godrej Or Eqv.</p>	54.00	Nos		
26	<p>VIP Dining - * Lounge Single Seater Sofa * Fabric / Leatherette Upholstered Cushion WOODEN LEGS</p> <p>Make Model - Featherlite Clara / Wipro Paradise 1905 / Coaster Design / Godrej Or Eqv.</p>	51.00	Nos		
27	<p>CGM / Chairman - Sofa - • MODULE&FINISH:3+1+1 • BRAND/COLLECTION : STANLEY/LUXURY UNLIMITED COLLECTION • UPHOLSTERY:-CASHMERE</p> <p>Make Model - Stanley Diamond Forever / Albans / Coaster Design / Godrej Or Eqv.</p>	2.00	Nos		
28	<p>MD/ DMD - • MODULE&FINISH:3+1+1 • BRAND/COLLECTION : STANLEY/ SOFAS & MORE COLLECTION • UPHOLSTERY:-S.MAX</p> <p>Make Model - Stanley-Diamond / Albans / Coaster Design / Godrej Or Eqv.</p>	3.00	Nos		
29	<p>PS CGM / Stilt Lobby Pearl (Leatherette/ Fabric)3 Seater Sofa 3+1+1 Make Model - Featherlite Pearl / Albans / Hni / Godrej Or Eqv.</p>	2.00	Nos		
30	<p>DGM / BANK BRANCH * S-900-3 SEATER SOFA 3+1 Make Model - Featherlite Converse / Albans / Hni / Godrej Or Eqv.</p>	15.00	Nos		
31	<p>OFFICE L.G. * S-900-3 SEATER SOFA 3 Make Model - Featherlite Converse / Albans / Hni / Godrej Or Eqv.</p>	7.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
32	GM - Interact: S-902 3 Seater Sofa Interact: S-902 (Leatherette/ Fabric) 3+1 Make Model - Featherlite Interact: S-902 / Albans / Hni / Godrej Or Eqv.	4.00	Nos		
33	CGM / Chairman / Md- Recyliner - • MODULE&FINISH:CHAIR WITH OTTOMAN • BRAND/COLLECTION : STANLEY/LUXURY UNLIMITED COLLECTION • UPHOLSTERY:-CASHMERE Make Model - Stanley -Oslo / Albans / Hni / Godrej Or Eqv.	3.00	Nos		
34	Recyliner - Motorized Recliner Assisted to Sit Down and Recline Assisted Sit Up and Stand Make Model - Featherlite Motorized Recliner / Albans / Hni / Godrej Or Eqv.	18.00	Nos		
	Items of work provided in this schedule but not covered in the specifications shall be executed strictly as per instructions of the project manager/architect.				
	Execution & Detailing as per approved shop drawing.				
K	SIGNAGES				
1.00	INTERIOR SIGNAGE				
1.01	Directional Signage (Vinyl) - SPECIFICATION - Size -450mm x variable, Text height- 23mm, Font- as per client, Colour - Pantone 2727 C. DIRECTIONAL SIGNAGE FINISHING White vinyl cut letters on blue acrylic sheet or black vinyl cut letters	25.00	Nos		
1.02	Single sided Directional Signage - SPECIFICATION - Size -450mm x variable, Text height- 23mm, Font- as per client, DIRECTIONAL SIGNAGE (METAL). black vinyl cut letters on brush steel plates	25.00	Nos		
1.03	Double sided Directional Signage - SPECIFICATION - Size -450mm x variable, Text height- 23mm, Font- as per client, DIRECTIONAL SIGNAGE (METAL). black vinyl cut letters on brush steel plates	25.00	Nos		
1.04	DOOR SIGNAGE (PUSH/PULL) SPECIFICATION :- Size 80mm x 80mm, Material : Etched graphics on brush steel plates.	263.00	Set		
1.05	Room ID- Meeting,Cabins & Other BOH areas Size:305x77mm	150.00	Nos		
1.06	FIRST AID SIGNAGE (VINYL) SPECIFICATION : Size : 100mm x 100mm, Text height : 14mm, Font : Myraid Pro, Material : Low glare acrylic with digital print vinyl graphic, Colour : Pantone 361 C	20.00	Nos		
1.07	DB/SHAFT SHUTTER SIGNAGE SPECIFICATION :- Size 250mm x 80mm, Text height : 16mm & 11mm, Font : Myraid Pro, Material : Brush steel with raised vinyl graphic, Colour : Black.	50.00	Nos		
2.00	FIRE EXIT / EXIT SIGN / FIRE EXTINGUISHER SIGNAGES				
2.01	Lift Instruction signage - Photoluminescent single side -wall mounting Size : 8" x 8"	15.00	Nos		
2.02	Manual call point Signage - Photoluminescent single side - wall mounting Size : 12" x 4"	15.00	Nos		
2.03	Hose Reel Signage - Photoluminescent single side - wall mounting Size : 12" x 4"	30.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
2.04	Exit Signage - Photoluminescent - Single side - wall mounting Size : 12" x 4"	-	Nos		
2.05	Fire Exit Signage - Photoluminescent - dual sided - Suspended Size : 16" x 6"	30.00	Nos		
2.06	Fire Exit Signage - Photoluminescent - Single side - wall mounting Size : 12" x 4"	-	Nos		
2.07	Fire Extinguishers Signage - Photoluminescent - single side - wall mounting Size : 12" x 4"	-	Nos		
2.08	Fire Evacuation Map - single side - wall mounting Size : 12" x 17" Photoluminescent -	30.00	Nos		
2.09	Fire Evacuation Map - single side - wall mounting Size : 17" x 24" Photoluminescent -	2.00	Nos		
(I) TOTAL FOR PART-I (INTERIOR FURNISHING WORKS) (EXCLUDING GST)					
PART II - ELECTRICAL					
A	DISTRIBUTION BOARDS				
1	LDB: Supply, Installation, testing and commissioning of Double door 8 way TPN MCB DB consisting of the following. 32A 4 Pole MCB (C-Series) as Incomer - 1 No. 25A, 30mA DP ELCB as Incomer- 3Nos. 6A 'C' Series SP MCB as out going - 18 Nos. The incoming copper conductors should be connected directly to the DB Earth benches and the body should be earthed from DB earth bench or out side main earth bench if any.				
	Complete with all inter connections and neat marking/identification of DB Name, Cable Size and outgoing MCBs using good quality stickers /paint.	32.00	Set		
2	PDB (RAW POWER DB) : Supply, Installation, testing and commissioning of Double door 8 way VERTICAL TPN MCB DB consisting of the following. 40A 4 pole MCB and separate 40A 4 Pole 100mA ELCB as Incomer - 1 No. 10A SP MCB (C-Series) - 20 Nos. Dummy Plates-4 Nos. The incoming copper conductors should be connected directly to the DB Earth benches and the body should be earthed from DB earth bench or out side main earth bench if any.				
	Complete with all inter connections and neat marking/identification of DB Name, Cable Size and outgoing MCBs using good quality stickers /paint.	32.00	Set		
3	COMPUTER DB (UPS OUTPUT DB) : Supply, Installation, testing and commissioning of Double door 8 way VERTICAL TPN MCB DB consisting of the following. 40A 4 pole MCB and separate 40A 4 Pole 300mA ELCB as Incomer - 1 No. 10A SP MCB (C-Series) - 20 Nos. Dummy Plates-4 Nos. The incoming copper conductors should be connected directly to the DB Earth benches and the body should be earthed from DB earth bench or out side main earth bench if any.				
	Complete with all inter connections and neat marking/identification of DB Name, Cable Size and outgoing MCBs using good quality stickers /paint.	28.00	Set		
	Complete with all inter connections and neat marking/identification of DB Name, Cable Size and outgoing MCBs using good quality stickers /paint.				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
4	EM -LDB: Supply, Installation, testing and commissioning of Double door 4 way TPN MCB DB consisting of the following. 32A 4 Pole MCB (C-Series) and separate 40A, 30mA 4P ELCB as Incomer - 1 No. 6A 'C' Series SP MCB as out going - 12 Nos. The incoming copper conductors should be connected directly to the DB Earth benches and the body should be earthed from DB earth bench or outside main earth bench if any. Complete with all inter connections and neat marking/identification of DB Name, Cable Size and outgoing MCBs using good quality stickers /paint.	14.00	Set		
B	LIGHT & POWER POINT WIRING				
	WIRING FOR LIGHT, FAN, PLUG, SOCKETS ETC				
1	POINT WIRING Supply and wiring for light/fan/exhaust fan/calling bell/mirror lamp/bulk head light/wall fans etc.with 3 plate ceiling rose and by using 3 X 1.5 Sqmm FRLS PVC insulated copper conductor wire in 20mm dia 1.6mm thick heavy duty rigid PVC conduit, controlled by 6 Amps modular type switch with provisions for modular type ceiling fan regulator on separately fabricated MS Box. The M. S. box should be earthed properly. One way point. (The switch boards shall be placed at user friendly locations for easy ON/OFF. Separate Switch Board for EB/UPS lights and Separate SB near entrance & Visitors lounge). The Raw Power & UPS Power Supply to Record Room / Compactor Room / Document room etc.shall be taken though 16A S/S (Raw Power) fixed outside the respective entrance and to be taken to SBs inside respective room using 6/16A plug Top with 3 core 2.5 Sq.mm flexible cable with braided flexible hose. (Average length 6 Mtr)	2,500.00	No.		
2	Same as above but for secondary points (looped points)	1,000.00	Nos.		
3	Supply and Installation of Surface mount single load 360 degree PIR Occupancy Sensor having a detection range of 7 x 7 Meter. (Approved Make:Shneider/Hager/Legrand)	300.00	Nos.		
4	Supply and fixing of Modular type 6A, 2/3 pin plug points controlled 6A modular switch mounted on suitable box. (on common switch board)	800.00	No.		
5	Same as above but for modular type 6A 2/3 pin plug points with 6A modular type switch in separate location. (Token Dispenser / Display, Pedestal fans, other equipments etc)	150.00	No.		
6	Same as above but for 2 Nos. modular type 6 A 2/3 pin plug points with 2 nos. 6A modular type switch in separate location.	132.00	No.		
7	Supply and fixing of modular type 6/16A, 3 module plug socket with 16A modular type switch mounted on suitable Box.	195.00	No.		
8	Supply and Installation of Modular Type 16A SP switch on suitable box including cost of all accessories for group light control.	600.00	Nos.		
9	RAW POWER STATION : Supply and installation of combined 6A, 3pin modular plug socket & 16A combined 3 module modular plug socket controlled by 16A Switch in suitable single PVC box for raw power supply in counters, tables etc.	1,000.00	No.		
10	UPS POWER STATIONS Supply, install, test and commissioning of computer power stations with 4 Nos. 6A modular type two module 2/3 pin sockets mounted on suitable PVC / M.S.Box. The boxes should be fixed on wall / partitions (wooden) consealed or open as required at site.	1,000.00	No.		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
11	Supply, install, test and commissioning of 16A modular type master switch with indicator with suitable PVC box for the main control of UPS Power Station in the Tables.	1,000.00	No.		
12	Supply and providing 6/16 A plug top and 1.5m long 3 core 2.5Sqmm flexible copper cable for taking incoming supply from 6/16A socket. (For Raw Power & UPS power supply to Strong room (Cash), Record Rooms and Water Pump. The 3 core cable shall be laid through braided hose (green) with supporting clamps placed inside strong room/locker room/record room for safe keeping of connecting cable.	60.00	Nos.		
13	CIRCUIT WIRING Supply and wiring wall / floor etc. / recessed / surface as per colour code with 3 runs of 1.1KV grade 1.5 Sqmm FRLS PVC insulated flexible copper wire for phase neutral and earth conductor with standard colour coding, through ISI marked 20mm dia rigid PVC heavy duty conduit with all accessories. The rate includes the cost of complete wiring from switch box to switch box. (For lighting, UPS & Raw Power Circuits & its Sub Circuits)	10,000.00	Mtr.		
14	Same as above but with 3 x 2.5 Sq.mm FRLS PVC Insulated copper wire.	70,000.00	Mtr.		
15	Same as above but with 3 x 4 Sq.mm FRLS PVC Insulated copper wire.	4,000.00	Mtr.		
16	Supply and Laying of RG-06 TV Cable from Terrace to each TV Point in 20 mm dia Rigid heavy duty PVC Conduit	3,000.00	Mtr.		
17	POP-UP TYPE FLUSH TYPE BOXES - (In flooring)				
17.1	3 M Boxes (Legrand make cat no. 0540 10 or equivalent)	40.00	Nos		
17.2	4 M Boxes (Legrand make cat no.0540 12 or equivalent)	40.00	Nos		
17.3	6M Boxes (Legrand make cat no. 0540 11 or equivalent)	40.00	Nos		
17.4	8M Boxes (Legrand make cat no. 0540 13 or equivalent)	40.00	Nos		
18	Installation Kit for Raised floors / Table top				
18.1	3 M	45.00	Nos		
18.2	6 M	10.00	Nos		
19	Supply and Charges for fixing wooden/steel framed laminated copies of Electrical Inspectorate/MSEDCL/Bank's Engineer/Architect approved as fitted drawings inside the UPS room. (Copy of final as fitted drawing approved by Central Electrical Inspectorate. both schematic and layout drawings.) (in electrical rooms on both sides per floor)	28.00	LS		
C	RACEWAY & CABLE TRAY				
1	FLOOR RACEWAYS / CONDUITS / JUNCTION BOXES : Supply and installation of following raceways / conduits / Junction Boxes in flooring.				
1.1	50 x 40 mm GI, 2 mm thick	100.00	Mtr.		
1.2	100 x 40 mm GI, 2 mm thick	100.00	Mtr.		
1.3	150 x 40 mm GI, 2 mm thick	100.00	Mtr.		
1.4	100 mm x 100 mm x 50 mm GI (cover 2.0mm thickness)	80.00	Nos.		
1.5	150 mm x 150 mm x 50 mm GI (cover 2.0mm thickness)	80.00	Nos.		
1.6	250 mm x 250 mm x 50 mm GI (cover 2.0mm thickness)	80.00	Nos.		
2	Supply and installation of perforated ready made 150mm wide 16 G GI cable tray for laying the wiring pipes, cables etc supported using threaded rods and slaugted angle channels nuts and bolts.	450.00	Mtr.		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
3	Supply and installation of perforated ready made 200mm wide GI cable tray for laying the wiring pipes, cables etc supported using threaded rods and slaughted angle channels nuts and bolts.	250.00	Mtr.		
4	Supply and installation of perforated ready made 300mm wide GI cable tray for laying the wiring pipes, cables etc supported using threaded rods and slaughted angle channels nuts and bolts.	250.00	Mtr.		
D	CABLES				
1.0	Supply, handling, laying effecting proper connections testing and commissioning of following sizes of 1.1 KV grade PVC / XLPE insulated Armoured Aluminium / Copper conductor cables. The cables shall be laid as per Hypercitys instruction or on cable trays laid over MS supports cable racks or fixing on walls including clamping the cable to supports in an approved manner as required complete with earthing as specified for continuous earthing along with cable . (The cost of the cable trays or ladders, excavation and back filling of trenches will be measured separate. The unit cost of the cable shall include clamps, fasteners etc. as required for proper installation. Earthing will be measured separately and need not be quoted under this item). All complete as required and as per final instruction as given by consultant/site engineer. The cables should be properly dressed and to be tied to the cable trays using appropriate cable ties.				
	ALUMINIUM CABLES				
1.1	3.5 Core 35 sq. mm. Al Armoured XLPE cable	300.00	RM		
1.2	3.5 Core 25 sq. mm. Al Armoured XLPE cable	300.00	RM		
1.3	4 Core 16 sq. mm. Al Armoured XLPE cable	1,500.00	RM		
	2.0 COPPER CABLES				
2.1	4 Core 10 sq. mm. Cu Armoured XLPE cable	90.00	RM		
2.2	4 Core 6 sq. mm. Cu Armoured XLPE cable	120.00	RM		
2.3	4 Core 4 sq. mm. Cu Armoured XLPE cable	200.00	RM		
2.4	5 Core 2.5 sq. mm. Cu Armoured XLPE cable	80.00	RM		
2.5	3 Core 6 sq. mm. Cu Armoured XLPE cable	90.00	RM		
2.6	3 Core 4 sq. mm. Cu Unrmoured XLPE cable	120.00	RM		
2.7	3 Core 2.5 sq. mm. Cu Armoured XLPE cable	200.00	RM		
3.0	Provide and install Cable terminations for the above cables including Single / Double compression type chrome plated brass glands and lugs (crimping type), PVC taping as required and all accessories complete.				
	ALUMINIUM CABLES				
3.1	3.5 Core 35 sq. mm. Al Armoured XLPE cable	64.00	Nos		
3.2	3.5 Core 25 sq. mm. Al Armoured XLPE cable	24.00	Nos		
3.3	4 Core 16 sq. mm. Al Armoured XLPE cable	225.00	Nos		
	4.0 COPPER CABLES				
4.1	4 Core 10 sq. mm. Cu Armoured XLPE cable	12.00	Nos		
4.2	4 Core 6 sq. mm. Cu Armoured XLPE cable	16.00	Nos		
4.3	4 Core 4 sq. mm. Cu Armoured XLPE cable	18.00	Nos		
4.4	5 Core 2.5 sq. mm. Cu Armoured XLPE cable	10.00	Nos		
4.5	3 Core 6 sq. mm. Cu Armoured XLPE cable	12.00	Nos		
4.6	3 Core 4 sq. mm. Cu Unrmoured XLPE cable	16.00	Nos		
4.7	3 Core 2.5 sq. mm. Cu Armoured XLPE cable	18.00	Nos		
E	LIGHT FIXTURES & FANS				
1	Supply and Installation of 12 Watts, 1200 System Lumens, 4000 K (CCT) (Neutral White), 2 kV surge protection LED commercial Down Light fitting with DALI (Digital Addressible Lighting Interface) Driver and with die cast aluminium housing. (Wipro Mollis or equivalent) (2 year warranty)	450.00	Nos		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
2	Supply and Installation of 15 Watts, 1500 System Lumens, 4000 K (CCT) (Neutral White), 2 kV surge protection LED commercial Down Light fitting with DALI (Digital Addressible Lighting Interface) Driver and with die cast aluminium housing.(Wipro Mollis or equivalent) (2 year warranty)	500.00	Nos		
3	Supply and Installation of 18 Watts, 1800 System Lumens, 4000 K (CCT) (Neutral White), 2 kV surge protection LED commercial Down Light fitting with DALI (Digital Addressible Lighting Interface) Driver and with die cast aluminium housing.(Wipro Mollis or equivalent) (2 year warranty)	450.00	Nos		
4	Supply and Installation of 12 Watts, 1200 System Lumens, 4000 K (CCT) (Neutral White) 2 kV surge protection LED commercial Down Light fitting with Driver and with die cast aluminium housing.(Wipro Mollis or equivalent) (2 year warranty)	275.00	Nos		
5	Supply and Installation of 15 Watts, 1500 System Lumens, 4000 K (CCT) (Neutral White) 2 kV surge protection LED commercial Down Light fitting with Driver and with die cast aluminium housing.(Wipro Mollis or equivalent) (2 year warranty)	275.00	Nos		
6	Supply and Installation of 18 Watts, 1800 System Lumens, 4000 K (CCT) (Neutral White) 2 kV surge protection LED commercial Down Light fitting with Driver and with die cast aluminium housing.(Wipro Mollis or equivalent) (2 year warranty)	275.00	Nos		
38	Supply and installation of 4000K (CCT) suspended 120 degree 'Y' connector with 1 feet, 5.5 Watts Max/feet, 50mm width, with system efficiency of 100 lumen min./Watt LED linear lighting on all 3 arms with integral DALI (Digital Addressible Lighting Interface) Driver for pattern formation of the linear light fitting with powder coated extruded aluminum housing black in colour with all accessories and suspension kit for suspended installation.(Wipro Axion+ or Philips Pureline or equivalent) (2 year warranty)	300.00	Nos.		
7	Supply and installation of 4000K (CCT) suspended 90 degree 'L' connector with 1 feet, 5.5 Watts Max/feet, 50mm width, with system efficiency of 100 lumen min./Watt LED linear lighting on all 2 arms with integral DALI (Digital Addressible Lighting Interface) Driver for pattern formation of the linear light fitting with powder coated extruded aluminum housing black in colour with all accessories and suspension kit for suspended installation. (Wipro Axion+ or Philips Pureline or equivalent) (2 year warranty)	50.00	Nos.		
8	Supply and installation of 4000K (CCT) suspended '+' (Cross) connector with 1 feet, 5.5 Watts Max/feet, 50mm width, with system efficiency of 100 lumen min./Watt LED linear lighting on all 4 arms with integral DALI (Digital Addressible Lighting Interface) Driver for pattern formation of the linear light fitting with powder coated extruded aluminum housing black in colour with all accessories and suspension kit for suspended installation.(Wipro Axion+ or Philips Pureline or equivalent) (2 year warranty)	50.00	Nos.		
9	Supply and installation of 5.5 Watts Max/feet, 50mm width, with system efficiency of 100 lumen min./Watt, 4000 K (CCT) (Neutral White), 2 kV surge protection, suspended Linear LED Light fittings with DALI (Digital Addressible Lighting Interface) Driver and with powder coated extruded aluminum housing black in colour and end caps and with all accessories and suspension kit for suspended installation. (Wipro Axion+ or Philips Pureline or equivalent) (2 year warranty) The linear lighting pattern for any length of straight portion and arms should be made possible at site using SI.No.3& 4 under light fixtures to match the work station layout and cabins.	450.00	Mtr		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
10	Supply and installation of 4000K suspended 120 degree 'Y' connector with 1 feet, 7.5 Watts/feet, 50mm width, with system efficiency of 115 lumen/Watt LED linear lighting on all 3 arms with integral DALI (Digital Addressible Lighting Interface) Driver for pattern formation of the linear light fitting with powder coated extruded aluminum housing black in colour with all accessories for suspended installation. (Wipro Aaxon+ or Philips Pureline or equivalent) (2 year warranty) (2 year warranty)	400.00	Nos.		
11	Supply and installation of 4000K suspended 90 degree 'L' connector with 1 feet, 7.5 Watts/feet, 50mm width, with system efficiency of 115 lumen/Watt LED linear lighting on all 3 arms with integral DALI (Digital Addressible Lighting Interface) Driver for pattern formation of the linear light fitting with powder coated extruded aluminum housing black in colour with all accessories for suspended installation. (Wipro Aaxon+ or Philips Pureline or equivalent) (2 year warranty)	50.00	Nos.		
12	Supply and installation of 4000K suspended '+'(Cross) connector with 1 feet, 7.5 Watts/feet, 50mm width, with system efficiency of 115 lumen/Watt LED linear lighting on all 3 arms with integral DALI (Digital Addressible Lighting Interface) Driver for pattern formation of the linear light fitting with powder coated extruded aluminum housing black in colour with all accessories for suspended installation. (Wipro Aaxon+ or Philips Pureline or equivalent) (2 year warranty) (2 year warranty)	50.00	Nos.		
13	Supply and installation of 7.5 watts per feet, 50mm wide,with system efficiency of 115 lumen/Watt (862 System Lumens), 4000 K (Neutral White), 2 kV surge protection, suspended Linear LED Light fittings DALI (Digital Addressible Lighting Interface) Driver and with powder coated extruded aluminum housing black in colour and end caps and with all accessories and suspension kit for suspended installation. (Wipro Aaxon+ or Philips Pureline or equivalent) The linear lighting pattern for any length of straight portion and arms should be made possible at site using Sl.No. 5 & 6 under light fixtures to match the work station layout and cabins.	800.00	Mtr		
14	Supply and installation of 30 Watt, 4 feet, 3450 System Lumens, 4000 K (Neutral White), 2 kV surge protection, suspended Linear LED Light fittings DALI (Digital Addressible Lighting Interface) Driver and with powder coated extruded aluminum housing black in colour and with all accessories for suspended installation.(Wipro Aaxon+ or Philips Pureline or equivalent) (2 year warranty)	75.00	Nos		
15	Supply and installation of 40 Watt, 8 feet, 4600 System Lumens, 4000 K (Neutral White), 2 kV surge protection, suspended Linear LED Light fittings DALI (Digital Addressible Lighting Interface) Driver and with powder coated extruded aluminum housing black in colour and with all accessories for suspended installation. (Wipro Aaxon+ or Philips Pureline or equivalent) (2 year warranty)	75.00	Nos		
16	Supply and installation of Wireless 5 Button Wall mounting DALI based control switches for the group/invidual control of linear and down light fittings in any pattern formation including all mounting accessories like plate, box etc as per manufacturer instructions. (Wipro iSense or equivalent) (2 year warranty)	300.00	Nos.		
17	Supply and installation of Wireless 8 Button Wall mounting DALI based control switches for the group/invidual control of linear and down light fittings in any pattern formation including all mounting accessories like plate, box etc as per manufacturer instructions.(Wipro iSense or equivalent) (2 year warranty)	50.00	Nos.		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
18	Supply and installation of DALI 4 driver controller for the interface between wall mounted control and lighting fixtures including connected cabling. (Wipro iSense or equivalent) (2 year warranty)	300.00	nos.		
19	Supply and installation of DALI 32 driver controller for the interface between wall mounted control and lighting fixtures including connected cabling. (Wipro iSense or equivalent) (2 year warranty)	120.00	nos.		
20	Supply and installation of 12 Watt, 1200 Lumens, 4000 K (Neutral White) LED Wall Light fittings with Driver and with powder coated extruded aluminum housing black in colour and with all standard accessories for installation. (Wipro LW 31 or equivalent) (2 year warranty)	100.00	Nos		
21	Supply and installation of 33 Watt, 2970 Lumens, 4000 K (Neutral White) Recess mounted 2x2 ft size LED edge backlit direct- indirect light, Light fittings with DALI (Digital Addressible Lighting Interface) Driver and with all standard accessories for installation. (Wipro VergeLED or equivalent) (2 year warranty)	100.00	Nos		
22	Supply and installation of recess mounted full glow 36 Watt, 3600 Lumens, 4000 K (Neutral White) Recess mounted 2 x 2 ft size LED Light fittings with diffuser and all mounting accessories complete. (Wipro Immaculate or equivalent) (2 year warranty)	100.00	Nos		
23	Supply and installation of 800 mm dia, 40 Watt, 4000 K (CCT) Neutral White Suspended circular full glow LED Light fittings with Driver and all suspension kit and accessories for its suspended installation. (Wipro Orbit or equivalent) (2 year warranty)	50.00	Nos		
24	Supply and installation of 800mm dia, 40 Watt, 4000 K (CCT), Neutral White, Suspended Heaxgon shaped full glow LED Light fittings with DALI Dimmable Driver and all suspension kit and accessories for its suspended installation. (Wipro Hexa or equivalent) (2 year warranty)	50.00	Nos		
25	Supply and installation of 600mm dia, 30 Watt, 4000 K (Neutral White) Suspended circular ring LED Light fittings with DALI Dimmable Driver and all suspension kit and accessories for its suspended installation. (Wipro Orbit ring or equivalent) (2 year warranty)	25.00	Nos		
26	Supply and installation of 600mm dia, 30 Watt, 4000 K (CCT), Neutral White, Suspended Heaxgon shaped ring LED Light fittings with DALI Dimmable Driver and all suspension kit and accessories for its suspended installation. (Wipro Hexa ring or equivalent) (2 year warranty)	25.00	Nos		
27	Supply and installation of 20 Watts per 4 feet, 50mm wide , 4000 K (Neutral White) suspended curve LED Light fittings (in '8' pattern) with DALI (Digital Addressible Lighting Interface) and with powder coated extruded aluminum housing black in colour and end caps and with all accessories for suspended installation.	100.00	Mtr.		
28	SITC of Linear type 25 mm wide LED profile light with Aluminium casing and acrylic diffuser with 16 Watts per Metre (240 LED per Meter) LEDs (Philips/Wipro make) with high colour consistency including inbuilt connectors, LED drivers, end caps and mounting clips etc. (Neutral White 4000K (CCT)).	200.00	Mtr.		
29	SITC of Linear type 50mm wide LED profile light with Aluminium casing acrylic diffuser with 32 Watts per Metre (2 runs of 240 LED per Meter) and LEDs (Philips/Wipro make) with high colour consistency including inbuilt connectors, LED drivers, end caps and mounting clips etc. (Neutral White 4000K (CCT)).	200.00	Mtr.		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
30	SITC of Linear type 75mm wide LED profile light with Aluminium casing acrylic diffuser with 48 Watts per Metre (3 runs of 240 LED per Meter) and LEDs (Philips/Wipro make) with high colour consistency including inbuilt connectors, LED drivers, end caps and mounting clips etc. (Neutral White 4000K (CCT).	200.00	Mtr.		
31	Supply and Installation of LED Picture Lamp (costing Rs.1500/- per piece and as selected by Architect)	200.00	Nos.		
32	Supply and providing IP 20 type, 10 Watts/ Metre flexible LED Strip light (Any colour as selected by the Architect at Site) with the corresponding driver of 5/10A including cost of driver unit. Philips / Wipro Garnet make.	2,000.00	Mtr.		
33	Supply and providing IP 20 type, 15 Watts / Metre flexible LED Strip light (Any colour as selected by the Architect at Site) with the corresponding driver of 5/10A including cost of driver unit. Philips / Wipro Garnet make.	2,000.00	Mtr.		
34	Supply and installation of 12 Watts recess mounting round Sky Cob tilt LED Spot light fitting with metal housing. (Neutral White 4000K CCT) Philips Sky COB or Wipro or equivalent.	250.00	Nos.		
35	Supply and installation of 7 Watts recess mounting round Sky Cob tilt LED Spot light fitting with metal housing. (Neutral White 4000K CCT) Philips Sky COB or Wipro or equivalent.	250.00	Nos.		
36	Supply and installation of 5W flush type narrow rim LED Spot lights (Wipro or Philips or Equivalent	100.00	Nos.		
37	Supply & installation of Mains power operated electronic calling bell	150.00	Nos		
38	Supply and Installation of 20 / 21W, 4 Feet LED Batten Light fitting with suitable mounting clips. Philips Slimline / Panasonic Harrow AL	200.00	Nos.		
39	FANS				
39.1	Supply and installation of exhaust fan (Toilets) Crompton / Almonard make. The cost shall be inclusive of cost of wall cutting, its re-plastering finishing and fabricated mettalic grill grouted to the outside wall.	60.00	Nos.		
39.2	Supply and installation of 12" size Heavy duty exhaust fan with metallic body in the new UPS Room with required wall opening and its finishing thereof. The cost shall be inclusive of cost of wall cutting, its re-plastering finishing and fabricated mettalic grill grouted to the outside wall.	4.00	No.		
39.3	Supply and installation of 5 Star rated 1200mm Sweep BLDC ceiling fan without remote (Crompton High Speed / Atomberg)	60.00	Nos.		
39.4	Supply and Installation of step type 2 Module modular electronic regulator.	60.00	No.		
F	EARTHING				
1	Supply of Installation of Following Earthing Material wire including necessary accessories, clamping to walls, cables etc. as required and interconnection between lengths as per specifications and as per good installation practice. The rate shall include all supports, accessories and hardware necessary for proper installation. (All GI strips should be welded on a lap joint practice and two coats of bitumin paint of should be applied on the same to avvoid corrosion in future. And all copper strips should be brazed on a lap joint parctice and should be insulated with PVC sleeve while running on cable trays / wall.) And GI / Al / Cu SWG wires should be terminared using ring types lugs.				

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
	GI EARTH CONDUCTORS				
1.1	1 x 8 SWG hard drawn bare copper wire	600.00	RM		
1.2	25 x 3 mm Cu. Strip for Main Panel	300.00	RM		
	COPPER EARTH CONDUCTORS				
1.3	1C X 4 Sq. mm Cu. Flexible wire	340.00	RM		
1.4	1C X 6 Sq. mm Cu. Flexible wire	160.00	RM		
1.5	1C X 16 Sq. mm Cu. Flexible wire	390.00	RM		
1.6	Earth Busbar box Using 400 X 200 X 150mm Cu Earth Busbar box & 30 X 5 mm , 300 mm long earth bus	52.00	Nos		
G	SAFETY EQUIPMENTS				
1	Supply and providing of Electrical Grade Rubber Mat (2m x 1m x 6mm) (for COS & UPS room)	28.00	Nos.		
2	Supply and fixing of wooden/steel framed Shock Treatment chart with glass of Standard size. (UPS room & Near VDB)	28.00	Nos.		
3	Supply and fixing of LT DANGER BOARD Sticker (Red back ground with white letters and size of Min. 15x10 Cms) (on All DBs & UPS Room Door)	140.00	Nos.		
4	First Aid Box 300x300 with all necessary Kit	14.00	Nos		
5	Supply and fixing of approval make, 0.415kV grade, rubber gloves.	14.00	sets		
H	PUBLIC ADDRESS SYSTEM				
1	Supply and wiring as per colour code with 2.50Sqmm PVC insulated stranded copper wire 2 runs through ISI grade 20mm conduit for speakers.	11,000.00	m		
2	Supply and fixing 9W recessed type speakers on ceiling. Ahuja CS-663T /Bosch	380.00	No.		
3	Supply, Installation, Testing & commissioning of 240 W Amplifier with provision for connecting wired microphone and cordless microphone connectivity with 20 zone call station 1. Microcontroller based with builtin 240 Watt Amplifier 2. Automated Evacuation message facility all accessories etc to make the system complete. Amplifier with USB port.	5.00	No.		
4	Supply and installation of powder coated GI sheet fabricated 10 tier vertical rack for housing the 250W Audio power amplifiers (10 Nos.).	1.00	No.		
(II) TOTAL FOR PART-II (ELECTRICAL WORKS) (EXCLUDING GST)					
	PART III - VOICE & DATA CABLING WORKS				
A	VOICE TELEPHONE				
1	Supply and 200 pair Armoured copper telephone cabling (0.50 Sq.mm) on wall /ceiling/ trenches / cable trays etc clamped using GI clamps of suitable size at 60cm intervals.	1,370.00	m		
2	Supply and installation of KRONE connector telephone junction box of 120 pair.	44.00	Nos.		
3	Charges for marking the telephone sockets and its correspondonding cable in the KRONE Box and preparation of single line diagram / layout of the whole telephone wiring showing location and numbering marked in the plan using AutoCAD, lamination and displaying it near the Telephone KRONE Box.	1.00	LS		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
B User End - CAT6A					
1.0	Supply and laying of 25 mm heavy duty PVC conduit on wall / ceiling /trenches / cable trays etc and clamped at suitable intervals (50 Cm) using GI Clamps.	35,500.00	m		
2.0	Supply and laying of CAT6A U/UTP Cable, 4-Pair, LSZH through the 25mm conduit already provided. Cables are to be tagged at both ends.	1,06,140.00	m		
3.0	Supply and installation of Cat 6A Information Outlets, Blue Colour for DATA with suitable PVC Box. (without face plate) with proper tagging.	1,224.00	Nos.		
4.0	Supply and Installation of Cat 6A Information Outlets, Yellow Colour for Redundant. DATA with suitable PVC Box. (without face plate) with proper tagging.	708.00	Nos.		
5.0	Supply and Installation of Cat 6A Information Outlets, Green Colour for VOICE with suitable PVC Box (without face plate) with proper tagging.	1,056.00	Nos.		
6.0	Supply and Installation of Cat 6A Patch Cords - 7 Feet,LSZH, Blue with proper tagging on both ends.	1,226.00	Nos.		
7.0	Supply and Installation of Cat 6A Patch Cords - 7 Feet,LSZH, Yellow with proper tagging on both ends.	708.00	Nos.		
8.0	Supply and Installation of 2-Port British Style Shuttered Face Plate - White with proper tagging.	600.00	Nos.		
9.0	Supply and Installation 4-Port British Style Shuttered Face Plate - White with proper tagging.	564.00	Nos.		
C Rack End CAT6A					
1.0	Supply and Installation of CAT6A - UTP- 24 Port Modular Jack panel 1U, - DATA in the provided data rack with proper tagging.	60.00	Nos.		
2.0	Supply and Installation of CAT6A - UTP- 24 Port Modular Jack panel 1U, - RDATA in the provided data rack with proper tagging.	36.00	Nos.		
3.0	Supply and Installation of CAT6A - UTP- 24 Port Modular Jack panel 1U, - VOICE in the provided data rack with proper tagging.	48.00	Nos.		
4.0	Supply and Installation of Cat 6A Information Outlets, Blue Colour - DATA in the provided jack panel with proper tagging.	1,224.00	Nos.		
5.0	Supply and installation of Cat 6A Information Outlets, Yellow Colour - R. DATA in the provided jack panel with proper tagging.	708.00	Nos.		
6.0	Supply and installation of Cat 6A Information Outlets, Green Colour - VOICE in the provided jack panel with proper tagging.	1,056.00	Nos.		
7.0	Supply and installation of Cat 6A Patch Cords - 7 Feet,LSZH, Blue - Data between patch panel and switch with proper tagging on both ends.	1,224.00	Nos.		
8.0	Supply and installation of Cat 6A Patch Cords - 7 Feet,LSZH, Yellow - R.Data with proper tagging on both ends.	708.00	Nos.		
9.0	Supply and installation of Cat 6A Patch Cords - 7 Feet,LSZH, Green - VOICE 100 % Considered between patch panel and switch with proper tagging on both ends.	1,056.00	Nos.		
D Fiber Back Bone Cable 6F - OM4-2 Runs					
1.0	Supply and installation of LazrSPEED® Indoor/Outdoor Low Smoke Zero Halogen Riser Distribution Cable, 6 fiber single-unit - OM4 through cable trays between floors (Main Server Room to floor wise server room) with propoer tagging on both ends.	6,000.00	m		
2.0	Supply and installation of LIU - Black, 12F, 1U, LC OM4, Fullloaded with Splice tray, Couplers & Pigtel for fibre optic cable with proper tagging.	104.00	Nos		
3.0	Supply and installation of LC-LC OM4 Multimode 50/125 micron Duplex Patch Cord, 3 Meter (fibre patch chords) with proper tagging.	208.00	Nos		
E Rack & Accessories (Net rack)					
1.0	Supply and installation 42U 800X800 Network Rack With 2 Nos 12 socket PDU with 5/15A, Inlet Plug type 16A Indian Round Pin, 16A MCB - PDU Rating 3.6KVA/Side feed-3Mt/ Black, With standard Accessiores complete.	26.00	Nos		
F Documentation, Testing & Labelling					

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
1.0	Documentation: Charges for preparation of floor wise data cabling lay out drawing, providing framed (with glass) copies of the same in corresponding floor wise server rooms. Original drawings of al the floors should be submitted to the Bank. This also include submission of 25 years warranty certificate and documents for all the passive components used in the total works done.	1.00	Job		
(III) TOTAL FOR PART-III (VOICE & DATA CABLING) (EXCLUDING GST)					
PART IV - FIRE FIGHTING /FIRE ALARM / FIRE EXTINGUISHER RELATED WORKS					
A	Fire Hydrant & Sprinkler System (Existing)				
1	Flexible High Pressure Sprinkler Hose – Forged Elbow				
1.1	Removing of existing flexible hose, supply & installation of Suitable Make / VS Make ½ " Male x ½ " Female, forged Elbow to each sprinkler socket, reinstallation of flexible hose and testing of whole sprinkler line / points (As per interior false ceiling drawing)	2,050.00	Nos.		
1.2	Supply and Installation of Flexible High Pressure Hose(To existing Sprinkler System) 1.5 / 1 Meter, UL / FM approved (New age / Suitable make)with all required assembly items including quick response 68degree rating pendant sprinkler bulb of UL/FM approved	150.00	Nos.		
2	Smoke Detection & Fire Alarm System (Existing System - Addressable Type Tyco Fire & Security Make – Fire Class LPCB approved– Made by Czech Republic). Installation /testing / commissioning / addressing - as per new interior drawing (all installed existing & new detectors and other related Items of fire alarm system) etc of stilt,ground and upper fifteen floors of building				
2.1	Smoke Detectors (Optical Type – Tyco Make)	170.00	Nos.		
2.2	Flasher Cum Hooters (Tyco Make)	15.00	Nos.		
2.3	Manual Call Point (Tyco Make)	15.00	Nos.		
2.4	Response Indicator (Tyco Make)	170.00	Nos.		
2.5	Armoured Cable ISI Mark 2x1.5 sq mm, multi core (Suitable for existing addressable fire alarm system) (Finolex/Polycab/ RR Cable)	500.00	Mtr		
2.6	Installation /testing / commissioning / addressing (all available & new smoke detectors and other Items) etc (02 Nos Fire Alarm Control Panel Tyco System located at ground floor Security Control Room)	1.00	Job		
3	FIRE EXTINGUISHERS: Supply and Installation of the following type of fire extinguishers.				
3.1	Dry Chemical Power type Fire Extinguishers, Trolley Mounted, Internal Cartridge – 25 Kg capacity ABC type (Safex/New Age/ Minimax - ISI Mark)	15.00	Nos.		
3.2	Carbon-di-Oxide Type – 4.5 kg capacity with trolley mounted (Safex/New Age/ Minimax - ISI Mark) with M.S / Metal Stand	15.00	Nos.		
3.3	Carbon-di-Oxide Type – 3 kg capacity (Safex/New Age/ Minimax - ISI Mark) With M.S. / Metal Floor Stand	15.00	Nos.		
4	Safety Signage's – Glow in Dark – Photo luminescent Type with duration of 120 Minutes duration Good Quality (EXIT, Emergency EXIT, No Smoking, Assembly Area,Etc (Prolite Make)	100.00	Nos.		
(IV) TOTAL FOR PART-IV (FIRE FIGHTING /FIRE ALARM / FIRE EXTINGUISHER RELATED WORKS) (EXCLUDING GST)					
PART V - VIDEO SURVEILLANCE SYSTEMS					
1	Supply & installation of 2 Megapixel IP IR Fixed Lens WDR Dome Camera with provision for fixing SD Card (on any surface) conforming to technical specifications as per Annexure-1 under Technical Bid-Video Surveillance systems (Approved makes: CP Plus / Honeywell / Godrej)	200.00	Nos.		
2	Supply & installation of 2 Megapixel IP IR Fixed Lens WDR Bullet Camera with provision for fixing SD Card (on any surface) conforming to technical specifications as per Annexure-2 under Technical Bid-Video Surveillance systems (Approved makes: CP Plus / Honeywell / Godrej)	20.00	Nos.		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
3	Supply & installation of 4 Megapixel IP IR Fixed Lens WDR Bullet Camera with provision for fixing SD Card (on any surface) conforming to technical specifications as per Annexure-3 under Technical Bid-Video Surveillance systems (Approved makes: CP Plus / Honeywell / Godrej)	10.00	Nos.		
4	Supply and installation of Micro SD card 128 GB (Class 10 or above) in the above Dome/Bullet Cameras (Approved makes: Sandisk / CP Plus / hp)	230.00	Nos.		
5	Supply & installation of 5 Megapixel IP Fish eye Camera with provision for fixing SD Card (on any surface) conforming to technical specifications as per Annexure-4 under Technical Bid-Video Surveillance systems (Approved makes: CP Plus / Honeywell / Godrej)	80.00	Nos.		
6	Supply & installation of 128 Channel 8 SATA Network Video Recorder with provision for fixing HDD (Approved makes: CP Plus / Honeywell / Godrej)	2.00	Nos.		
7	Supply & installation of 64 Channel 8 SATA Network Video Recorder with provision for fixing HDD (Approved makes: CP Plus / Honeywell / Godrej)	1.00	No.		
8	Supply & installation of 32 Channel 8 SATA Network Video Recorder with provision for fixing HDD conforming to technical specifications as per Annexure-5 under Technical Bid-Video Surveillance systems (Approved makes: CP Plus / Honeywell / Godrej)	1.00	No.		
9	Supply & installation of 24 Port POE Switch conforming to technical specifications as per Annexure-6 under Technical Bid-Video Surveillance systems (Approved makes: CP Plus / Netgear / cisco / D-Link)	4.00	No.		
10	Supply & installation of 8 Port POE Switch conforming to technical specifications as per Annexure-7 under Technical Bid-Video Surveillance systems (Approved makes: CP Plus / Netgear / Cisco / D-Link)	30.00	No.		
11	Supply and installation of HDD 10TB in the provided Network Video recorders conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance system (Approved makes: WD / Seagate)	20.00	Nos.		
12	Supply and installation of 65" LED Display Monitor for CCTV System conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance systems (Approved makes: LG / Samsung)	2.00	Nos.		
13	Supply and installation of Wall Rack for CCTV Monitor conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance systems.	2.00	Nos.		
14	Supply and installation of 6U Wall Mounted Rack for Network Video Recorder conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance systems	4.00	Nos.		
15	Supply and laying of 2 core 1 sq. mm PVC insulated copper Power Cable through 20/25mm dia Rigid Heavy Gauge (HMS) PVC Conduit clamped using GI clamps at 50 cm intervals on wall/ceiling/trays/trenches etc. conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance systems (approved Makes: Polycab / Finolex / RR Cable/ V-Guard)	600.00	Mtr		
16	Supply and laying of 15 metre Long HDMI Cable through PVC conduit / casing and capping of suitable size conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance systems.	6.00	Nos.		
17	Supply and laying of CAT 6 Armoured Cable through 25mm dia Rigid Medium Gauge (MMS) PVC Conduit clamped using GI clamps at 50 cm intervals on wall/ceiling/trays/trenches etc conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance systems (approved Makes: Polycab / Finolex / RR Cable/ V-Guard/D-Link))	9,000.00	Mtr		
18	Supply and laying of Fibre 24 Core Cable through 25mm dia Rigid Medium Gauge (MMS) PVC Conduit clamped using GI clamps at 50 cm intervals on wall/ceiling/trays/trenches etc conforming to technical specifications as per Annexure-8 under Technical Bid-Video Surveillance systems (approved Makes:)	1,200.00	Mtr		

SR	DESCRIPTION	Qty	Unit	RATE	AMOUNT
19	Charges for Testing & Commissioning of the entire CCTV Systems of all floors, providing training to the Bank's Officials for day to day operation etc.	1.00	Job		
(V) TOTAL FOR PART-V (VIDEO SURVEILLANCE SYSTEMS) (EXCLUDING GST)					

SUMMARY OF PRICES QUOTED		
I	TOTAL FOR INTERIOR FURNISHING WORKS	Rs
II	TOTAL FOR ELECTRICAL WORKS	Rs
III	TOTAL FOR VOICE & DATA CABLING WORKS	Rs
IV	TOTAL FOR FIRE FIGHTING /FIRE ALARM / FIRE EXTINGUISHER RELATED WORKS	Rs
V	TOTAL FOR CCTV & SECURITY SYSTEMS	Rs
	GRAND TOTAL (EXCLUDING GST)	Rs