

STATE BANK OF INDIA
ADMINISTRATIVE OFFICE DURGAPUR
SCHEDULE OF WORKS : CIVIL /STRUCTURAL WORKS
PROJECT : ROOF TREATMENT AND WATER-PROOFING WORKS AT ROOF OF ASANSOL BRANCH
ROOF TREATMENT ASANSOL BRANCH

SI. No.	Item Description	Unit	Quantity	Rate (Rs./Unit)	Amount(Rs)
1	The surface cleaning is to be done thoroughly by mechanical means like wire-brushing, chiseling, manual chipping & grinding, etc., for removing the existing old Tar Felt layers. The cleaning of roof surface is to include removal of all dirt, dust, foreign matters, etc., to attain a smooth surface. The surface preparation includes exposing the mother roof slab and checking the slop of the same before going for treatment. Complete removal of debris from work site as well as from the campus conforming to local Municipal rules must be ensured.	SQM	1300.00		
2	Providing and applying bituminous Water Base Primer on the entire cleaned roof surface. The priming coat should have a dosage @ 0.40 litre per sqm area as per the manufacturer's specification.	SQM	1300.00		
3	Providing and applying 3 mm thick Glass Fiber Reinforced APP membrane with an overlap of 80mm at side and 120 mm at the end upto the height of parapet wall. APP will be specially reinforced with non-woven polyester core with polyester reinforcement @ 160 g per sqm. Both faces of the reinforced core shall be covered up with thermo-fusible polyethylene film. All joints are to be fused using LPG / Propane torch employing extra care towards ensuring full bondage. Note: The rates of inclusive of laying and filling the joints with LPG gas torch flame.	SQM	1300.00		
TOTAL VALUE OF WORKS					
Amount in words:					
Note:	Estimate has been prepared as per Bank's approved rates for similar works				
	Goods & Services Tax (GST) shall be paid extra as admissible on final bill.				
	The Contractor must furnish a warranty for a period of 7 years from the Date of Completion against any defect on a non-judicial stamp paper of Rs. 100/- only.				
	The vendor has to engage authorised applicator for roof treatment and should produce				
	Certificate of Gaurantee for a period of 7 years from the authorised applicator after completion of works along with the final bill.				

Signature of the Contractor with Official Seal

Bank reserves the right to select any material out of the specified make.

