

**STATE BANK OF INDIA**  
**ASANSOL BRANCH**

**SCHEDULE OF WORKS : PLUMBING WORKS ALONG WITH REPLACEMENT OF RAIN-WATER PIPES AT ASANSOL BRAN**

**PROJECT: REPLACEMENT OF RAINWATER PIPES AT ASANSOL BRANCH**

SI. No.	Item Description	Unit	Quantity	Rate	Amount (Rs.)
1	Laying of 110 mm dia. u-PVC Rainwater Downcomer (RWDC) pipes with fitting & fixing with necessary fittings, short pieces, clamps, etc., including scaffolding, staging, etc., complete	R-m	230		
2	Laying of 55 mm dia. u-PVC Rainwater Downcomer (RWDC) pipes/SWR pipes with fitting & fixing with necessary fittings, short	R-m	32.00		
3	<b>Dismantling:</b> Cleaning the roof surface with wire brush, taking out the old tarfelt layer from roof by chipping and then dressing the mother slab accordingly.	Sqm	1500.00		
4	Dismantling of old pipes and fittings manually and taking all necessary safety measures	Rm	260.00		
5	Screed concrete in terrace(1:2:4) after rmaking proper slope at the rainwater outlets	Cum	30.00		
6	Fixing, tee, bend, shoe, P-trap,S-trap and connector pipes	Ls	1.00		
7	Removal of small plants, vegetation from the terrace and parapet walls	Ls	1.00		
8	Removal of debris from the site and dumping te same to nearest local municipality as directed	Ls	1.00		
9	Cement mortar (1:4) with water-proofing compound for closing the gaps and holes in walls and terrace	sqm	16.00		
<b>TOTAL VALUE OF THE WORK :</b>					

**Amount in words:**

**Note:** Estimate has been prepared as per Bank's approved rates for similar works  
Goods & Services Tax (GST) shall be paid extra as admissible on final bill.

**Signature of the Contractor with Official Seal**

*# Bank reserves the right to select any material out of the specified make.*