

PRICE BID

PROPOSED CIVIL WORKS AT STATE BANK OF INDIA, SME BRANCH, PANIPAT (HR)

S.No.	DSR no.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
1	<u>DISMANTLING WORK:</u>					
1.1	15.70	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge				
	15.7.4	In cement mortar	10.00	cum		
	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead				
1.2	15.23.1	For thickness of tiles 10 mm to 25 mm	312.50	sqm		
2	<u>BRICK WORK 4.5" thick walls</u>					
	6.13.2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.				
	6.13.2 +6.15	Cement mortar 1:4 (1 cement :4 coarse sand)Extra for providing and placing in position 2 Nos 6mm dia. M.S. Bars at every third course of half brick masonry.	68.00	sqm		
3	<u>PLASTER WORK</u>					
	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under,including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.				
	14.1.2	1:4 (1 cement: 4 fine sand)	120.00	sqm		
4	<u>RCC LINTEL</u>					
		RCC lintel for doors / windows / opening including steel reinforcement and bending & binding of steel, inclusive of shuttering / scaffolding as required, complete in all				

		respects.				
		steel reinforcement Main - 4nos.of 10mm dia, ring of 8mm dia @ 6"c/c				
4.1		4.5"x9" (for 3'-0" door)	2.00	each		
4.2		9"x9" (for 3'-6" door)	2.00	each		
5	<u>RCC SLAB</u>					
		Providing and laying RCC slab 2.5" thk for kitchen in RCC 1:2:4 including shuttering steel reinforcement as req.all complete as per direction of Engineer-in-Charge.	4.50	sqm.		
6	<u>VITRIFIED TILE FLOORING:</u>					
	NS	Providing and laying 1st quality vitrified tiles (Marble series Double charged-JOHNSON/ KAJARIA/ RAK- as approved by Bank's Engineer/Architect) of following sizes, as per design pattern on floor & skirting with chemical or adhesive/ cement as directed and joints to be filled with grout of approved colour, including dismantling existing floor tiles and disposal of malba from site, cutting wooden/ aluminum doors to match new floor level, preparing of surface & disposal of malba from site.				
6.1		32"X32" Vitrified tiles Double Charged-marble series.	288.00	sqm		
6.2		24"X24" Vitrified tiles Double Charged-marble series.	14.00	sqm		
7	<u>WALL TILES:</u>					
	NS	Providing and laying 1st quality ceramic glazed tiles of size 12"x24" fixed usin cem. Sand mortar, with groves filled with white cement & matching pigment, complete in all respects Make: Kajaria, Nitco, Somany	53.00	sqm		
8	<u>GRANITE</u>					
	NS	Providing and fixing Polished Granite stone in kitchen counter with 18 mm thick stone slab over a layer of 6mm thick High density Polystyrene foam which is fixed over the				

		counters using heatex/ equivalent adhesive. The slabs of stone shall be jointed with silicone adhesive of matching shade, all complete as specified and as directed by the Engineer-in-Charge. The front edge of the stone shall be made 36mm thick (by joining two pieces of stone) and provided with full round moulding along the visible edge of the counter.				
		Polished Granite stone slab of all colour and texture except Black, Cherry/Ruby Red	4.50	sqm		
9	<u>G.I PIPE</u>					
		Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.				
9.1		15 mm dia nominal bore	80.00	mtr		
9.2		20 mm dia nominal bore	40.00	mtr		
10	<u>SOIL WASTE DRAINAGE PIPE WORK</u>					
		Providing & fixing PVC(SWR) Pipes Type B, heavy class conforming to S13592-1992. (PRINCE / SUPREME / DIPLAST/ ASTRAL), including necessary fittings like bend, offset, collars etc., complete. Rates to include cutting/ chasing walls, floor, fixing pipe & making good the damages with cement mortar AND CONNECTING UPTO TO EXISTING EXTERNAL MANHOLES, complete in all respect.				
10.1		75 mm dia	20.00	mtr		
10.2		100 mm dia	20.00	mtr		
11	<u>CP FITTINGS & ACCESSORIES</u>					
		<i>NOTE: The scope of work shall include removal of old fittings & fixtures wherever applicable. Making chase / holes & repairing them, complet in all respects. No extra payment shall be allowed for any incidental as above.</i>				
11.1		Providing & fixing 15mm dia CP Bib Cock with CP wall flange, complete.	3.00	nos.		

		MODEL = FLR.5047N of Jaquar or equivalent of Cera /SOMANY				
11.2		Bibcock Long Body: Providing & fixing 15mm dia CP Long Body Bib Cock with CP wall flange, complete.	1.00	nos.		
		MODEL=CON.107KV of Jaquar or equivalent of Cera				
11.3		Providing & fixing 15mm dia CP Angle valve A with CP wall flange, complete.	7.00	nos.		
		MODEL = FLR-5053N of JAQUAR or equivalent of Cera / Hidware				
11.4		Providing & fixing 15mm dia CP Pillar cock (JAQUAR FLR-5015), complete.	1.00	nos.		
		MODEL FLR-5015 of JAQUAR, complete.				
11.5		Providing & fixing 15mm dia CP Pillar cock , auto closing type, complete.	1.00	nos.		
		MODEL=PRS-031 JAQUAR ,complete.				
11.6		Providing & fixing CP jali (heavy duty) with CP outer ring, complete.	9.00	nos.		
11.7		Providing & fixing single bowl Stainless Steel Kitchen Sink size 22"x18"x8" including cutting & shaping granite slab & filling the gaps with cement grout with matching color pigment around the edges of Sink, including CP waste & PVC drain pipe.	1.00	nos.		
		MODEL Flamingo of HINDWARE or equivalent of JAINA/NEELKANTH				
11.8		Providing & Fixing floor mounted one piece EWC including flushing cistern with dual flush (3/6ltrs) including all fittings & fixtures, water jet, seat cover complete in all respects. Model Aspiro S-100 of Hindware or equivalent of Cera/Somany/Parryware	3.00	nos.		
11.9		Providing & fixing table top Wash Basin of size 515x415x145mm, including CP waste and CP BOTTLE TRAP, etc complete in all respects	2.00	nos.		
		MODEL: WHB: CRESPO (Cat No. S2020171) of				

		CERA / equivalent of JAQUAR/SOMANY				
11.10		Providing & fixing urinal 385x325x635 including CP bottle trap, complete in all respects.	2.00	nos.		
		MODEL=URSWHT-13253N of JAQUAR /equivalent of CERA/SOMANY				
11.11		Providing & fixing 600x450 mm or as directed, beveled edge mirror 5.5 mm superior glass (ATUL/ SAINT GOBBIN) complete with 6 mm thick hard board ground fixed to wooden cleats & CP brass screws, washers & clips etc. complete.	3.00	nos.		
12	<u>ACRYLIC PAINT INCLUDING PRIMER</u>					
	13.83	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.				
	13.83.2+ 13.85.3	Two coats With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	200.00	sqm		
13	<u>ENAMEL PAINT</u>					
	13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	13.61.1	Two or more coats on new work	64.00	sq.m.		
14	<u>DOOR WITH CHOWKHAT</u>					
		Providing & fixing 35mm thick solid core flush with 35 x 15mm beech wood beading around with 1 mm laminate on both sides including necessary hardware viz., door stopper, door mortise lock, handles, brass hinges of approved make & equality melamine polish finish to all beech wood members etc., complete as directed.				

14.1		Single Shutter 2'-6"x7'-0" including chowkhat 5"X2.5"with single rebate	4.00	nos.		
14.2		Single Shutter 3'-0"x7'-0" including chowkhat 5"X2.5"with single rebate	1.00	nos.		
		Note: (i) All wood to be sprayed with anti termite and anti borer spray. 5 CONCRETE WORK (CAST IN SITU)				
15	<u>WATERPROOFING</u>					
	22.3	Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C., kitchen and the like consisting of:				
		(i) Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface.				
		IIInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface				
		IIIrd course of applying blown or residual bitumen applied hot at 1.7 kg. per sqm of area.				
		IVth course of 400 micron thick PVC sheet. (Overlaps at joints of PVC sheet should be 100 mm wide and pasted to each other with bitumen @ 1.7 kg/sqm).	23.00	sq.m.		
		TOTAL				
Amount in Words						