

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION & INTERIOR WORK'S OF GROUND FLOOR OF HOSTEL BUILDING AT SBILD INDORE. | | | | | |
|--|--|-----|------|------|--------|
| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
| | CIVIL WORK'S | | | | |
| 1 | REPAIRING OF INTERNAL PLASTER /CRACKS | | | | |
| | Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including necessary staging work, disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. | | | | |
| | With cement mortar 1:4 (1 cement : 4 fine sand) | 425 | Sqm | | |
| 2 | Providing & laying 12 mm thick Plastering of walls and ceiling with cement mortar 1:4, curing, staging wherever Necessary after cleaning the existing surfaces, chipping of old plaster etc complete | 100 | SQM | | |
| 3 | Providing & laying Vitrified Floor tiles | | | | |
| | Providing and laying "Doubly Charged"(Italian Marble Shades) white base vitrified floor tiles 600x 600 as per selection and approval of Authorities, different sizes and 9-10 mm thick with water absorption less than 0.08% and conforming to IS : 15622, as approved by Architect, in all colors and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Make johnson, Kajaria, Somany, Nitco (Basic Rate Of Tiles 800/- sqm) | 465 | Sqm | | |
| 4 | RUBBER MAT FLOORING FOR PLAY AREA | | | | |
| | Providing and laying Rubber mat Flooring 6.5mm tk. Any Colour for Play Area as per selection and approval of Authorities, including all amteria, labour etc complete of make wonderfloor or EQ | 95 | Sqm | | |
| 5 | Providing & fixing of Vitrified wall tiles in Dado for toilets | | | | |
| | Size- 600 x1200 mm of make Simpolo, Kajaria, Nitco, Bell, Johnson, Somany etc, or equivalent in first quality Joints to be filled and finished neat with cement grout as per specifications including cutting at traps, mitring of joints if required cleaning applying acid wash curing etc. including all labour, materials etc complete at all levels. Make- Kajaria, Nitco, Johnson, Somany etc, Note- Including all material , labour etc complete. (Basic Rate Of Tiles 950/- sqm) | 205 | Sqm | | |
| 6 | Granite Work's | | | | |
| | Providing, fixing at site 17-19mm thick black coloured Granite stone on the bottom, sides, top of window periphery, Self and sill, , with necessary moulding at edges, fixing with araldite wherever required including cutting, grinding, moulding, making necessary holes, metallic Anchor fasteners , making necessary provision for fixing of MS Grill and windows, all contingencies etc complete. (Basic Rates- 2100/- sqm) | 35 | sqm | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|------|------|------|--------|
| 7 | Granite Door Frame : | | | | |
| | Granite Frame :Providing and fixing door frame wide-150 mm (opening size 2.10 m x 0.9 m) made of approved shade of 19.0mm thick granite, with necessary Rebate, to be fixed with Araldite as per the given shape, necessary moulding of edges of granite to be rounded & polished, etc. Necessary holes, etc. to be made for fixing various hardware's, etc complete.. | 75 | RM | | |
| 8 | M.S GRILL | | | | |
| | Providing and fixing at site M.S. grills of required pattern to be fixed in brick wall to be grouted including concreting work, frames of windows etc. with M.S. flats, square or round bars etc. including 2 coats of steel primer, and two coats of approved shade of synthetic enamel, the cost shall include all labour, materials, contingencies etc complete. | 1700 | KG | | |
| 9 | Plastic Emulsion Paint : | | | | |
| | Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/distemper/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty not equivalent. minimum 2 coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete as per the instructions of the Bank | 810 | Sqm | | |
| 10 | Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, Walls : | 30 | Sqm | | |
| | Providing & applying Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, walls, etc. Removing, scrapping & cleaning the existing enamel paint. Then first coat of primer to be applied. After The enamel paint of approved shade shall be applied in minimum 3coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete | | | | |
| 11 | TEXTURED PAINT | | | | |
| | Painting on wall with "Self Texture" textured paint as per design including final coat of colour, all materials , labour etc. complete. | 130 | Sq m | | |
| 12 | REMOVING OF EXISTING WINDOW WITH GRILL | | | | |
| | Removing of existing windows (steel or wood) shutter including chowkhats, M.S Grill , holdfasts etc. complete and stacking within 50 metres lead including repairing of damage window surface , labour etc complete. | 70 | SQM | | |
| 13 | REMOVING OF EXISTING DOOR | | | | |
| | Removing of existing flush Door shutter and stacking within 50 metres lead including repairing of damage surface , labour etc complete. | 12 | each | | |
| 14 | REMOVING OF EXISTING DOOR WITH FRAME | | | | |
| | Removing of existing Toilet doors including chowkhats, holdfasts etc. complete and stacking within 50 metres lead including repairing of damage surface , labour etc complete. | 18 | each | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|-----|------|------|--------|
| 15 | REMOVING OF OLD VITRIFIED+ TOILET FLOOR & WALL TILE | | | | |
| | Removing of existing vitrified tiles, toilet tiles wall, floor including of dumping wast material out side the site with in 5 km,transportation labour etc complete | 450 | SQM | | |
| 16 | DISMENTALLING OF EXISTING TOILET FLOOR SUNK | | | | |
| | Excavation of existing toilet sunk floor including of dumping waste material out side the premises 5 km ,transportation labour etc complete | 25 | CUM | | |
| 17 | FILLING | | | | |
| | Filling & Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs and finishing top with water proofing compound including all material, labour etc complete. | 15 | CUM | | |
| 18 | PCC WORK | | | | |
| | PCC 1:3:6 work below external flooring and below plinth protection including all materials, labour etc complete, ,including ramming , curing for 10 days etc complete. | 5 | CUM | | |
| 19 | Sanitary Works : | | | | |
| | <u>EUROPEAN W.C WALL HUNG WITH CONCEALED WATER TANK FOR TOILETS</u> | | | | |
| a | Providing and fixing white vitrous Wall Mounted European WC ENIGMA of Jaguar/Hindware/Parryware or Eq. Make IGBC Certified – a. Wall Hung EUROPEAN WC b. flush valve inlet, outlet, anti syphonic pipe etc. (if required) complete c including making chases and holes in floors and walls and repairing the same with cement mortar (1:3) plastering, tiling etc. d Flush Valve Dual Flush Concealed Body Type Jaquar make Note- include all fittings jointing material, labour and making connection with the existing line complete. (Basic Rates- 12000/- Nos) | 14 | Nos | | |
| | <u>WASH BASIN counter Top type</u> | | | | |
| b | Providing & Fixing at site Counter Top type Wash basin of oval or approved shape size, to be fixed in Black coloured Granite Platform with push button type Long body Bib cocks off Parko, Plumber, Jacquar make including CP heavy duty fittings all accessories such as PVC connection, Angle cock all materials, labour, 'materials, etc complete Excluding cost of Black granite counter top to be paid separately (Basic Rates-8000/- Nos) | 14 | Nos. | | |
| c | <u>HEALTH FAUCET</u> | | | | |
| | Providing & Fixing at site Toilet Health Faucet with wall hook , 8mm diameter and 1.2 meter flexible pipe including all fittings, material , labour etc complete. Jaguar/Hindware/Parryware or Eq. make as per the site requirement etc complete. (Basic Rates- 1400/-Nos) | 14 | Nos. | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|-------------------|-------------------|------|--------|
| | Plumbing Works : | | | | |
| d | Providing and fixing in position bib cock. Angular, Stop Cock with Wall Flange -Jaguar/Hindware/Parryware or Eq. make or equivalent including all required connections and settings for proper functioning to the Engineer's satisfaction.(Basic Rates-1050/- Nos) | 88 | Nos | | |
| e | Providing and fixing in position two way bib cock. Jaguar/Hindware/Parryware or Eq. Make IGBC Certified including all required connections and settings for proper functioning to the Engineer's satisfaction. (Basic Rates- 1200/- Nos) | 14 | Nos | | |
| f | Providing & Fixing at site Jacquar make wall mixture IGBC Certified to be fixed at site including all necessary connections , fittings, cost of top shower 300 x 300mm all labour, ,materials, etc complete (Basic Rates- 5000/- Nos) | 14 | Set | | |
| g | Providing and fixing in position 15mm Class 'B'CPVC pipe of approved ISI branded complete with fittings Tees, Bends etc, Makes: Prince, Supreme, Astral | 150 | Rmt | | |
| h | Providing and fixing in position 20mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, Makes: Prince, Supreme, Astral | 250 | Rmt | | |
| i | Providing and fixing in position 25mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, | 350 | Rmt | | |
| j | Providing and fixing brass/ gun metal high pressure full way or gate valves with MS handle head complete with fitting, Teflon tape, testing etc. | 13 | Nos | | |
| k | Providing and fixing Pvc Pipe for soil waste/rain water/drainage disposal of superior Indian make such as Kisan, Premium, Supreme, Prince or Kasta i/c jointing with rubber ring, adhesive lubricant solvent cement with PVC clips bends, joints, bends with doors, etc. fittings as per site requirement with testing etc. complete.(All floor) including scaffolding, 75 mm PVC pipes 110 mm PVC pipes 150 mm PVC pipes | 150 200 300 | Rmt Rmt Rmt | | |
| l | Providing and fixing at site towel stand 450 x300 mm wide Stainless Steel heavy duty to be fixed at site with metallic Anchor fasteners etc complete of Jaguar/Hindware/Parryware or Eq. Make | 14 | Nos | | |
| m | Towel ring SS Finished Squar type Jaguar/Hindware/Parryware or Eq. Make | 14 | NOS | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|-----|------|------|--------|
| n | Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of approved make including stainless steel jali, including all materials, labour etc complete. | 30 | Nos | | |
| | | | | | |
| o | SHOWER PANEL(200X200) | | | | |
| | P/Fixing of shower IGBC Certified with Arm in toilets as per site requirement including all fittings etc complete (Basic Rates-1600/-Nos) | 14 | Nos | | |
| | | | | | |
| 20 | GYSER | | | | |
| | Providing and fixing 15.00 liter Gyser 5 Star Rating including all fitting , labour etc complete Make- Orien, Havells, Crompton (Basic Rates-7000/- Nos) | 14 | Nos | | |
| | | | | | |
| 21 | Dismantling W.C. Indian/ European Pan of all sizes ,pipe, wash basin, bib cock , pipes etc complete including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in Charge. (First floor Toilets) | 14 | JOB | | |
| | | | | | |
| 22 | BRICK WORK (for ventilation packing) | | | | |
| | 100mm Half brick masonry with common burnt clay Local Best available bhatta/ Chimney Bricks of class designation 40 in superstructure above plinth level up to floor 3 level, including laying of 50mm Thick RCC Band at every 1.20 M apart with 2 nos 8.0mm thick Ms tor Bars including laying, bending all materials, etc complete. | 12 | SQM | | |
| | Cement mortar 1:4 (1 cement : 4 coarse sand) | | | | |
| | | | | | |
| 23 | 12-15 mm cement plaster (Internal) over the brick wall surfaces inside plaster over double or single brick wall of mix | | | | |
| | 1:5 (1 cement: 5 fine sand) | 20 | SQM | | |
| | | | | | |
| | TOTAL AMOUNT FOR CIVIL WORK'S (A) | | | | |
| | | | | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|------|------|------|--------|
| | INTERIOR WORK | | | | |
| 1 | REPAIR & RENOVATION EXISTING MAIN DOOR | | | | |
| | Repairing of existing main Entrance door with change of Damage Glass , beeding and Wooden polish ,repair of damage Surface etc complete with change of fittings | 1.00 | JOB | | |
| | Brass SS Finished 200mm tower bolts1 Nos, | | | | |
| | SS finish screws | | | | |
| | SS Brush finished L drops 1 Nos | | | | |
| | Door stopper 1 Nos, | | | | |
| | 2 Nos SS finished 300mm Handles | | | | |
| 2 | NEW FLUSH DOOR + 1.0mm Lamination | | | | |
| | Providing, making & Fixing of Flush door at site,:- 32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on both sides Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm Note- Including all materials, labour, transport, taxes, delivered and placed in position at site of work. (Note- Board Make-Century, Green Ply & Duro. & Fittings Godrej & EBCO) | 30 | SQM | | |
| 3 | ONE SIDE RELAMINATION AND ONE SIDE ACP SHEET FOR TOILET DOOR | 30 | SQM | | |
| | Providing, making & Fixing of Flush door at site,:- 32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on one sides & 3.0mm ACP Sheet other Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm Note- Including all materials, labour, transport, taxes, delivered and placed in position at site of work. | | | | |
| 4 | CUBBOARD SHUTTER WITH SHELVES | 70 | SQM | | |
| | Providing & Fixing at site 25 mm thick EHDMMR Ply door shutters + frame to be fixed on outer of existing CUBBOARDS after removing of Old shutters & Frame, to be finished with 1.0mm approved shade of laminated finish and internal of the sutter to have 0.8mm laminated finish, The cost of Cupboard shall include 3-4 nos internal shelves to be made with 18.0mm EHDMMR ply as per given design with 0.8mm lamination on top & bottom, all internal surface of cupboards to be finished with 0.8mm laminated finish, the cost shall include all materials, labor, hinges 150mm SS finished handles, magnetic catchers, all labour, materials, contingencies etc complete, note all external surface measurement of cupboard to be considered (Note- Make- Century, Green Ply & Duro.) | | | | |
| 5 | REMOVING OF EXISTING BEDS, TABLES & PANELING | 1 | JOB | | |
| | Removing/ Dismantling of existing Beds,tables & paneling and shifting as per direction of department including all labour etc complete. (Note- Make- Century, Green Ply & Duro.) | | | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|-------|------|------|--------|
| 6 | 100 MM wide PLY BOXING WITH LAMINATE FOR BED BACK | 20.00 | SQM | | |
| | Providing and fixing Ply backing in Box shape as per the given design & drawing Boxing with 18mm EHDMMR Ply with all exposed surface to have 1.0 mm thick laminated finish including all fitting , labour, material etc complete (Note- Make- Century, Green Ply & Duro.) | | | | |
| 7 | SINGLE BED (0.90X1.830) | | | | |
| | Providing and fixing at site Single Bed for room to be made of 100x38.0mm Teak wood frame and Legs, and the Bed top shall be of 12.0mm EHDMMR Ply, with necessary supports , the wooden frame to have Regular polished finish, the cost shall include all labour, materials, etc complete (Note- ply Make- Century, Green Ply & Duro.) | 24.00 | NOS | | |
| 8 | STUDY TABLE- 3'6" x1'6" | | | | |
| | Providing and fixing at site Study Table for room to be made of 19.0mm EHDMMR Ply, with 1.0 mm Laminate as per design & Drawing, the cost shall include all labour, materials, etc complete (Note- ply Make- Century, Green Ply & Duro.) | 24.00 | NOS | | |
| 9 | S.S CURTAIN ROD | | | | |
| | Providing and fixing at site "Stenless Steel" 25mm dia curtain rods, including side brackets with carved heads at ends including all fittings , labour material etc complete. | 30 | RM | | |
| 10 | CURTAIN | | | | |
| | Providing and fixing at site Curtain of approved colour & pattern including stitching as approved, fixing of curtain rings all fittings , labour material etc complete. (Basic Cost Fabric-300 /sqm) | 50 | SQM | | |
| 11 | TV Panelling | | | | |
| | Providing & fixing wall panelling behind the TV with 19.0mm thick panelling as per the given design to be finished with 1.0mm thick laminated finish all the external edges to have matching shades of polish, The cost shall include all materials , all labour materials contingencies etc | 20.0 | SQM | | |
| 12 | Luggage / Storage | | | | |
| | Providing & fixing at site Luggage Rack/Storage of approved design & drawing including sliding drawers in 19.0mm EHDMMR ply and 1.0mm laminated finish of approximate size 900 x 450 x 700mm including all labour, materials, etc compete (Note- Make- Century, Green Ply & Duro.) | 12.0 | NOS | | |
| 13 | Side Storage | | | | |
| | Providing & fixing at site Side Storage as per design & drawing including 2 Nos sliding drawers in 19.0mm EHDMMR ply and 1.0mm laminated finish of approximate size 750 x 450 x 450mm including all labour, materials, etc compete (Note- Make- Century, Green Ply & Duro.) | 12.0 | NOS | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|-------|------|------|--------|
| 14 | Bed Back Wall Panelling & Other area | | | | |
| | Providing & fixing wall panelling for Bed Bach with 19.0mm thick panelling with Aluminium 50x25x1.6 mm tk framing as per the given design to be finished with 1.0mm thick laminated finish all the external edges to have matching shades of polish, The cost shall include all materials , all labour materials contingencies etc | 165.0 | SQM | | |
| 15 | False Ceilings : | | | | |
| | Note : i) Rate to be included for all kinds of profiles and cut outs required for light fixtures, Speakers, Smoke detector, trap doors and AC grill in the ceiling. Provision for light fittings, AC grills and diffusers have to be made at no extra cost supported with tees, Angles, etc. suitably fixed all complete as per drawing and direction. The area of these cutouts which is less than 0.5 sqmt for one unit will not be deducted while measuring the ceiling area. ii) The contractor must co-ordinate with electrical & AC contractor for working out various levels for the false ceiling & make the marking on the walls / columns before starting the false ceiling work. | | | | |
| | Gypsum Board False Ceiling : | 400 | Sqmt | | |
| | Providing, making and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres. | | | | |
| | 12.5mm tapered edge Gypboard (conforming to IS 2095-1982) is then screw fixed to ceiling section with 25mm dry wall screws at 230mm centres. Screw fixing is done mechanically with drilling machine with suitable attachment. Finally tapered edges of the Gypsum boards are to be jointed and finished so as to have a flush look which includes filling and finishing with jointing compound, joint paper/fibre tape and two coats of dry wall top coat suitable for Gypsum board etc. complete as per the recommended practices / specifications of the manufacturer. Including two coats of primer suitable for gypsum board two or more coats of plastic emulsion paint of approved shade and also including making necessary openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitable fixed all complete as per drawing and specification and direction. Rate to be inclusive of shadow profile at the junction of wall & ceiling, in between of ceiling, etc. complete. | | | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|---|------|------|------|--------|
| 16 | Full Height Partly Glazed/ Solid Wooden Partitions (Including Door) : for office | | | | |
| | Providing and fixing full height partly wooden, partly glazed/ Solid partitions- specifications (Measurement shall be taken up to finished partition level & not of frame work and sal wood member shall go up to slab/beam soffit) Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways 8 mm thk. MR plywood Termite & Borer proof from both the sides 1.0mm thick approved shades of laminate 5 mm thick float glass (for Partly Glazed Partitions) Etching as per approved design including 32mm partly glazed/ fluse door with teak wood Beading 1 mm lamination on both sides 8 mm plain glass, (for partly Glazed Doors) with Frame of 100mm x 50 mm, Note -Including all fittings,material, screw, labour etc. Complete. | 16 | SQM | | |
| 17 | Removing of Existing Wooden/ Aluminium Partition including Repair damage surface at throw the waste material out side the premises or as per direction including all labour etc complete | 1 | JOB | | |
| 18 | Providing and fixing designer type 5.0mm mirror with wooden frame as required at site, of standard make, with 3" Teak wood framing on all sides to be fixed at site over the existing wall/ wall panelling | 25.0 | SQM | | |
| 19 | DOOR JAMB | | | | |
| | Proving and fixing at site 19mm Thick EHDMMR Ply DOOR Jambs as per the required pattern, including giving of necessary rebate for fixing of Flush door shutter, including lamination with 1.0mm thick laminated finish, including all materials, labour, all contingencies etc compete. with lamination for internal doors(Note- Make- Century, Green Ply & Duro.) | 70 | sqm | | |
| 20 | MOSQUITO MESH fiber Jali in Ventilators | | | | |
| | Providing and fixing at site Mosquito mesh fiber jali for Window/Ventilation , to be fixed to existing windows with velcrow tape to be made to existing window size including all materials, labour, contingencies etc complete. | 10.0 | SQM | | |
| 21 | ALUMINIUM WINDOW Bronze Anodised : Three track | | | | |
| | Providing and fixing Aluminium Windows Sampion Anodised to be sliding with 3 track using standard approved section 1.3 mm thick and section of <u>Jindal, Hindalco, Mann or equivalent approved make and of size</u> , 5.5mm float glass, to be provided with rubber gaskets, locks, handles, silicon sealants on all edges, Complete as per design and direction of Engineer – in charge, including fixing of SS Mosquito Net in the sliding shutter including all accessories, locking arrangement, fixing of silicon sealant on the external edges, all materials. labour etc complete. | 55 | Sqm. | | |

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL & INTERIOR RENOVATION WORK'S OF GROUND FLOOR OF
HOSTEL BUILDING AT SBILD INDORE.

| S.NO | ITEM AND SPECIFICATION | QTY | UNIT | RATE | AMOUNT |
|------|--|-----|------|------|--------|
| 22 | CABIN TABLE P / F Cabin Table having a size of 5'6" X 2' 3" X 2' 6" ht. in 19mm thk BWP Grade Ply of approved make for table top and sides. Table side credenza having a size of 4' X 1' 6" X 2' 6" ht. in 19 mm MR ply with a drawer unit & openable shutters etc as per the design / drawing, finished in 1 mm thk laminate of approved make and shade etc. complete. All the exposed surfaces should be provided with 1mm thick laminate matching to the table top laminate. For CPU : P/F 19 mm thk ply stand 18" x 9" to be fixed with on the verticals/ apron of the table as directed. All exposed surfaces whether inner side or outside must be 1mm laminated with approved laminate shade. | 1 | Nos. | | |
| 23 | NUMBER PLATE Providing and fixing Number plat for Rooms as per pproved design including all material, labour etc complete | 14 | NOS | | |
| 24 | Providing and fixing GLASS SHELVES FOR TV SET UP BOX | 12 | NOS | | |
| | TOTAL AMOUNT FOR INTERIOR WORK (B) | | | | |
| | TOTAL AMOUNT (A+B) | | | | |