

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO (M.P).

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
CIVIL WORK'S					
A	INTERNAL RENOVATION WORK'S				
1	REPAIRING OF INTERNAL PLASTER /CRACKS				
	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including necessary staging work, disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.				
	With cement mortar 1:4 (1 cement : 4 fine sand)	150	Sqm		
2	PROVIDING & LAYING VITRIFIED FLOOR TILES WITH APPROVED TILE ADHESIVE				
	Providing and fixing 1st class premium quality, double charged 600 x 600mm vitrified tiles in floor, skirting "- (As per approved Colors & shades) of make Kajaria/ Johnson/ Somany etc. , or equivalent in first quality over the existing Flooring with approved Tile adhesive Note- Including all material , labour etc complete.(Basic Rate Of Tiles 800/- sqm)	700	Sqm		
3	REMOVING OF EXISTING TOILET FIXTURES WC, WASH BASIN, PIPES , ETC COMPLETE (TOILET+ WC+ BATH)				
	Dismantling W.C. Indian/ european Pan of all sizes , wash basin, bib cock , pipes etc complete including disposal of dismantled materials i/c malba all complete as per directions of Engineer-inCharge.				
A	TOILETS & W.C	13	NOS		
B	BATHS	13	NOS		
4	DISMANTALLING/EXCAVATION OF EXISTING TOILET , WC & BATHS FLOOR SUNK				
	Excavation of existing toilet sunk floor including of dumping waste material out side the premises 5 km ,transportation labour etc complete	13	CUM		
5	WATER PROOFING OF TOILET, WC & BATHS SUNK				
	Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C.,and toilet the like consisting of :				
	(i) Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface. (ii) IInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface. (iii) IIIrd course of applying blown or residual bitumen applied hot at 1.7 kg. per sqm of area. (iv) IVth course of 400 micron thick PVC sheet. (Overlaps at joints of PVC sheet should be 100 mm wide and pasted to each other with bitumen @ 1.7 kg/sqm).	55	SQM		
6	FILLING WITH BRICK BATS (FOR TOILETS & BATHSSUNK)				

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
	Filling & Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs and finishing top with water proofing compound including all material, labour etc complete.	10	CUM		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
7	PCC WORK (FOR TOILETS & BATHS)				
	PCC 1:4:8 work for Toilets & Baths including all materials, labour etc complete, including ramming, curing for 10 days etc complete.	3.1	CUM		
8	PROVIDING & FIXING OF NON-SKID VITRIFIED FLOOR TILE FOR TOILETS AFTER REMOVING OF EXISTING TILES				
	Size- 600 x600 mm of make Simpolo/ Kajaria/ Johnson/ Somany etc , or equivalent in first quality Joints to be filled and finished neat with cement grout as per specifications if required cleaning applying acid wash curing etc. after removing of existing tiles and throwing of the waste material to other nearby site including transportation all labour, materials etc complete at all levels. (Basic Rate Of Tiles 600/- sqm)	37	Sqm		
9	PROVIDING & FIXING OF VITRIFIED WALL TILES IN DADO FOR TOILETS AFTER REMOVING OF EXISTING WALL TILES				
	Size- 600 x1200 mm of make- Kajaria,/ Johnson/ Somany etc, or equivalent in first quality Joints to be filled and finished neat with cement grout as per specifications including cutting at traps, mitring of joints if required cleaning applying acid wash curing etc. after removing of existing wall tiles and throwing of the waste material to other nearby site including transportation all labour, materials etc complete at all levels. (Basic Rate Of Tiles 600/- sqm)	260	Sqm		
	SANITARY WORKS :				
10	WALL MOUNTED EUROPEAN WC				
	Providing and fixing white vitreous Wall Mounted European WC of Hindware/Parryware /Johnson Pedder/ Kohler or Eq. make- Wall Hung EUROPEAN WC flush valve inlet, outlet, anti symphonic pipe etc. (if required) complete including making chases and holes in floors and walls and repairing the same with cement mortar (1:3) plastering, tiling etc. Flush Tank Dual Flush Concealed Body Type Jaguar/Hindware/Parryware make Note- include all fittings jointing material, labour and making connection with the existing line complete (Basic Rate 8500/-Nos)	13	Nos		
11	WASH BASIN + TAP + FITTINGS				
	WASH BASIN : Providing and fixing white vitreous wash basin with Half turn of Hindware/Parryware/Johnson Pedder/ Kohler or Eq. make & Pedestal with CI brackets, 15 mm heavy pillar cock, 32mm cp brass coupling, waste pipe etc. The rate should include all fittings jointing material, labour and making connection with the existing line complete. (Basic Rate 3000/-Nos)	13	Nos		
12	CPVC PIPE				
a.	Providing and fixing in position 40mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, (for Water Supply Tube well to Tank)	250	Rmt		
b.	Providing and fixing in position 25mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc,	300	Rmt		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORKS FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
c.	Providing and fixing in position 20mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, Makes: Prince, Supreme, Astral	200	Rmt		
d.	Providing and fixing in position 15mm Class 'B' CPVC pipe of approved ISI branded complete with fittings Tees, Bends etc, Makes: Prince, Supreme, Astral	150	Rmt		
13	PROVIDING AND FIXING G.I. PIPES COMPLETE WITH G.I. FITTINGS AND CLAMPS, I/C CUTTING AND MAKING GOOD THE WALLS ETC.				
a.	40 mm dia nominal bore	10	Rmt		
b.	25 mm dia nominal bore	10	Rmt		
c.	20 mm dia nominal bore	10	Rmt		
14	Providing and fixing in position bib cock. Angular, Stop Cock with Wall Flange Hindware/Parryware/Johnson Pedder or equivalent Make IGBC Certified upon approval complete including all required connections and settings for proper functioning to the Engineer's satisfaction. (Basic Rate – 900/- Nos)	26	Nos		
15	Providing & Fixing CP finish Two Way Bib cock with wall flange Jaguar/Hindware/Parryware/Johnson Pedder or Eq. Make IGBC Certified along upon approval make and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc.complete (Basic Rate – 1150/- Nos)	13	Nos		
16	HEALTH FAUCET Providing & Fixing at site Toilet Health Faucet with wall hook , 8mm diameter and 1.2 meter flexible pipe including all fittings, material , labour etc complete. Hindware/Parryware/Johnson Pedder or Eq. make as per the site requirement etc complete. (Basic Rate – 1050/- Nos)	13	Nos.		
17	Providing & Fixing CP finish Swan type bib cock of Hindware/Parryware/Johnson Pedder or equivalent make upon approval and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc.complete (Basic Rate – 950/- Nos)	26	NOS		
18	Providing and fixing Mirror of make modiguard/ saint gobain etc or equivalent of height 1220 mm complete with flat polished edges, fitted on site on 12 mm ply base, base having wooden lipping border and finished with laminate if instructed. The mirror shall be either pasted on the ply with silicon adhesive or fitted with stud-head screws with air gap in between (minimum 6 nos average per location) or both as per approval complete to the Engineer's satisfaction.	10	SQM		
19	WALL MIXER Providing & Fixing at site wall mixture make- Hindware/Parryware/Johnson Pedder/Kohler or Eq including all necessary connections , fittings, all labour, ,materials, etc complete (Basic Rate – 3200/- Nos)	12	Set		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
20	Providing and fixing Pvc Pipe for soil waste/rain water/drainage disposal of superior Indian make such as Kisan, Premium, Supreme, Prince or Kasta i/c jointing with rubber ring, adhesive lubricant solvent cement with PVC clips bends, joints, bends with doors, etc. fittings as per site requirement with testing etc. complete.				
a.	75 mm PVC pipes	85	Rmt		
b.	100 mm PVC pipes	125	Rmt		
21	Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of approved make including stainless steel jali, including all materials, labour etc complete.	34	Nos		
22	Providing and fixing at site towel rail 600- 900mm wide Stainless Steel heavy duty to be fixed at site with metallic Anchor fasteners etc complete of Hindware/Parryware/kohler make or EQ. (Basic Rate – 900/- Nos)	13	Nos		
23	Providing and fixing at site Shower Panel 200x200 mm Stainless Steel heavy duty with Conealed Angle Cock to be fixed at site with metallic Anchor fasteners etc complete of Hindware/Parryware make or EQ. (Basic Rate – 1250/- Nos)	13	Nos		
24	Providing and fixing brass/ gun metal high pressure full way or gate valves with MS handle head complete with fitting, Teflon tape, testing etc.	12	Nos		
25	Providing and fixing stainless steel sink 1 number Nirali Make or equivalent as per approval of size approx. 18inch X 24 inch or as available per approval in platform complete including all required cutting, filling, preparation for installation, connecting waste coupling, waste pipe, adhesives/ sealers/ fillers etc.	12	NOS.		
26	Disconnecting damaged overhead/terrace PVC water storage tanks of any size (All Blocks) from water supply line and removing from the terrace including shifting at ground level as per direction of Engineer-in-charge	1	JOB		
27	Providing and placing and installing of New PVC Insulated Water Tank 1000 liter (triple layer) insulated Tank, including all fittings, union, bends, sockets all accessories, labour etc complete make – sintex, Rotomax or EQ	12	NOS		
28	Mirror polishing on marble work/Granite workwhere ever required to give high gloss finish complete. For kitchen platform	36	SQM		
29	KITCHEN WORK'S				
A	Providing and fixing Marble for below kitchen Platform with 19.0mm thick 2 nos Marble partitions of 500x 720mm to be fixed at the specified distance or as per drawings to be erected as base support,Use Existing Granite top & Mirror Polish including all material ,labour etc complete	75	SQM		
B	Providing and fixing at site front portion of below the platform to be covered with 19.0mm thick post formed laminated nuwood sections and the inside baskets shall be of SS Fittings Hittech, EBCO or equivalent, with adjustable hinges, all baskets, partitions, with 19mm MDF and molded & Laminated front panels, SS Brush finished Handel's EBCO Make SS Grade 306, as per the given design & drawing, The cost shall include all accessories, labour, materials, all fittings, contingencies if any, handels, stoppers etc complete.	40	RM		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
30	Removing/Dismantling Existing Windows with Grill including chowkhats, holdfasts etc. complete and stacking within 50 metres lead including repairing of damage window surface , Scaffolding labour etc complete.	82	each		
31	Dismantling Old doors shutter and stacking within 50 metres lead including repairing of damage surface , labour etc complete. (All Doors)	48	each		
32	Dismantling Old doors Dewas Frame (FOR TOILETS) within 50 metres lead including repairing of damage surface , labour etc complete.	9	each		
33	Repair & Re-polishing of Existing Kota Stone Flooring, skirting,and Replace Brocken Kota Stone with surface repair including all material, labour etc. Complete	140	Sqm.		
34	ALUMINIUM WINDOW BRONZE ANODISED : THREE TRACK	105	SQM		
	Providing and fixing Aluminium Windows Bronze Anodised to be sliding with 3 track using standard approved section and 5.0mm float glass, to be provided with rubber gaskets, locks, handles, silicon sealants on all edges, Complete as per design and direction of Engineer – in charge, including fixing of SS Mosquito Net in the sliding shutter including all accessories, locking arrangement, fixing of silicon sealant on the external edges, all materials, labour etc complete.				
35	NEW M.S. GRILL				
	Providing and fixing at site M.S. grills of required pattern to be fixed in brick wall to be grouted including concreting work, frames of windows etc. with M.S. flats, square or round bars etc. including 2 coats of steel primer, and two coats of approved shade of synthetic enamel, the cost shall include all labour, materials, contingencies etc complete.	2450	Kgs		
36	GRANITE WORK'S FOR WINDOW BOTTOM SILL				
	Providing, fixing at site 17-19mm thick black coloured Granite stone on the bottom, and sill, , with necessary moulding at edges, fixing with araldite wherever required including cutting, grinding, moulding, making necessary holes, metallic Anchor fasteners , making necessary provision for fixing of MS Grill and windows, all contingencies etc complete.	25	sqm		
37	S.S RAILING				
	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fixing the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the sides of waist slab/Treads with suitable arrangement as per approval of Engineer-in-charge. (Approx wt of Railing 10 kg per Sqm Mode of measurements: Area of Railing above finished floor level shall be measured). Make-Jindal or Eq.	22	SQM		
38	ENAMEL PAINTS TO DOORS, WINDOWS, GRILLS, METALLIC SURFACES, WALLS :	525	Sqm		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
	Providing & applying Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, walls, etc. Removing, scrapping & cleaning the existing enamel paint. Then first coat of primer to be applied. After The enamel paint of approved shade shall be applied in minimum 3coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete Make- Asian /Nerolac/ Berger				
39	PLASTIC EMULSION PAINT				
	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/distemper/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete as per the instructions of the Bank Make- Asian /Nerolac/ Berger	3200	Sqm		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
40	WHITE CEMENT BASED PUTTY ON INTERNAL WALLS				
	Providing and applying white cement based putty "Birla White" of average thickness 1.0 mm on internal walls, over the plastered surface to prepare the surface even & smooth without undulations including all materials, labour etc complete.	3200	Sqm		
41	NEW FLUSH DOOR + 1.0MM LAMINATION FOR ROOMS				
	Providing, making & Fixing of Flush door at site,:- 32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on both sides Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm Note- Including all materials, labour, transport, taxes, delivered and placed in position at site of work. (Note- Board Make-Century, Green Ply & Duro. & Fittings Godrej & EBCO)	80	SQM		
42	ONE SIDE RELAMINATION AND ONE SIDE ACP SHEET FOR TOILET DOOR	40	SQM		
	Providing, making & Fixing of Flush door at site,:- 32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on one sides & 3.0mm ACP Sheet other Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm Note- Including all materials, labour, transport, taxes, delivered and placed in position at site of work. Including all accessories.like				
	Sliding bolt with SS Brush Finish Godrej Or EQ				
	Tower Bolts SS Finished 125 mm				
	Heavy duty SS Hinges				
	Baby Latch (Bath room door Latch)				
43	GRANITE STONE DOOR FRAME				
	Providing and fixing at site 15 to 18 mm thick gang saw cut, mirror polished, premoulded and pre-polished, machine cut for Door frames of required size, approved shade, colour and texture laid with single rebate again made up of second piece of granite to be fixed to main piece with help of "Araldite" to be fixed over the Jambs of door openings over the Brick wall with 1:4 mortar (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding of Edges and polishing to edges to give high gloss finish etc. complete at all levels. The cost shall include of making necessary holes for Fixing of Steel screws and anchor fastners.	130	RM.		
44	BUY BACK				
	Buy Back old Existing M.S grill, Dewas window frames, Cow catcher pipes & sheds etc .	-1	NOS		
	TOTAL AMOUNT FOR INTERNAL RENOVATION WORK				

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
B	EXTERNAL RENOVATION WORK'S				
1	Removing of existing worn out external plaster as per existing site condition and redoing of 15-19mm thick external plaster 1n 1:4 cement mortar, including all materilas, labor, scaffolding etc complete./ including crack repairing	100	Sqm		
2	DISMENTALLING OF EXISTING CHAJJA SLOPE Dismantling Existing Elevation Element Chajja Slope Including throw out the waste material our site the premisess or as per direction of engineer including Scaffolding all material, labour etc complete	12	CUM		
3	REPAIRING OF EXISTING CHAJJA SLOPE Repairs to Chajja Elvation Elements with plaster of thickness 12 mm to 15 mm (1:4) including all material, labour ,scaffolding etc complete	44	sqm		
4	NEW BRICK WORK : Providing and laying Half Brick thick Brickwork in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete. including 2 nos 6 mm dia M.S bars at every third course of brick masonry in all floors	6	SQM		
5	PLASTER EXTERNAL SIDE Providing & laying 12-15 mm thick Plastering of walls and ceiling with cement mortar 1:4, curing, ladder use, cleaning, etc. complete all floors	185	SQM		
6	TERRACE WATER PROOFING Two coats of Brush application with 1.0mm thickness in two coats, Brush application with two components mixed together to be applied as per the manufacturer instruction over the existing for terrace water proofing, after cleaning of existing roof surface with all the dust, grit, fungus etc, and cleaning the surface with wire brush, all materials, labour etc complete.	480	sqm		
7	WEATHER COAT EXTERIOR EMULSION PAINT Two or more coats of exterior grade premium finish WEATHER COAT or EQ exterior emulsion of required colour on the external walls, including necessary staging etc complete. Make- Asian Ultima / Nerolac/ Berger	2100	Sqm		
8	Removing/dismantling of Old existing Rain water pipe and throw the wast material out side the site and direction of engg. Including all labour material etc complete.	1	JOB		
9	Providing and fixing at site 110mm dia PVC pipes for Rain water including all clamping, connecting properly with roof top khurras, scaffolding, all materials, labour etc complete	84	RM		
10	Dismenting of Existing shed with purline & all member including repair of damage surface and cleaning of site and throw out the waste material out site thre premisess or as per direction of engineers including all labour etc complete	1	JOB		
11	Main Boundary Gate Repair with change damaged members , Sliding bolt including Alignments gate , painting etc complete	2	NOS		
12	Removing old cow catcher & throw the waste material out site the premisess and repair damage area including all material, labour etc complete	1	JOB		
13	Structure steel work for New Cow catcher as per drawing including all fitting ,material, labour etc complete	100	Kgs		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORKS FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
14	Copra/ murum filling work for Plinth protection side including all material, labour etc complete	20	CUM		
15	P.C.C (1: 2:4) work for Drain bottom area, Paver side and Plinth Protection Repair work including Curing ,all material, labour etc complete	15	CUM		
16	Painting of Existing Paver Blocks with approved shade and Re-leveling of Pavers wherever Necessary	825	SQM		
17	PAVER BLOCK (REPLACE ONLY BROKEN BLOCKS) Providing and laying 65-80 mm thick any colored with pigment factory made cement concrete interlocking matching shape & size/ Look paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand/ stone dust, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	150	SQM		
18	PRECAST DRAIN SLAB Providing & laying etc. Pre-Cast Concrete work of 1:1.5:3 in Drain Slab including reinforcement, material, labour etc. complete.	7	CUM		
19	REPAIRING OF PLINTH PROTECTION (wherever necessary) Repairing of existing plinth protection with fill /repair all crack wherever necessary with m-20 concrete+ 75mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over the existing base and including finishing the top smooth.	210	sq m		
20	MAIN HOLE & CHAMBER REPAIR (wherever necessary) Repairing of Main Hole / Chamber with 1: 5 (Cement: sand) Plaster in Chamber inside and out side with repair of damage surface including all material, labour etc complete	15	NOS.		
21	Cleaning and de-silting and repair of gully trap/Rain water chamber chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in-charge.	30	NOS.		
22	Cleaning of chocked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and dechocking of sewer lines. De-chocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm	1	JOB		
23	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	1	JOB		
24	MAIN HOLE CHAMBER C.I COVER Providing and fixing C.I. cover with frame (light duty) total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : including all material , labour etc complete	20	NOS.		

TENDER & SPECIFICATIONS FOR PROPOSED CIVIL RENOVATION WORK'S FOR SBI STAFF QUARTERS AT KHAJURAHO

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
25	GULLY TRAP CHAMBER C.I COVER				
	Providing and fixing Gully Trap C.I. cover with frame (light duty) total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : including all material , labour etc complete	15	NOS.		
26					
	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including Excavation , filling ,all material,labour etc complete	1	NOS.		
B	<u>TOTAL AMOUNT FOR EXTERNAL RENOVATION WORKS</u>				
<u>ABSTRACT SHEET</u>					
A	TOTAL AMOUNT FOR INTERNAL RENOVATION WORK				
B	TOTAL AMOUNT FOR EXTERNAL RENOVATION WORKS				
	GRAND TOTAL				
	+ GST AS APPLICABLE				