

N.O.W. - FURNISHING OF STATE BANK OF INDIA						
CIVIL WORKS FOR THE VARIOUS WORKS FOR THE BANK HOUSE SRINAGAR						
BOQ FOR THE CIVIL WORKS.						
S.No.	DSR REF.	Item	Quantity	Units	Rate	Amount
1	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.5	1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	8.68	CU.M		
2		VITRIFIED TILE FLOORING 400MM X 400MM				
	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. (PAVER ANTISKID ROUGH TEXTURE 12MM THICK Tiles from Johnson and Johnson, Kajaria, Somany etc)	250.46	SQM		
	11.41.2	Size 400mm x 400mm				
3		FULL BRICK MASONARY				
	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level and in foundations (including the cost of excavation and re-filling as required) in all shapes and sizes in :				
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	2.68	cu.m		
4		PLASTERING				
	13.1	12 mm cement plaster of mix :				
	13.1.1	1:4 (1 cement: 4 fine sand)	12.55	SQ.M		
5	13.2	15 mm cement plaster on the rough side of single or half brick wall of mix :				
	13.2.1	1:4 (1 cement: 4 fine sand)	12.55	SQ.M		
6	NS	Plastering and repair of the existing damaged portion of lime surkhi as per CPWD specifications plastered as per required thickness for smooth finish for mouldings, cornices and plain portion as per site condition. The work shall include removal of any loose plaster complete.	60.00	SQ.M		
7	9.48	Providing and fixing M.S. grills/gate/shutter made of required pattern in frames of windows/openings etc. with M.S. flats, square or round bars, MS Sheets, SQUARE/RECTANGULAR PIPES, etc. complete with locking arrangement as per the direction of the engineer-in-charge including enamel finished coats over approved steel primer complete.	7.50	SQ.M		
8	NS	External Emulsion paint				
		Providing and applying External Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including one primer coat, complete in all respects (Colour to approval) applicable to old or new.	350.00	SQ.M		
		Total Value of Works				
		Note: GST shall be paid extra				