

PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR RACPC-WEST IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD						
Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.						
SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
[A]	FURNISHING WORK					
1	TABLES					
1.01	TABLE SIZE: 6'-0" X 2'-6" X 2'-6" HT. (T1) (For CM / CDCO/NPA/DOCUMENTATION)	10.00	NOS			
	Supplying and installation of Table as per the following description: Size 6'-0" x 2'-6". Table top shall be made from 18 mm thick commercial plywood with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Computer metal Key board tray with mouse pad of approved make shall be provided. Exposed surfaces of the cabinet shall have laminate, All internal surface will have 0.80 mm thick balacing laminate					
	Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing					
	Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.					
	Drawer Facia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed.					
	Ready made Foot rest , Readymade CPU trolley with caster and metallic cable Manager shall be provided in table. All exposed edges of teak wood shall have polished with smooth edges & corners					
	Exposed edges of Table Top, panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.					
	All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate of approved shade. Etc. complete.					
	As per drawing and instruction of Architect/Bank work to be Completed					
	FINISHING DETAILS IN NUTSHELL:					
	1) Table Top : 18 mm thick commercial plywood with equal sized 10mm thick back painted toughened glass					
	2) Front Apron & Sides : 1.0 mm thick Dark Laminate					
	3) Facing of Drawers : 1.0 mm thick Dark Laminate					
	4) All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate					
1.02	TABLE SIZE: 5'-0" X 2'-6" X 2'-6" HT. (T3)	3.00	NOS			
	Same as above Item-no-1.01 but 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. Table top finish 1.0mm thick laminate instead of back painted glass. (For PROC. / L & T / CDO / NPA STAFF / AUDITOR)					
1.03	TABLE SIZE: 6'-6" X 3'-0" X 2'-6" HT. (T6)	1.00	NOS			

PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR RACPC-WEST IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD						
Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.						
SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
	Supplying and installation of Table as per the following description: Table top shall be made from 18 mm thick commercial plywood with 1.00mm laminate. necessary intermediate support. as per detail drawings Exposed surfaces of the table shall have 1.0mm thick laminate All internal surface will have 0.80 mm thick balacing laminate. (For DOCUMENTATION)					
1.04	MEETING TABLE SIZE: 7'-0" X 3'-0" X 2'-6" HT. (T7)	1.00	NOS			
	Supplying and installation of Table as per the following description: Table top shall be made from 18 mm thick commercial plywood with equal sized 10mm thick back painted toughened glass with polished edges hole cut for cable manager. with necessary intermediate support. as per detail drawings Exposed surfaces of the table shall have laminate All internal surface will have 0.80 mm thick balacing laminate.(For MEETING ROOM)					
1.05	CONFERENCE TABLE SIZE: 10'-6" X 4'-0" X 2'-6" HT. (T8)	1.00	NOS			
	Supplying and installation of Table as per the following description: Table top shall be made from 18 mm thick commercial plywood with equal sized 10mm thick back painted toughened glass with polished edges hole cut for cable manager. with necessary intermediate support. as per detail drawings Exposed surfaces of the table shall have laminate All internal surface will have 0.80 mm thick balacing laminate. (For CONFERENCE ROOM)					
1.06	RECEPTION TABLE SIZES: 12'-0" X 2'-6" X 2'-6" + 1'-0" HT. (T9)	1.00	NOS			
	Table top made from 18mm thick ply wood + 6mm thick Corian sheet with bufing polishing finish					
	Apron (Front side) made from 18mm thick ply wood + 1mm thick laminate finish					
	Both sides made from 18mm thick ply wood + 1mm thick laminate finish					
	3" thick Partition above working table top made from 18mm thick+6mm thick ply wood with necessary framing with 6mm thick Corian sheet with bufing polishing finish.					
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. Ready made Foot rest CPU stand trally with castor and metallic cable Manager shall be provided in table top. All internal surface will have 0.80 mm thick balacing laminate					
	Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter- As per drawing and instruction of Architect/Bank Complete					
1.07	Removing, repairing, shifting and refixing, resizing of old tables (approx. 25 nos.) available at our existing premises Ground floor shifting to First floor including lead - lift. (Existing table size: 4'-6" x 2'-6" x 2'-6" ht. but Resizing is 4'-0" x 2'-6" x 2'-6" ht 21 nos and 3'-6" x 2'-0" x 2'-6" 4 nos) with 1mm laminate top, and all sides changed with required necessary hardware. including polishing where ever required. including changing of group lock, cable manager etc. complete.	25.00	NOS			

PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR RACPC-WEST IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD						
Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.						
SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
1.08	Removing, repairing, shifting and refixing of old tables (AGM table) from ground floor to first floor in the same premises including lead - lift. (Existing table size: 7'-0" x 2'-6" x 2'-6" ht.) new table top size of 7'-0" x 3'-0" x 2'-6" ht.. with 1mm laminate top and sides with required necessary hardware. including providing and laying 10 mm thk. toughened back painted glass of approved shade with bevelled edge and polishing where ever required. including changing of group lock, cable manager etc complete.	1.00	NOS			
1.09	Removing, repairing, shifting and refixing of old tables from ground floor to first floor in the same premises including lead - lift. (Existing table size: 4'-6" x 2'-6" x 2'-6" ht.) new table top size of 5'-0" x 2'-6" x 2'-6" ht.. with 1mm thk. laminate top, and all sides changed with required necessary hardware. Including polishing where ever required. Including changing of group lock, cable manager.etc. complete	24.00	NOS			
2	STORAGE					
2.01	SIDE CREDENZA	78.90	SQ.MT			
	Removing, repairing and refixing of existing side unit and back side storage from ground floor to first floor same premises including lead - lift. item includes changing of laminate of approve shade with removing of existing laminate by heating. including polishing where ever required. including changing of group lock. and required minor repairs. Front elevation area will be consider for payment purpose.					
2.03	P/F ELECTRIC CUB BOARD	13.00	SQMT			
	Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.					
3	PARTITION WORK AND DOORS					
3.01	LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS	60.30	SQMT			
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass with machine cut eadge as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.					
3.02	BOTH SIDE LAMINATE PARTLY GLAZED / SOLID FULL HEIGHT PARTITION WITH DOOR	152.00	SQMT			

PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR RACPC-WEST IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD

Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.

SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides,1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 8 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 8 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, door closer, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.[REFER DRG]					
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.					
3.03	REMOVING, RECONDITIONING EXISTING PARTITION AND PROVIDING AND FIXING NEW WOODEN PARTITION INCLUDING DOOR.	112.40	SQMT			
	Removing,reconditionin existing partition and providing and fixing new partly glazed bothside laminated wooden partition including door as per given layout. Item includes changing of1mm thick laminate on bothsides of existing 1.22 mt height or any height partition and wooven door also.Item also includes erecting new partly glazed wooden partition above 1.22 mt height/any height and up to existing false ceiling with 1.5mm thick aluminium section of required size for matching thickness of existing partition in a maximum grid of 600mm x 600mm, 6/8 mm thick plywood and 1.00 mm thick laminate on both sides and 8mm thick glass.Item also includes providing and fixing new and reconditioning of existing partly glazed wooden door with matching laminate on both sides, providing new cylindrical lock, Door Closer, Door Stopper and required necessary all accessories,matching beading patties,polishing,cleaning etc. complete. (Existing partition and new partition including door, the combined furnished visible actual area as p					
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.					

PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR RACPC-WEST IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD						
Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.						
SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
4	PANELLING WORK					
4.01	PANELING WITH LAMINATE	101.10	SQMT			
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .					
4.02	PANELING FOR DISPLAY WALL WITH 3M VINYL FILM WITH PRINTED DESIGN	2.90	SQMT			
	Providing and laying panelling on wall having 12 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose.					
	Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width.					
4.03	PANELING FOR DIGITAL WALL WITH BULE / WHITE HIGH GLOSS PU COATING FINISHING	23.10	SQMT			
	Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only finished visible surface area shall be measured for payment.					
4.04	PANELING WITH MDF FLUTED + COLOR	7.80	SQMT			
	Wall paneling made from framework of 25 x 25 x 1.20 mm thick hollow aluminum sections spaced 600mm c/c, over which MDF fluted wooden panel of 10mm +/- 2mm shall be fixed as per the design in the drawing or as directed by Architect.					
	(i) Framework:- Made out of 25 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.					
	(ii) Panel Finishing:- Providing & fixing 10mm +/- 2mm thick approved MDF fluted Wooden Panelling fixed on the aluminum sections with tongue and groove joints in line and level including 3 coats of Plastic emulsion paint.					
	(iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.					
	(v) Applying 3 or more coats of plastic emulsion paint etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete.					

PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR RACPC-WEST IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD						
Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.						
SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
	<p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) MDF:- Nuwood / Action tesla / Dura turff / Century/Green or equivalent approved by the Bank.</p> <p>(c) Color:- Asian / Nerolac or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear paneling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.</p>					
5	SHELFIE POINT (2100mm x 1800mm x 1800mm ht)	1.00	NOS			
	<p>Providing and fixing both sides laminate solid partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides,1.0 mm laminate of approved make shall be fixed on MDF / plywood. front partition shall be design home shape cutting and sides finish teakwood beading patti with malemine polish as per detail drawings.</p>					

PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR RACPC-WEST IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD						
Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.						
SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
6	3M GLASS FILM OVER GLAZED PARTITIONS	198.20	SQMT			
	Providing and fixing in position high impact resistant 3M Glass Films of approved design & pattern, which once installed on glass, give additional strength to glass, reduce glare & prevent glass from splintering on impact. thickness not less than 4 Mil (100 mic.) or 7 Mil (175 mic.)					
7	WALL PAPER	15.90	SQMT			
	Providing and applying Wall paper approved by Architect / Bank's Engineer, wall paper basic price of Rs 100=00 Per Sq.Ft					
8	GRID FALSE CEILING	439.10	SQMT			
	Providing and Fixing of Armstrong Mineral Fibre Acoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid.					
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. Item includes Removing of Existing false ceiling with frame, sheet etc.and disposal of unservicable material behind the Municipal limit.					
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications.					
9	GYPSUM BOARD FALSE CEILING	311.40	SQMT			
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA/Serra (Gypsteel Ultra/Serra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. Item includes Removing of Existing false ceiling with frame, sheet etc.and disposal of unservicable material behind the Municipal limit.					
	After completion of work to certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their					
	Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished visible surface area shall be measured for payment.					
TOTAL COST OF FURNITURE WORK						

GST will be extra as applicable

Note: (a) In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this