

| PRICE BID OF CIVIL WORK OF EXISTING BRANCH PREMISES OF CHURCHA BRANCH (Baikunthpur) RBO- AMBIKAPUR, C.G. | | | | | |
|---|--|------------|-------------|-------------|---------------|
| S.No. | Description of Item | Qty | Unit | Rate | Amount |
| | Civil Works : | | | | |
| | Mode of Measurements: Area of exposed and finished surfaces will be measured. | | | | |
| 1 | Dismantling of cash, clerical counters, tables, side units etc. and shifted the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within the Branch premises etc. complete. as per the instruction given by the Bank Engineer. | 1 | Job | | |
| 2 | Dismantling of old Alluminium/ Glass/ wooden partitions/ flooring and shifting to a suitable place as per the instruction of the branch including shifting charges within the branch premises etc. The cost shall include removal/ dismantling etc. of existing wall tiles, dressing/ chiselling/ finishing/ replastering etc. for levelling or surface preparation purposes to achieve smooth, leveled surface suitable for tiling. Disposal of dismantled/ chiseled tiles and all related debris shall be borne by the contractor outside compound as per Municipal norms. The cost shall also include safely chiselling out remains of tiles from the wall surface without damaging existing pipelines, conduits, cables, wires, switch boards or any such item concealed inside the wall below the tiles., safe handling and removal of debris to a safe distance as directed by the engineer-in-charge. The work shall be done with utmost care to avoid any structural or physical damage to the existing electrical wiring, plumbing works, doors, ventilators, exhaust fans etc. complete. as per the instruction given by the Bank Engineer. | 1 | Job | | |
| 3 | Collecting & Gathering all the wires, cables, conduits, and all loose wires with the help of metal clips/ plastic lockable binders etc. The all collection of bundles of wires will be fixed along with top of walls/ beams etc. This will be hidden in false ceiling. The work will be completed as per the instructions of Architect/Bank Engineer. | 1 | Job | | |
| 4 | Providing & laying 18 mm thick Plastering of walls and ceiling with cement mortar 1:4, curing, ladder use, cleaning, etc. | 70.00 | Sqmt | | |
| 5 | GRANITE DOOR FRAME Providing and fixing 18 to 20mm thk. Jet Black or any other approved shade machine cut, mirror polished, premoulded Granite stone to the Doors / Staircase Steps (Risers & Treads) / kitchen platform / vanity counters / window sills / facias and similar locations in required shape and size laid over 25mm thick cement mortar 1:5 base and fixed with neat cement slurry, filling joints with matching pigment epoxy base joint filler compound, including curing, moulding and mirror polishing to edges complete as directed at site. Note: The Granite to Staircase steps, window sills, vanity counters etc. to be provided in one piece & minimum 7'0" in length for Kitchen platform and similar locations. The rate to include cutting grooves to Staircase Treads, necessary holes for locks , tower bolt etc. Clear visible area shall be paid and no overlapping shall be payable. | 20.00 | R.Mt. | | |
| 6 | Providing & constructing Zade Black Granite platform for pantry and wash basin counters complete as per specifications with 18-24 mm kota stone stand and kota stone or MS angle/T section supports as required and as instructed, including base stone in kota stone and fixing of 15-18 mm thick mirror polished, machine cut jet black granite with simple full round edge moulding and facia for pantry counter and double thick edges with full round moulded edges and of required size. The granite full round moulding shall be fixed with araldite adhesive to the counter top. The cost shall be inclusive of cutting for sink, basin, taps etc. as and when required. | 2.00 | Sqm | | |

| | | | | | |
|----|--|--------|-------|--|--|
| 7 | Providing & laying matt finish Non-skid ceramic floor tiles in toilet areas as per specifications of size 300X300 of make Simpolo, Kajaria, Nitco, Bell, Johnson, Somany etc, or equivalent in first quality and of design, colour and make as per approval laid over cement plaster. The joints shall be filled and finished neat with cement grout as per specifications cleaning shall be done by applying acid wash curing etc. complete at all levels. | 10.00 | Sqm | | |
| 8 | Providing & laying vitrified wall tiles for dado in pantry area and on walls in toilets as per specifications of size 1200mm x 600mm of make Simpolo, Kajaria, Nitco, Bell, Johnson, Somany etc, or equivalent in first quality of design, colour and make as per approval laid and border in special/dark colours as per approval laid over fresh or existing cement plaster including surface preparation if required to the architects satisfaction, joints to be filled and finished neat with cement grout as per specifications including cutting at traps, mitring of joints if required cleaning applying acid wash curing etc. | 40.00 | Sqm | | |
| 9 | Providing & fixing 1st class premium quality, double charged vitrified tiles in floor, skirting of approved size (800mm x 800mm or 600mm x 600mm as directed) of make Simpolo, Kajaria, Nitco, Bell, Johnson, Somany etc, or equivalent in first quality conforming to IS:15622 of approved make in all colours shades of any size in floors and skirting over 20 mm thick bed of cement mortar 1:4 and jointing with grey cement slurry @3.3 kg per Sqmt, or fixing the same on existing floor fixed on a screed of approved adhesive viz Carebond or Nitobond or Balendura including pointing in white cement mixed with pigment of matching shade complete. | 195.00 | Sqm | | |
| 10 | Providing and laying in position mechanically mixed Reinforced Cement Concrete (RCC) of 1:1 1/2:3 using 20 mm and downgrade metal at all levels upto plinth level for various RCC structural elements in any shape and design as per structural drawings and as directed including transporting (manually / mechanically), laying, compacting and finishing the surface in line, level and plumb as required and cost of curing etc. complete. The Rate to include necessary formwork, centring, shuttering, complete in all respects and execution of work at all heights and location with required lead and lifts complete as directed by Engineer in charge. | 0.50 | Cu.mt | | |
| 11 | EUROPEAN WC : Providing and fixing white vitrous EWC of Jaguar make (OPAL OPS - WHT- 15751P180 UF) having P / S trap connection including 10 litre capacity PVC ISI approved make low height cistern. The rate should include all fittings jointing material, labour and making connection with the existing line complete. | 2 | Nos | | |
| 12 | Providing & fixing in position Flush Valve Dual Flush Concealed Body Type Jaquar make, Plumber or equivalent upon approval with all WCs complete including all required connections and settings for proper functioning to the Engineer's satisfaction. | 2 | Nos | | |
| 13 | Providing and fixing in position first quality white Jaguar (Code : URS-WHT- 13255 make Gents Urinal Without Sensor) or equivalent as per approval and making all connections of urinal with other accessories such as flush pipe ,outlet, etc. filling including making chases and holes in floors and walls and repairing the same with cement mortar (1:3) plastering etc. to original condition and painting of fittings etc. complete | 2 | nos | | |
| 14 | WASH BASIN : Providing and fixing white vitrous wash basin with pedastal of Jaguar make (Code : CNS - WHT - 801 + CNS- WHT +305) make with CI brackets, 15 mm heavy pilar cock, 32mm cp brass coupling, waste pipe etc. The rate should include all fittings jointing material, labour and making connection with the existing line complete. | 3 | nos | | |

| | | | | | |
|----|---|----|-----|--|--|
| 15 | Providing and fixing in position Angular Stop Cock with Wall Flange Jaquar make (Cat. No. FLR 5053N), Plumber or equivalent upon approval complete including all required connections and settings for proper functioning to the Engineer's satisfaction. | 7 | Nos | | |
| 16 | Providing & Fixing CP finish Two Way Bib cock with wall flange Jaquar make (Cat. No. FLR 5041N), Plumber or equivalent along with Hand Shower (Health Faucet) (ABS Chrome Plated) with 8mm dia and 1 M long Flexible tube and wall hook (Cat. No. ALD 573) or equivalent upon approval make & design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc. | 2 | Set | | |
| 17 | Providing & Fixing CP finish Pillar cock long body bib cock of Jaquar make (Cat. No. FLR 5011N/ FLR 5047N), Plumber or equivalent make upon approval and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc. | 3 | Nos | | |
| 18 | Providing and fixing in position 15mm Class 'B' CPVC pipe of approved ISI branded complete with fittings Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried underground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required. Makes: Prince, Supreme, Astral | 20 | Rmt | | |
| 19 | Providing and fixing in position 20mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried under ground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required Makes: Prince, Supreme, Astral | 20 | Rmt | | |
| 20 | Providing and fixing in position 25mm Class 'B' CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried under ground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required Makes: Prince, Supreme, Astral | 10 | Rmt | | |
| 21 | Providing and fixing brass/ gun metal high pressure full way or gate valves with MS handle head complete with fitting, teflon tape, testing etc. | 1 | Nos | | |
| 22 | Providing and fixing 75 mm PVC pipes for soil waste/rain water/drainage disposal of superior Indian make such as Kisan, Premium, Supreme, Prince or Kasta i/c jointing with rubber ring, adhesive lubricant solvent cement with PVC clips, bends, joints, bends with doors, etc. fittings as per site requirement with testing etc. complete. | 5 | Rmt | | |
| 23 | Providing and fixing 100 mm PVC pipes for soil waste/rain water/drainage disposal of superior Indian make such as Kisan, Premium, Supreme, Prince or Kasta i/c jointing with rubber ring, adhesive lubricant solvent cement with PVC clips bends, joints, bends with doors, etc. fittings as per site requirement with testing etc. complete. | 5 | Rmt | | |
| 24 | Providing and fixing stainless steel jali (grating) with or with-out hole for waste pipe for floor/ Nahani trap inner lining in SS. | 6 | Nos | | |

| | | | | | |
|---|---|---|------|--|--|
| 25 | Providing and fixing PVC waste pipe for wash basin and kitchen sink including PVC waste fittings complete. | 4 | Nos | | |
| 26 | Providing and fixing stainless steel sink 1 number Nirali Make or equivalent as per approval of size approx. 18inch X 24 inch or as available per approval in platform complete including all required cutting, filling, preparation for installation, connecting waste coupling, waste pipe, adhesives/ sealers/ fillers etc. | 1 | Nos. | | |
| TOTAL (Excluding GST) | | | | | |
| Note:- The rates quoted includes all other taxes,duties, loading, unloading, transportation, other expenses etc to site. | | | | | |
| GST will be paid additionally as applicable | | | | | |
| | | Seal & Signature of Contractor | | | |
| | | | | | |