

**INDICATIVE PRICE BID FOR INTERIOR WORKS FOR UNIFORM LAYOUT IMPLEMENTATION IN  
SBI RASMEC KAZHAKOOTAM (BRANCH CODE - 61042)(PROPOSED PREMISES FOR SHIFTING),  
UNDER AO THIRUVANANTHAPURAM.**

Sl No.	Description of work	Quantity	Unit	Rate	Amount
1	<b>LOW HEIGHT PARTITION :-</b>	123.00	Sq.M		
	Providing and fixing of Low height partitions for Single window system of 1350 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Existing Clear float glass of 12 mm thick to be removed and refixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle shall be provided.				
2	<b>Custom Made Full Height Solid Partition:-</b> Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beadings. Measurement for the partition area shall be considered from floor level to false ceiling level only.	84.00	Sq.M		
3	<b>Full height partly solid and partly Glazed partition :-</b> Providing and fixing in position partly panelled and partly glazed partition as per specification in item no.(8) above but with 8 mm thick float glass with etching between 900 mm and 2100 mm level between the solid partition as per size required at site fixed with necessary SS D brackets. The edges of partition is to be finished with 1 mm thick laminate. Measurement for the partition area shall be consider from the floor level to false ceiling level only.	69.00	Sq.M		

4	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	19.00	Sq.M		
5	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.( DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	17.00	Sq.M		
6	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using <b>PT</b> Standard fittings like PT 90/PT 92 of <b>Dorma or equivalent make</b> at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	60	Sq.M		
7	Gypsum Board False Ceiling - Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprisingFrame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete. Rate to include closing of all wall openings with masonry or plywood, above the false ceiling level, as per Engineer's instructions.	630	Sq.M		

8	<b>AGM's TABLE:-</b>				
	Providing and fixing Branch Manager's table of size 2100 x 800 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. 12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.	1	No.		
9	<b>Side Tables For AGM:-</b> Providing and fixing side unit for Manager / BM table to detail as per drg. of size 1500mm x 600 mm made of 18 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc.,complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	No.		
10	Providing and fixing <b>Officer's table</b> of size 1800 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.8 above. 12 mm thick glass with polished edges to be provided on table top.	4	No.		
11	Providing and fixing <b>Officer's table</b> of size 1500 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.8 above. 12 mm thick glass with polished edges to be provided on table top.	28	No.		
12	Providing and fixing table of size 1200 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.8 above. 12 mm thick glass with polished edges to be provided on table top.	20	Nos.		
13	Providing and fixing table of size 1200 x 600 X 750 mm high to detail as shown in drg. as per specification in item no.8 above. 12 mm thick glass with polished edges to be provided on table top.	3	Nos.		
14	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 100 x 45 cm as per specification in item no.9 above.	40	Nos.		

15	<b>Low Level Storage</b> : - Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exposed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	78	Sq.M		
16	<b>Wall and Column Panelling</b> :- Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood finished with 1 mm thick laminate.	75	Sq.M		
17	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface.	304	Sqm		
18	Plain painting with one coat putty - Two coats of plastic emulsion paint to be applied on wall / ceiling using roller brush, after levelling the surface and applying one coat of primer and one coat of putty.	689	Sqm		
19	Providing and fixing ROLLER blinds of approved quality for the windows.	79	Sqm		
20	TABLE for VIDEO CONFERENCE HALL of size - 1.2m x 3m .	1	Nos.		
	Supply and fixing Conference hall table of size of the table is 3.0x1.20x0.75cm with rounded edges at both ends. The width and height of the table is 150 cm and 75 cm respectively. The length of the table is 710 cm. The table top and sides are made of 18mm thick marinegrade plywood(IS 303 grade) finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. The inner vertical portion of the table is with 18mm thick plywood, verticals to be given at 75cm c/c amd finished with 1mm thick laminate of approved color and brand with exposed top edges lipped with 2 mm pvc edge band tape.				
	12mm thick glass with polished bevelled edges to be provided for the table top with necessary wire manager. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Main vertical supports at corners and covering all around made of 18 mm thick plywood at front, sides and rear with necessary lipping etc. complete. Cable managers to be provided at intermediates as shown in the drawing. Also, necessary provisions, as required by for electrical works, such as fixing sockets/switches etc should be facilitated.				

21	CENTRE TABLE for DISCUSSION ROOM of size - 1.2m diameter -	2	Nos.		
	Providing and fixing Centre Table of size 1.2m diameter and 0.75m high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. 12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Vertical supports at corners and covering all around made of 18 mm thick plywood at front, sides and rear with necessary lipping etc. complete.				
22	Providing and fixing good quality <b>Aluminium composite panelling</b> for front portion of Bank, at the exterior columns, with white coloured panels.	34	Sqm		
	<b>TOTAL</b>				
	<b>GST @ 18%</b>				
	<b>GRAND TOTAL</b>				