

## PRICE BID FOR AIR-CONDITIONING WORKS FOR SBI MINI RACPC, MEHSANA

Sr.No.	Description	Quantity	Unit	RATE	AMOUNT
[A]	<b>AIR CONDITIONING WORK</b>				
[I]	<b>MACHINE PART</b>				
[a]	<b>AC EQUIPMENT WITH - INVERTER COMPRESSOR</b>				
1	Supply & providing of <b>4 way Inverter Cassette Type AC</b> ceiling mounted cassette unit with indoor and out door having <b>eco friendly</b> refrigerant. Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have <b>copper condensor Unit</b> , Make: Daikin/ Mitsubishi Heavy Industries/Toshiba. <b>[Mini 5 Star rating as per BEE Guide Line 2022]</b>				
1.a	Inverter 4-way Cassette of 3.00 TR.( 3 Phase Compressor Only.)	8	NO		
2	Supplying & providing of <b>Hi-wall Inverter Split Type AC</b> with high wall mounted indoor and out door unit. having <b>eco friendly</b> refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall have <b>copper condensor Unit</b> , Make: Carrier/ Hitachi/ Daikin/ Mitsubishi Heavy Industries/ Toshiba/ Trane/Blue star. <b>[Mini 5 Star rating as per BEE Guide Line 2022]</b>				
2a	Inverter Hi-wall Split AC of 1.0 TR	2	No.		
2b	Inverter Hi-wall Split AC of 1.50 TR	1	NO		
	<b>TOTAL FOR PART- I</b>				
[II]	<b>LOW SIDE WORK</b>				
1	Installation of IDU & ODU of 4.00 TR/3.00/2.00 TR ceiling mounted cassatte unit with first oil & gas charge & commissioning etc. Rate including ceiling mounted suspension Kit etc complete	8	NO		
2	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including 5.0 Rmt copper tubing and electrical wiring connection etc. complete.	3	NO		
3	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit of 4.00/3.00/2.00 TR ceiling mounted cassette unit with 2.5 Sqmm 4 Core copper flexible cable of Finolex / R R Kable/Havells/CEI make. The copper piping shall be insulated with 13mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armafex/ Superlon Make	80	RMT		
4	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit beyong 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 2.5 Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armafex/ Superlon Make (	30	RMT		
5	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealled in inside wall)	100	RMT		
6	Providing and Fixing M.S Powder coated stand for keeping outdoor unit of cassate A/C and Split A/C. ( Redy made)	11	NO		



Sr.No.	Description	Quantity	Unit	RATE	AMOUNT
7	MISC. CIVIL WORK LIKE MAKING ZARI IN WALL, WALL OPENING TO PASS DUCTS & PIPES, CORE CUTTING, PLASTERING & RE-FINISHING OF THE SAME TO THE ORIGINAL FINISH AS PER THE SITE REQUIREMENTS.	1	JOB		
	<b>TOTAL FOR PART- II</b>				
	<b>TOTAL ( I + II )</b>				
				<b>NET AMOUNT</b>	
	+ GST AS APPLICABLE				

