

PRICE BID FOR THE INTERIOR WORKS IN SBI AT SANDHOL

Make of materials to be used as under:

1)	Glass 5mm, 8mm, 12mm	MODIGUARD / SAINT GOBAIN /
2)	Automated door accessories and fittings	Dorma/Boonadam/Kaba
3)	19mm th. ply	Archid, Century, Greenply (Sainik, Ecotech)
4)	6mm, 4mm th. Ply	Archid, Century, Greenply (Sainik, Ecotech)
5)	Laminate	1mm th. of CENTURY / SUNMICA / AICA /GREENLAM
6)	Glue for fixing ply/laminate	Fevicol (Pidilite)
7)	35 mm flush DOOR	ISI marked
8)	Toughened glass door handles	Stainless steel handle of Godrej
9)	Multipurpose locks for drawers	GODREJ / DORSET / OZONE
10)	Locks for doors	GODREJ NIGHT LATCH / GODREJ
11)	Hydraulic Door closer /Floor Spring	GODREJ / EVERRITE / HYPER ISI
12)	CPU Trolley / Telescopic Channels	EBCO /ZIPCO or equivalent
13)	Cupboard / Drawer handles	Stainless steel matt finish of
14)	Gypsum board Ceiling System	INDIA GYPSUM
15)	Gypsum Board false Ceiling Sections	RONDO/BORAL/INDIA GYPSUM
16)	T-Grid Ceiling System	ARMSTRONG
17)	Aluminium Sections	HINDALCO, Jindal
18)	Door Mat	LG / DUROTUFF

S No	DESCRIPTION	QTY	UNIT	RATE	AMT
1	<p>RONDO/BORAL/INDIA GYPSUM BOARD FALSE CEILING:</p> <p>Providing and fixing suspended false ceiling including steps and provision of cope lighting as per design with 12.5mm tapered edge Gypboard / 12mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consisting of a perimeter channel fixed round the perimeter. The intermediate channel at 1200mm c/c in the one direction and the ceiling section at 450mm c/c in the other direction to be connected by a connecting clip. The grid to be suspended with an adjustable strap hanger.</p> <p>The grid to be suspended with an adjustable strap hanger at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts to be used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers to be screwed to the</p>	70	Sqmt.		

2	<p>Armstrong PPGI METAL SHEET Grid False Ceiling with channels having black groove at bottom:-</p> <p>Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries. The suspension system shall be the Armstrong Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions.</p> <p>Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched at every 1200mm c/c maximum and 1200mm cross tee at every 600mm c/c maximum and 600mm cross tee at every 1200mm c/c maximum and wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of premier mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as per manufacturer's specifications.</p>	52	Sqmt.		
3	<p>TEAK WOOD VINEAR CEILING & WALL PANELLING (Archid, Century, Greenply (Sainik, Ecotech):</p> <p>Providing and fixing 4mm thk. teak veener in ceiling over 8mm thk. commercial ply screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes esprit polished of approved shade. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.</p>	25	Sqmtr		
4	<p>FULL HEIGHT PARTITION/LOW HEIGHT PARTITION:</p> <p>Providing and fixing wooden full height partition with following specifications:</p> <p style="text-align: right;">(a)</p> <p>Supporting system comprising of Dry wall Frame Work Alum. box (HINDALCO / JINDAL make) section of 50mm x 50mm (18 Gauge) square section @ max. 600mm c/c both horizontally and vertically. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at</p>	25	Sqmt.		
	<p>(b) The partition shall have 9mm Plywood (Archid, Century, Greenply (Sainik, Ecotech)) fixed on both sides with screws for the entire height of the partition and finished with approved 1.0mm Th. Laminate of desired shade, design on both sides. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finished with metallic laminate of desired shade, design.</p>				

	<p>(c) The full height partition shall be WITH OR WITHOUT 8mm clear float glass (MODIGUARD / SAINT GOBAIN / ASAHI FLOAT / AIS) with etching fixed as per drawing with 75mm x 12mm Teak wood jamb/chaowkhat around glass opening and 12mm x 25mm teak wood beading for fixing of glass on both sides. As per the direction of Engineer-in-charge and design.</p> <p>(d) The work to include providing and fixing of partly glazed wooden door shutters using 35mm readymade ISI flush door shutter with 1.0mm thick laminate (1mm th. of CENTURY / SUNMICA / AICA /GREENLAM / KITLAM) of desired shade/textures as per drawing with teak wood frame of 75mm x 40mm. The door shall have 6mm thick teak wood lipping all around the edges. The door shall have vision panels with 8mm thick clear float glass with etching fixed with double 14mmx25mm thick teak wood moulding as per design. The exposed surface of wood shall be deco painted in desired shade. The door shall be complete in all respect with hardware handles 18" long, godrej 6-lever lock/night latch lock, door stoppers, 8" tower bolts, hinges, door closer for each door etc all in brass.</p> <p>(e) The low height partition shall have 12 mm thick glass with etching as per design fixed with stainless steel wall cladding profile (WCP) of</p>				
5	SWO COUNTERS:				
	<p>Providing and fixing at site SWO counters each upto 5'-0"/4'-6" long, 2'-6" high and 3'-0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply (Archid, Century, Greenply (Sainik, Ecotech)) with 1.0 mm thick laminate (1mm th. of CENTURY / SUNMICA / AICA /GREENLAM / KITLAM) on outer visible surfaces excluding table curvilinear top (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood/MDF beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commer ply and finished with 6mm thk. flexi ply as base for polyacrylic sheet or approved laminate as/design with provision for LED Light in bottom. Teak wood/MDF lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, , of approved make fixed on channels, as per manufacturer's instructions / specifications.</p>	2	Nos.		

	Three drawers with autolock running on both sides mounting Telescopic (channels) of approved make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non Visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finished with 1mm thk. white/off white laminate. All exposed Teak wood edges / teak wood lipping /MDF beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest , Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.				
6	COREAN: POLYACRYLIC 12mm THICK STONE (KORAE) Providing and fixing (12mm thick (MERINO MAKE) white polyacrylic stone (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all respect including adhesives, buffing and wastage.	5	Sqmt		
7	WALL PANELING: Providing and fixing panelling on column/wall. Framing shall consist of Heavy duty Aluminium Box Sections 50mmx25 mm (HINDALCO / JINDAL make) with maximum spacing of @ 600mm c/c Both ways horizontally and vertically on the column/wall. This framing would be covered by 9mm thk. com. Ply (Archid, Century, Greenply (Sainik, Ecotech) finished in approved 1.0mm Th. Laminate (1mm th. of CENTURY / SUNMICA / AICA /GREENLAM / KITLAM) of desired shade, design. Wooden molding, lipping etc. shall be provided wherever required as per drawing and deco painted / melamine polish in desired shade. The paneling shall have skirting and intermediate bands finished with metallic laminate of desired shade, design. The work shall also include the cost of making cut-outs for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc.	95	Sqmt.		
8	WALL PAPER: Providing and laying wall paper as per sample approved.	0	Sqmtrs		
9	TEXTURE PAINT: Providing and laying texture paint of "Heritage" Co. " <u>Rustic type</u> " as per colour scheme.	20	Sqmtrs		

10	TOUGHENED GLASS DOORS & PARTITION: Providing & fixing 12 MM thick toughened glass (MODIGUARD / SAINT GOBAIN / ASAHI FLOAT / AIS) for door and fixed glazing, with complete patch fittings such as floor spring, handles, lock and L-brackets etc. The job shall also include etching design.	25	Sqmt.		
11	OFFICE TABLES with 1½" thick post-form factory made Tops: (a) Providing and fixing at site Officer's table made of 19mm th. commercial ply (Archid, Century, Greenply (Sainik, Ecotech) finished with 1.0 mm thick laminate (1mm th. of CENTURY / SUNMICA / AICA / GREENLAM / KITLAM) of desired shade, design on outer visible surfaces; single color on horizontal surface & two color on vertical surfaces. . The front of the table top shall be projected and curved as per drawing. Provision for 3" dia. Round/3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the table. Esteem Biege wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The counter shall have a wooden keyboard rest of size 600mm x 270mm made with 19mm ply fixed with sliding telescopic channels of approved make. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space. (b) There shall be provision of one storage cabinet 1'3" wide. The frame shall be made with 19mm thick commercial ply. The cabinet shall have one lockable drawer running on side mounting drawer slides (channels) of approved make & one cupboard with shutter beneath the drawer, made of 19mm thick commercial ply with 1mm thick laminate of desired shade, design on front face, handle / knob and magnetic catcher shall be provided on one side				
a	Manager tables: 6'-0"x2'-9"	1	No		
b	Officer tables: 5'-0"/4'-6"x2'-6"	4	No		
c	Officer tables: 5'-0"x2'-6"	0	No		

12	<p>SIDE CREDENZAS: with 1½" thick post-form factory made Tops:</p> <p>Side credenza made of 19mm thick commercial ply frame and 6mm thick plywood on back side (Archid, Century, Greenply (Sainik, Ecotech) & 1mm thick laminate (1mm th. of CENTURY / SUNMICA / AICA / GREENLAM / KITLAM) on top horizontal surface & one vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer compartment 14" wide outer to outer, containing three drawers vertically running on side mounting drawer slides(channels) of approved make. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick ply. The remaining part of the credenza will have cupboard with shutters of 19mm thick ply and one shelf. All the internal surfaces shall be finished with 0.8 mm thick mica of desired shade, design, and the exposed wood shall be deco painted/malamine polished in desired</p>				
a	Side Credenza: 3'-6"x1'-6"	4	No		
b	Side Credenza: 3'-3"x1'-6"	1	No		
13	<p>WRITING STAND:</p> <p>Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.</p>	1	No.		
14	<p>NOTICE BOARD:</p> <p>Providing & fixing notice board of size 2'-6"x 4'-0" finished with ivory colour 1mm th. laminate on 19mm th ply, 1"x0.25" th. teak wood beading on all sides.</p>	2	Nos		
15	<p>NOTICE BOARD WITH OPENABLE GLASS:</p> <p>Providing & fixing soft boards of size 3'-6"x 2'-0" (covered with openable glass shutters) on 10mm th. comm. ply 12mm th. soft board finished with cotton fabric , 1"x2"teak wood beading</p>	2	nos		
17	<p>SERVER ROOM COUNTER:</p> <p>Providing & fixing server room: Counter 6'-0" long, 2'-3" wide & 2'-6" high with key board, storage cabinet below, drawers etc. hardware such as hinges, handles and catchers, finished with 1.00 mm thick laminate, painting etc. complete in all respects as per dras</p>	0	No		

18	MDF JAALI: Making and fixing in position (as per approved sample) Laser Cut Jaali & white acrylic sheet on partition cols etc. to be made out of MDF board of 8mm. thickness and make. All exposed surfaces to be finish with clear Duco paint / Melamine polish as per approved shade, fixed inside boxing frame of 6"x6" made of 19mm thick commercial ply with laminate finish . All complete as/ design to the entire satisfaction of Architect/ Engineer in charge (Elevation including frame shall be measured).	2	Sqmtrs		
19	STORAGE CABINETS: with 1½" thick post-form factory made Tops: Providing and fixing storage cabinets low ht and full ht x 16" (Deep) along the walls/partitions, as per interior drawings, using 19mm ply for cabinet, shutters, vertical and horizontal partitions, 6mm ply (Archid, Century, Greenply (Sainik, Ecotech) for the back and 1mm laminate (1mm th. of CENTURY / SUNMICA / AICA / GREENLAM / KITLAM) of approved shade on vertical and horizontal visible surfaces. The shutters shall be overlapped on the carcass and shall be provided hinges. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 19mm x 3mm, duly PU polished/deco painted in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade, design. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.	15	Sqmt. (Face Area)		
20 i	ACP PANELING ON WALL AND SHUTTER BOXING & IN ATM WALLS: Providing and fixing Aluminium Composite Panel (Indo Bond/Alustone) wall cladding with the 3mm thick PVDF coated aluminium composite panel (ACP) (0.25 mm coil thick) with frame of aluminium channels (25 x 50 x 1.6mm), cleat angle (8 x 18 x 2mm) necessary hardware, backup material and weather sealant to make the joints leak proof. The spacing for the channel along the length and spacing of cleat on the perpendicular shall not be more than 600mm.	35	Sqmt.		
ii	P/F partition & door for UPS in ATM with complete hardware with (on frame of Alum section 1.75"x1.75") ACP on both sides.	0	Sqm		
21	FIRE PROOF DOOR FRAME: Providing and fixing fire resistant door frame of section 143 x 57 mm having built in rebate made out of 16 SWG G.I. Sheet (zinc coating not less than 120 gm/sqm) duly filled with vermiculite based concrete mix, suitable for mounting 60 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10x4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including applying a coat of approved brand fire resistant primer etc. complete as per direction of Engineer-in-charge (including Dash fastener).	3	Sqmt.		

22	FIRE PROOF DOOR SHUTTERS: (i) Providing and fixing 50 mm thick glazed fire resistant door shutters conforming to IS:3614 (Part-II), tested and certified as per laboratory approved by Engineer-in-charge, with suitable mounting on door frame, consisting of vertical styles, lock rail, top rail 100 mm wide, bottom rail 200 mm wide, made out of 16 SWG G.I. sheet (zinc coating not less than 120 gm/ m2) duly filled FR insulation material and fixing with necessary stainless steel ball bearing hinges of approved make, including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer-in- charge (paneling to be paid for separately)				
	(ii) FIRE PROOF GLASS PANELS: Providing and fixing glazing in fire resistant door shutters, fixed panels, ventilators and partitions etc., with G.I. beading of appropriate size, made out of 20 SWG G.I. Sheet (zinc coating not less than 120 gm/ m2), fire resistant sealant, including applying a coat of approved fire resistant primer on G.I. beading etc., complete all as per direction of Engineer-in-charge. With clear fire resistant glass panes 6 mm thick of approved brand, having minimum 60 minutes fire resistance				
23	Planters: Providing & Supplying center table Of size 1'-6"x1'-6" for waiting area finished with 1mm th. laminate as per drg.	4	Nos		
24	VERTICAL BLINDS: P/F vertical blinds of vista: (S-Curve Motif-S) / Mac: (Havana ZHV1935) of approved shade / colour.	4	Sqmtrs		
25	SOFAS: Providing & Supplying 3-seater Sofa sets made with hard-wood frame and furnished with cotton cloth of Rs.600/- per M. with 6" th. Cushions of 40 Density as per drgs.	3	Nos		
26	Center table 2'x3': Providing & supplying centre table with 12mm th glass & with teak wood base frame.	1	No		
27	SBI LOGO: Providing , making to shape and size (as per the design provided) and fixing to position SBI bank logo ("LOGO & SBI") made out of ACP sheet of bank blue color (pre approved) fixed to position with aluminium framework with required screws, nutts bolts and hooks etc. of size 2' x 2'	1	No.		
28	P/F Glow Sign Board as per approved design, made of 3M vinyl sheet 26'x4'-0" complete with internal tubes 25 Nos. of Crompton make (copper choke) External frame work of G.I. Sheet, 18 gauge, M.S. angle frame / or M.S. square pipes 1 1/2" x 1 1/2" with outer beading, complete in all respects	10	Sq MTR		
	TOTAL				
	GST @ 18%				
	TOTAL WITH GST				

Signatures of Contractor
Name & address of the Contractor
Mobile No of the Contractor

