

PRICE BID					
Proposed Interior Furnishing Work of State Bank of India Branch Office at Bhalout, Distt. Rohtak					
S.No	ITEM	QNTY	UNIT	RATE	AMOUNT
1	SINGLE WINDOW COUNTER	25.00	Rft.		-
	Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commer ply and finished with 6mm thk. flexi ply as base for acrylic sheet as per design with provision for LED Light in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 finished with laminate on top side with back				
	Three drawers with autolock running on both sides mounting Telescopic (channels) of EBCO make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non Visible / Inside surface i.e. inside leg-space of table, inside drawers shall be finished with laminate. All exposed Teak wood edges / teak wood lipping beading shall be Spray painted Satin Enamel paint or sprit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest, Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size				
	Makes:				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Telescopic Channels: Godrej, EBCO, Ozone</i>				
	<i>Drawer Locks: Godrej, Ozone, EBCO</i>				
	<i>Autolock: Ozone, EBCO</i>				
2	12 mm thk. Solid Surfaces (Acrylic Sheet)	125.00	Sft.		-
	Providing & fixing 12 mm thk. Solid Surfaces (Acrylic Sheet) on counter top & required vertical position made to shaped for Single window Counter at transaction level as per design and approved colour (White). <i>Make: LG Hausys/ Granlum/ Merino Hanex/ Stylam Granex</i>				
3	12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front & Sides	65.00	Sft.		-
	Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free. <i>Make: Asahi Indla, St. Gobain,</i>				
4	Providing and fixing curved shape 12mm thick Toughened float Glass partition between Single Window counter partition front side as follows	25.00	Sft.		-

	12 mm thick Toughened clear float glass with polished edges shall be fixed with clamps/glass connectors on wooden partition as directed. All edges of glass shall be Diamond cut polished edges as directed complete. (Glass for Measurement outer longer width and height shall				
	<i>Make: Asahi Indla, St. Gobain,</i>				
5	stainless steel L - shaped clamps	50.00	Nos.		-
	Superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.				
6	Officer's & Staff Tables				
	Officers Table made of 19 mm thk. Commercial ply (ISI marked- GREEN (Ecotech)/ CENTURY (Sainik) with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); with 40 mm X 6 mm thick teak wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer/ electrical cables at appropriate place will be made in the top surface of the table. Teak wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 fixed on channels(EBCO/ HARRISON/ GODREJ). A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, which will be made of 19mm thick BWP commercial ply finished with laminate 1mm thk. One openable shutter one lockable drawer running on side mounting drawer slides (channels) & made of 19 mm thick BWP commercial ply with 1mm thick laminate on front face, handle / knob shall be provided. The sides of the drawer shall be made of 12 mm thick plywood (ISI marked- GREEN (Ecotech)/ CENTURY (Sainik), bottom of 6 mm thick plywood. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Inside of drawers & Non Visible/inside surfaces i.e. inside /log space of table, inside of				
a	O.T. / S.T. - Size 5'0" X 2'6" X 2'6"	2.00	Nos.		-
b	B.M. - Size 6'0" X 3'0" X 2'6"	1.00	Nos.		-
	<i>Makes:</i>				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Telescopic Channels: Godrej, EBCO, Ozone</i>				
	<i>Drawer Locks: Godrej, Ozone, EBCO</i>				
7	8.0 MM thk glass on top of officers tables	45.00	Sft.		-
	All the edges of the glass shall be grinded polished including Hole for cable manager.				
8	Side Credenza				
	Providing & fixing Side credenza 3'6" long & 15" deep, made of 19 mm thick commercial ply (ISI marked- GREEN (Ecotech)/ CENTURY (Sainik) and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have two drawers on top(with locks), horizontally running on side mounting drawer slides (channels) of EBCO/ GODREJ make, & inner surfaces finished with 1mm thk. white/off white laminate. The remaining part of the credenza will have cupboard with shutters and one shelf, with handle /knob and magnetic catcher. All non visible/inside surfaces shall be finished with 1mm thk. white/off white laminate and teak wood edges/ lipping/ heading shall be Spirit polished with matching				
a	Officer's & Staff side credenza as per Drawing & specification mention in item above. Size - 3'-0"/3'-6"/ 4'-0" X 1'-6"/1'-3" X 2'-6" (W X D X H)	60.00	Sft.		-

	<i>Makes:</i>				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Telescopic Channels: Godrej, EBCO, Ozone</i>				
	<i>Drawer Locks: Godrej, Ozone, EBCO</i>				
9	Back credenza / Storage	95.00	Sft.		-
	Providing & fixing storage cabinets, 18" deep & height as specified, made out of 19mm thick commercial plywood, including the inner shelves & shutters. The visible external surface shall be provided with 1.0mm thick laminate of shade specified, whereas internal surface including both sides of shelves shall be provided with balancing laminate of 0.8mm thickness. All the exposed edges of shutters & shelves shall be provided with beechwood lipping 5mm thick with clear polish finish. The shelves shall be spaced at approx. 15" vertically/as per drawings. The cabinets shall be complete in all respects with handles, catches.				
	<i>Makes:</i>				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Telescopic Channels: Godrej, EBCO, Ozone</i>				
	<i>Locks: Godrej, Ozone, EBCO</i>				
10	P/F ELECTRIC CUB BOARD	50.00	Sft.		-
	Providing and fixing Electric cup board using 18mm thick bison panel for vertical and shelves and aluminium framing of 50x25x1.20mm thick with 6mm thick bison panel on both side for shutter with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. shutter with approved make lock handle, hinges, ball catches P&fixing S.S Perforated jali shall be provided in shutter etc. complete as directed, depth of cup board 1'-3". Shutter height up to 7'-0" and above fixed Type up to false ceiling bottom				
11	Work Stations for System Room / Back Office/Lunch Area	10.00	Rft.		-
	Providing and fixing in position single level work station counter each to be divided at approx. 4 rft. In length, in system / swift room as per site conditions, 2'0" wide and 2'6" high, counter shall be made 19 mm thick commercial ply with 1.0 mm thick laminate on vertical as well as horizontal surfaces with provision of cable management for computer cables and electrical switch board at appropriate place, with teakwood lipping 3/4" x 1/4" on all edges including bottom touching floor. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications. A full depth CPU shelf 14" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply laminated with 1mm thick laminate on top and 3/4" x 1/4" teakwood lipping on two				

	A full length foot rest made of hard wood 3" x 1/2" section shall be provided at 4" above floor level. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1 mm laminate on front side of cupboard shutter with shutter having good quality locks, magnetic catcher, hinges, handle / knob etc. is to be provided. The shutters shall be provided beneath the drawers with each counter on its right / left hand side. All the three sides of the drawer will be made of 12 mm commercial plywood and front side of 19 mm commercial ply with 1 mm thick laminate. The bottom of drawer shall be made of 6 mm thick commercial plywood. The drawer will be provided with handle / knob of good quality to be got approved before fixing with drawer channel of 18" length & the counter should have provisions of foot rest , Space for CPU Non-laminated surface i.e. inside leg space of counter inside of drawer / cupboard / outside of drawers / footrest etc. to be enamel painted white and teak wood edges / lining / heading				
	Makes:				
	Commercial ply: Century, Greenply, Archid ply				
	Laminate: AICA, Greenlam, Merino, Formica				
	Telescopic Channels: Godrej, EBCO, Ozon				
	Locks: Godrej, Ozon, EBCO				
12	Full Height Partitions with etching on glasses. - Solid / partialy glazed/ flush	675.00	Sft.		-
	Providing and fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 2'0" to 2'6" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs / steel lugs. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. of approved laminate as per pattern on both sides upto 3'0" height and above 7'0" height and 5.00 mm thick glass with etching as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1mm thk brusshed steel flnsh lamiante. Work also includes providing and fixing of door as per drawing and specifications. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality. Providing and fixing 4"x2" steam beach member for frame & Providing door shutter using 30mm thick flush shutter with both side laminate and fixing 6 mm thick glass shall be provided in door shutter providing 5"				
	All wood shall be finished with high gloss Spirit polished of approved shade. The rate shall also include for providing groves in veneer. All job to be done to Architect's satisfaction / as per bank direction. Measurements to be taken upto false ceiling level & Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made above false ceiling.				
	Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.				
	Makes:				
	Commercial ply: Century, Greenply, Archid ply				
	Laminate: AICA, Greenlam, Merino, Formica				
	Telescopic Channels: Godrej, EBCO, Ozon				
13	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR S.W COUNTER AND CASH CABIN	335.00	Sft.		-

	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 8 mm thick commercial plywood of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved shed on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12 mm transparent toughened glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface. For Low height Single window and Cash cabin partition. Average height of partition shall be measured and paid.				
	<i>Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.</i>				
	<i>Makes:</i>				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Telescopic Channels: Godrej, EBCO, Ozone</i>				
14	Low Height Partition with etching on glasses (Height + 4'-0" / 6'0")	90.00	Sft.		-
	Providing and fixing Low Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. approved laminate as per pattern on both side's upto 4'0" height. The skirting shall be finished with 1mm thk brushed steel finish laminate. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality. All teak veneer / ply / wood shall be finished with high gloss. Spirit polished of approved shade.				
	<i>Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.</i>				
	<i>Makes:</i>				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Telescopic Channels: Godrej, EBCO, Ozone</i>				
15	Main Entrance Door for B.O & BM - Toughened Glass 12.0 mm thk. With etching	90.00	Sft.		-
	Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf glazed Toughned door of size approximately, 1800 to 700mm X 2100 mm all sides edge grained, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include necessary etching film / logo all inclusive, complete.				
16	Hardware for fixing Toughened Glass for B.O.	4.00	Job		-
	Providing and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings to accomodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete of godrej / dorma.				
17	Fixed Glass / Glazing for B.O - Toughened Glass 12.0 mm thk. with	70.00	Sft.		-

	Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grained, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include necessery etching film / logo all inclusive. complete				
18	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows	42.00	Sft.		-
	Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 31 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Dead Lock, S.S Handles,150 mm long Door stoppers, doorstop of approved make etc. all exposed surface /edges not laminated be provided with lacquer polish complete as per drawing				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
19	Wall Paneling				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un annodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply and following finishigs as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shell be made only for exposed surfaces & actual measurement at site, no payment shall be made for panelling behind furniture such as tables, Credenza, storage				
i.	Panelling finished with 1.0 mm thk. Approved shade & colour laminate.	890.00	Sft.		-
	<i>Makes:</i>				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
20	MDF Board exterior grade with jali work	72.00	Sft.		-
	Providing and fixing 8mm thick MDF Board exterior grade with jali work with high gloss PU coating paint over central column having 6mm thick commercial plywood fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2'-0" c/c bothway as per drawing and direction with all labour and material etc complete (Rate shall be including CNC cutting jali work and 1mm thick blue gloss laminate				
21	SOFT BOARD	25.00	Sft.		-
	Providing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6mm thick commercial plywood on back side and 12mm th soft board on front. Fixing cloth of selected design of Basic rate of Rs. 150 per mt. steam beach member shall have lacquer polish as directed				
22	Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop & Suggestion Box	2.00	Nos.		-

	Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and 3/4" x 1/4" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.				
	<i>Makes:</i>				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
23	Door Closer	3.00	Nos.		-
	Providing and fixing silver colour (or matching with colour scheme / as per site) hydraulic door closer to Doors complete in all respects.				
	<i>Makes: Godrej / Hyper / Dorma / Ozone</i>				
24	Mortice Lock	3.00	Nos.		-
	Providing and fixing silver colour (or matching with colour scheme as per site) Godrej make to Doors complete in all respects.				
	<i>Makes: Godrej / Harrison/Dorma</i>				
25	Night latch	3.00	Nos.		-
	Night latch in cash cabin door - Providing and fixing night latch lock Godrej make in aluminium / wooden doors, complete in all respects.				
26	Painting Work – Texture Paint	215.00	Sft.		-
	Providing and applying special / texture paint Asian royal matalic finish of approved shade & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind panelling, furniture such as tables, Credenza, storage etc.				
27	Panelling With ACP With Aluminium Frames)	550.00	Sft.		-
	Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering, scafoulding, labour.				
28	Providing & fixing Fire resistant door (GMC, Baddi/ Kutty, Paonta), including door frame 100x50x1.2mm GPST steel/ 16SWG GI sheet, duly powder coated, with hold fasts to be embedded in brick wall in cement concrete 1:2:4. Door shutter will be 46mm thick, made of powder coated 0.8mm thick GPST sheet, fire rating of 120 minutes, as per IS 3614 (Part 2). Fire rated wired glass of 300x200 mm size to be provided. Rates include all necessary hardware like pull handle, steel hinges, dead lock, hilty fasteners, complete in all respect.	25	Sft.		-
29	Providing and fixing 3m Vinyl film sandwiched with in 4mm thk acrylic sheets fixed with SS Studs over existing wall/ panelling/ partition complete in all respects to the entire satisfaction of the Engg./ Architect. Film will have colour & digital printing as per drawing/ instructions.	0	Sft.		-

30	P/F Roller blinds (FARRARI/ VISTA/ SUNFLEX/ DOUGLAS HUNTER), complete in all respect.	50	Sft.		-
31	William Tape for protecting floor & glass				
	Providing and fixing William Tape for protecting floor & glass from dust during construction .Item includes removing the tape after completion of work and cleaning the area.	0	Sft.		-
32	Diluting and injecting chemical emulsion for POSTCONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion) , Treatment of soil under existing floors & Walls using chemical emulsion @ one litre per hole, 300 mm apart including drilling 12 mm diameter holes and plugging with cement mortar 1 :2 (1 cement : 2 Coarse sand) to match the existing floor, With Chlorpyrifos/Lindane E.C. 20% with 1% concentration	0	Sft.		-
33	Providing and fixing triangular elements in ceiling as per design made of using 19mm thk ply frame and mounted from the ceiling using anchor rods 12mm thk 3 nos per element. The height of the unit is 6" and the bottom is fixed with 4mm thk heavy acrylic sheet and the ends are covered with black stickers. The inside of the box is designed to provide, supply, fix the LED strip llght(WIPRO GARNET D45027 (2700K) WW/with adopter) and all inner surfaces painted with 2 coats of enamel.	0	Sft.		-
34	Providing and fixing pargolas in the ceiling of size 4" X 9" X 4" long made using 12mm ply around and 19mm thk on top, all surfaces finished with 1mm thk approved shade laminate and the pargola is fixed from the ceiling using anchor rods and covered with 1" ss pipe sleeves each pargolas is fixed using 2 rods.	0	Nos.		-
35	False Ceiling With Steps. - Gypsum Board	630	Sft.		-
	Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The Intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).				
	The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for llght fittings. A/C ducting etc. The work should be complete as per Instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade.				
	The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps/ Vertical bands shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges,tools, lifts and all heights etc.				
36	False Ceiling - (Mineral Fibre)	1460	Sft.		-

<p>Providing & fixing Armstrong false ceiling RH-99 with 600x600x16 mm Fine Fissured Beveled Tegular Edge false ceiling laid in Armstrong silhouette grid system. The frame work comprises of main runner spaced at 1200 mm centres securely fixed to structural soffit by approved hangers at 1200 mm maximum centres. Hangers (G.I. wires 4.0 mm dia) to be fixed by approved roof plug, level adjuster, screws etc. The last runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200mm long cross tee(with double stitching) to be inter locked between main runners at 600mm centres to form 1200x600mm module. Cut cross tees longer than 600mm to be supported independently. 600x600mm module to be formed by fitting 600 mm long flush fitting cross tee centrally between 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to wall @ 450 mm maximum centres. The rates include making opening for electric fixtures, A.C units etc. Rates include dismantling existing false ceiling and removal of malba from site, complete in all respect.</p>				
<p><i>MAKE: Armstrong, St. Gobaln (Indla Gypsum)</i></p>				
<p>TOTAL AMOUNT</p>				-
<p>ADD GST @18% extra</p>				