

# PRICE BID

## FURNISHING ADDITION/ALTERATION WORKS ON 7th FLOOR, SBI, LAL DARWAZA PRAMISES ( OLD LHO BUILDING) AT AHMEDABAD.

Sr. No.	Description	Quantity	Unit	Rate	Amount
<b>Note :</b> Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage & removing of all existing furniture items and relocating,refixing the same as per instruction by bank etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills					
1	<b>FURNISHING</b> <b>CONFERENCE/MEETING ROOM TABLE</b> Supplying and installation of conference/meeting Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.  Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. [ <b>Only Top shall be measured for payment purpose.</b> ] Supporting structure vof conference table as per drawing.	9.78	SQ MT		
2	<b>SIDE CREDENZA (SIDE TABLE)</b>  <b>FINISHING DETAILS IN NUTSHELL:</b> 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Apron & Sides: Frosty White Laminate  <b>Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. ( For BM &amp; Officer's) Rate for length Less then 3'-3"</b>	14.00	SQ.MT		
	Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate  Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.  All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate <b>( FOR DETAILS REFER DRG. NO- )</b>				

- |   |  |       |      |
|---|--|-------|------|
| 3 | <b>DRAWER BOX (pedastal)</b>   | 32.00 | NOS  |
|   | <p>Drawe box of 1'-4" wide to be provided with three drawers &amp; drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood &amp; Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge biding with laqucer polished etc complete as directed.</p> |       |      |
| 4 | <b>STORAGE CABINET with Top &amp; Front laminate finished. Storage of any height</b>   | 36.00 | SQMT |
|   | <p>Same as above Item No-7, but all external surfaces to be finished with Laminate (approved shades)</p> <p><b>FINISHING DETAILS IN NUTSHELL:</b></p> <p>1) Top : Dark Laminate &amp; Burma Teak beading on Edges with pilishade</p> <p>2) <b>Front Apron &amp; Sides:</b> Dark Laminate/Frosty white Laminate as per design &amp; instructions</p>  |       |      |
| 5 | <b>P/F PANTRY PLATFORM CUB BOARD SHUTTER</b>   | 1.80  | SQMT |
|   | <p>Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface</p>  |       |      |
|   | <b>LOW HEIGHT PARTITION WORK</b>   |       |      |
| 6 | <b>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS</b>  | 28.00 | SQMT |
|   | <p>Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.</p>        |       |      |

7 **FULL HEIGHT PARTITION WORK**

**P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR**

50.00 SQMT

Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed and including removing existing partition and stacking of serviceable materials

For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.

8 **PANELLING WORK**

**P/F Wall panelling with laminate finishing for wall and Pillar etc**

35.00 SQMT

Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .

**FALSE CEILING WORK**

9 **P/F GYPSUM BOARD FALSE CEILING**

120.00 SMT

Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of **Gypsteel ULTRA ( Gypsteel Ultra shall be used)** supporting system in line and level. Finishing the surface and **applying 3 coats of Plastic emulsion paint** as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.

**After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.**

**Note : (1) Rate includes dismantalling of existing GYPSUM/ AMF/ POP false ceiling including stacking of servicable materials & disposal of unserviable materials & making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment.**

10 Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid 50.00 SMT

Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. **Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose**

After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications

Rate includes dismantling of existing Mineral fibre ceiling.

11 Refixing/Refitting and Reconditioning of existing wooden partition (LHT & FHT) with change of new location Including necessary polishing repairing/alternation if required complete as directed. Contractor must inspect site before quoting. 50.00 SMT

**TOTAL COST**

\_\_\_\_\_  
\_\_\_\_\_

**Note:**

[a] In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this.

[b] All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balacing laminate of aproved make & shade in the all S.W Counters/Tables/ Credenza, Storage Cup Board etc.