

Bill of Quantities for Interior Furnishing Works at Proposed State Bank of India., NAYA NANGAL BRANCH, NANGAL.					
INTERIOR FURNISHING WORKS					
S.N	ITEM	UNIT	QTY	RATE	AMOUNT
INTERIORS / FURNISHING					
1	<p>Single Level SWO Counters Providing and fixing at site SWO counters each upto 5'0" long, 2'-6" high and 3'-0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick laminate on outer visible surfaces excluding table curviliner top (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood/MDF beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commercial ply and finished with 6mm thk. flexi ply as base for polyacrylic sheet or approved laminate as/design with provision for LED Light in bottom. Teak wood/MDF lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, , of EBCO make fixed on channels, as per manufacturer's instructions / specifications.</p>	Rmt	14.00		
	<p>Three drawers with autolock running on both sides mounting Telescopic (channels) of Godrej, EBCO, Ozone make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non Visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finished with 1mm thk. white/off white laminate. All exposed Teak wood edges / teak wood lipping /MDF beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest , Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.</p>				
	<p>Makes: Commercial ply: Century, Greenply, Archid ply Laminate: AICA, Greenlam, Merino, Formica Telescopic Channels: Godrej, EBCO, Ozone Drawer Locks: Godrej, Ozone, EBCO Autolock: Ozone, EBCO</p>				
2	<p>12 MM thk. toughend glass for Banking / SWO Counters Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free. Superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides to holding the front glass partition to S.W. Counter.</p>	Sq.mt	14.00		
	<p>Make: Asahi India, St. Gobain,</p>				
3	<p>Superior quality stainless steel L - shaped slamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.</p>	Nos.	18.00		
4	POLYACRYLIC SURFACE HARD TOP ON SWO COUNTER TOP:				

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
	Providing and fixing (12mm thick) white polyacrylic stone (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all respect including adhesives, buffing and wastage.	Sq.mt	21.50		
	Make: LG Hausys, Granium, Merino Hanex, Stylam and Granex				
5	Officer's & Staff Tables				
	Officers Table made of 19 mm thk. Commercial ply(ISI marked- GREEN (Ecotech)/ CENTURY (Sainik) with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); with 40 mm X 6 mm thick teak wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer/ electrical cables at appropriate place will be made in the top surface of the table. Teak wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 fixed on channels(EBCO/ HARRISON/ GODREJ). A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, which will be made of 19mm thick BWP commercial ply finished with laminate 1mm thk. One openable shutter one lockable drawer running on side mounting drawer slides (channels) & made of 19 mm thick BWP commercial ply with 1mm thick laminate on front face, handle / knob shall be provided. The sides of the drawer shall be made of 12 mm thick plywood (ISI marked- GREEN (Ecotech)/ CENTURY (Sainik), bottom of 6 mm thick plywood. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Inside of drawers & Non-Visible/ inside surfaces i.e. inside / leg-space of table, inside of cupboard will have white coloured 1mm laminate. Teak wood edges / lipping / beading shall be Spirit polished.				
	Makes: Commercial ply: Century, Greenply, Archid ply Laminate: AICA, Greenlam, Merino, Formica Telescopic Channels: Godrej, EBCO, Ozone Drawer Locks: Godrej, Ozone, EBCO				
a	Size 7'0" X 3'0" X 2'6"	Nos.	1.00		
b	Size 6'0" X 3'0" X 2'6"	Nos.	1.00		
c	Size 5'0" X 2'6" X 2'6"	Nos.	3.00		
6	8.0 MM thk glass on top of officers tables. Providing & Fixing 8mm thk clear float glass for Officers' & BM table top with bevelling on edges all around & grinding including cutting for wire manager as per the instructions of the Achitect/Engineer in charge.	Sq.mt	7.25		
7	Side Credenza Providing & fixing Side credenza 3'6" long & 15" deep, made of 19 mm thick commercial ply (ISI marked- GREEN (Ecotech)/ CENTURY (Sainik) and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have two drawers on top, horizontally running on side mounting drawer slides (channels) of EBCO/ GODREJ make, & inner surfaces finished with 1mm thk. white/off white laminate. The remaining part of the credenza will have cupboard with shutters and one shelf, with handle /knob and magnetic catcher. All non visible/inside surfaces shall be finished with 1mm thk. white/off white laminate and teak wood edges/ lipping/ beading shall be Spirit polished with matching pigment.				
a	Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - 3'-0" / 4'-0" X 1'-6" X 2'-6" (W X D X H)	Rmt.	5.50		

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
	Commercial ply: Century, Greenply, Archid ply Laminate: AICA, Greenlam, Merino, Formica Telescopic Channels: Godrej, EBCO, Ozone Drawer Locks: Godrej, Ozone, EBCO				
8	Back credenza / Storage Providing & fixing storage cabinets, 18" deep & height as specified, made out of 19mm thick commercial plywood, including the inner shelves & shutters. The visible external surface shall be provided with 1.0mm thick laminate of shade specified, whereas internal surface including both sides of shelves shall be provided with balancing laminate of 0.8mm thickness. All the exposed edges of shutters & shelves shall be provided with beechwood lipping 5mm thick with clear polish finish. The shelves shall be spaced at approx. 15" vertically/as per drawings. The cabinets shall be complete in all respects with handles, catchers, locks, tover bolt(inside) etc.				
	In low height / back storages, drawers shall be provide as per design, running on telescopic channels. Internal surfaces shall be provided with 0.8mm th. Balancing laminate., whereas the visible top shall be provided with 1.0mm thick laminate	Sq.mt	19.00		
	Makes: Commercial ply: Century, Greenply, Archid ply Laminate: AICA, Greenlam, Merino, Formica Telescopic Channels: Godrej, EBCO, Ozone Drawer Locks: Godrej, Ozone, EBCO				
9	False Ceiling With Steps. - Gypsum Board Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).	Sq.mt	330.00		
	The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade.				
	The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps/ Vertical bands shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges,tools, lifts and all heights etc.				
	Make: Armstrong., St.Gobain (Inida Gypsum),, USG Knauf				

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
10	False Ceiling - (Mineral Fibre) Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – <i>Fine Fissured micro lock with silhouetted grid (black reveal)</i> , Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.	Sq.mt	84.00		
	Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.				
	Make: Armstrong., St.Gobain (Inida Gypsum),, USG Knauf				
11	Teak Ply Ceiling Providing and fixing 4mm thk. teak veneer in ceiling over 8mm thk. commercial ply screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes espirit polished of approved shade. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.	Sq.mt	20.00		
11	Wooden Partition with glasses frosted film as and where specified in laminate both sides. Providing and fixing Low / Full Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick commercial ply and 1.0 mm thick laminate as per pattern on both side's upto 4'0" height. The skirting shall be finished with 1mm thk brusshed steel finsih lamiante. Also 3"x5/8" teak wood section shall be provided on the exposed edges of the partitions, including provideing grove for 12mm/8mm thick glass wherever specified. The rate shall also include providing and fixing 8mm thk. glass of approved make with frosted film and also for providing grooves in laminate & wood.	Sq.mt	105.00		
11a	Wooden Partition with glasses frosted film as and where specified in teak veneer both sides. (basic price Rs 70/- sq.ft teak veneer)	Sq.mt	33.00		
	Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details. (iii) Measurements to be recorded up to finished false ceiling level.				
	Makes: Commercial ply: Century, Greenply, Archid ply Laminate: AICA, Greenlam, Merino, Formica Telescopic Channels: Godrej, EBCO, Ozone				

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
12	<p>Wall Paneling Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply and following finishigs as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza , storage etc.</p>				
a	Panelling with laminate	Sq.mt	87.00		
b	Panelling with teak veneer	Sq.mt	30.00		
c	Panelling with 12mmMDF with Spray Paint/Texture	Sq.mt	23.00		
	<p>Makes: Commercial ply: Century, Greenply, Archid ply Laminate: AICA, Greenlam, Merino, Formica</p>				
13	<p>Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop & Suggestion Box Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.</p>	Nos.	1.00		
	<p>Commercial ply: Century, Greenply, Archid ply Laminate: AICA, Greenlam, Merino, Formica</p>				
14	<p>Night latch in cash cabin door - Providing and fixing night latch lock Godrej/ Doorset/Ozone make in aluminium / wooden doors, complete in all respects.</p>	Nos.	2.00		
15	<p>Fixed Glass / Glazing for B.O & E - Lobby - Toughened Glass 12.0 mm thk. including frosted film as and where specified. Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grained, polished to be fixed with necessary patch fittings (Godrej / Ozone/ Dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate</p>	Sq.mt	15.00		
	fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include necessary etching film / logo all inclusive, complete				
	Make: Asahi India, St. Gobain,				
16	<p>Wall Connecting Profile Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass.,make: DORMA/OZONE</p>	Rmt	5.00		
17	<p>Toughned Glass Doors Providing & Fixing Openable 12mm thk. Toughned Glass Door,holded with Patch fitting (i.e. bottom & top patch,L-Patch, floor machine & Door lock) of (Godrej/Dorma/Ozone/Stanley) make,fixed in position as per manufacturers guidelines.</p>				
	The Job also includes providing & fixing of 24" long SS handle & provisions of holes/cuts in glass panel to facilitate fixing of Patch fitting & Handle. The job shall be complete in all respects,including necessary hardware, complete in all respects as per the instruction of the Architect / Engineer in charge.	Sq.mt	16.00		

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
18	Roller Blinds of Vista Make- IceLand Series				
	Providing & Fixing Roller Blinds of Vista make- Victorian Series made of Translucent fibre glass fabric of approved shade including 32mm round channel and mechanism and other fitting fixed in position as per manufacture's specification, complete in all respects to the satisfaction of Architect/Engineer in Charge.	Sq.mt	32.00		
19	PLANTER BOX				
	Supplying Planter 15"x15"x15" made of 19mm comm. Ply with 1mm laminate and polished teak wood moulding 25x 8 mm on top & lining of aluminum sheet.	Nos	4.00		
21	WOODEN Boxing				
	Providing & fixing wooden boxing on columns as per details, using 19mm thick commercial ply, with 1 mm thick laminate fixed as per pattern, complete in all respects.	Sq.mt	16.25		
23	Painting Work – Texture Paint				
	Providing and applying special / texture paint Asian royal matalic finish of approved shade & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc.	Sq.mt	51.00		
26	Panelling With Aluminium Composite Panels (With Aluminium Frames)				
	Supplying & fixing 3mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.25mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering, scafoolding, labour, material, complete.	Sq.mt	100.25		
26	MS FRAME FOR ACP CANOPY				
	Supplying & fixing MS Frame made out of hollow MS tubes of different sizes as per design, complete in all respects including cutting, welding and fixing to wall/slab with fasteners/bolts etc.	Kg	150.00		
22	WOODEN BOXING & SHUTTERS FOR ELECTRICAL PANEL with LOUVERS (18mm FIBRE CEMENT BOARD)				
	Providing & fixing at site cabinet 8'-6" height having overall depth of 1'-6".the carcass shall be made of 18mm thk Fibre Cement Board. The shutters shall be made of 18mm thk Fibre Cement Board. with 1.0mm thk laminate on outer surfaces using suitable adhesive. The shutters shall be mounted on heavy duty overlap type SS hinges & provided with magnetic catchers, lock & towerbolts as required with 5mm thk teak wood lipping on all the exposed edges, duly spirit polished. All internal surfaces, & back of shutters shall be painted white, complete in all respects. MAKE : ZYKRON (Century Ply) / SHERA Board / Equivalent	Sq.mt	5.00		
	Makes: FIBRE CEMENT BOARD: Zyrcon(Century), Shera Board, Gyproc (St. Gobain) Laminate: AICA, Greenlam, Merino, Formica				
27	Door to System room - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC.	Sq.mt	1.95		

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
a)	Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fastners).				
b)	Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately).				
c)	Hardware for fixing - Fire rated steel door including frame Providing and fixing following hardware for fixing fire rated steel door including frame, complete. Hinges 4X3X3 (Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.)				
SUB TOTAL PART A					
PART B					
WEALTH HUB_Emerald Lounge Works					
1	OFFICER'S TABLE- Size 1500mm x 750mm x 750mm (for Wealth Hub)				
	Supplying and installation of Table as per the following description and as designed by the Architect: Table Top: Providing and fixing 19 mm thick IS 303 BWR grade plywood with 4mm thick Teak veneer with melamine finish with necessary intermediate support. Table top shall be supported by 18 mm thick BWR grade ply wood with plywood framing. The top of the table shall be provided with equal sized 12mm thick toughened glass with polished edges. The top level of the glass shall be 750mm. Apron (Modesty Panel) made from 18mm thick BWR grade plywood finished with 1mm laminate. Table sides, back & intermediate panels (at 500mm from each side) made from 18 mm thick MR ply wood finished with 1mm laminate for exposed surfaces (4 faces) and 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. Drawer / Storage cabinet: Box of 400 X 750 X 720 mm shall be provided using 18 mm thick BWR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick BWR grade plywood. The drawer unit box and individual drawers to be fixed with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles C-type for each drawer. The front ply of the drawers to be overlapping the frame.	Nos.	2.00		

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
	Computer Keyboard (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest of 38 x 76 MM T.W members shall be provided. All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm ply finish with 1 mm thk. Laminate of size 400 x 375 mm for keeping CPU and PVC cable Manager shall be provided in the cutouts on the tabletop. All edges to be provided & fixed with teak wood lipping patti finished with melamine polish. All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade.As per drawing and instruction of Architect/Bank, work to be completed. Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.				
2	SIDE/ REAR CREDENZA- For officer and clerical staff table (for Wealth Hub)				
	Low Height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of 750 height and 450mm deep. Outer exposed structure with to be made with 19mm BWR ply as per IS 303 and back side using 8mm BWR grade ply. All shutters to be made from 25 mm thk BWR Ply and shelves to be made with 19 mm thk.BWR ply.The top portion of the side and rear credenza to be finished with approved veneer and finished with melamine polish. All the other internal and external surfaces to be finished with 1mm laminate of approved shade and All edges to be provide with TW lipping patti finished with melamine polish. Shutters will have concealed handle with wooden groove finished with approved shade of melamine polish as per drawing, magnetic	Nos.	2.00		
	catchers, self-closing SS hinges, locks (Godrej/ Hettich/Hafele), SS towerbolts etc. All shutters to be made overlapping the frame Only front elevation will be considered for area calculation. As per drawing and instruction of Architect/Bank, work to be Completed Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.				
3	Center Table (3'-0" X 2'-0" Oval / Rectangular) (for Wealth Hub)				
	Providing and supplying in position oval or rectangular centre table to be made out of 2" X 2" teakwood frame including 12mm thk clear glass top with bevelled edges including bottom glass shelf with etching etc complete. The rate shall also include SS lining design to the teakwood frames including all the necessary hardware, fittings, fixtures as per manufactursrs specifications complete.	Nos.	1.00		
4	FULL HEIGHT SOLID WOODEN PARTITION WITH BOTH SIDES LAMINATE				
	Providing & fixing in position 70mm thick +/- 2mm full height solid/opaque wooden partitions finished with laminate on both sides comprising as under:- (i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) both ways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling. (ii) Plywood skin:- Providing & fixing 8 mm thick comm.ply on both sides of the framework and additional 6mm thk. MDF on both side in layers to create grooves as per the design. (iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate, on both sides of partitions in approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approve quality adhesive complete.				

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
	<p>(iv) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full-length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.</p> <p>(vi) The door shall be provided with approved make lock, heavy duty door closer, 4 nos. of 5" brass oxidized hinges, SS Brush finish H handle of 9" etc. complete.</p> <p>(vii) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutouts etc. complete.</p> <p>(viii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) MDF Board:- Greenply, Century, Samrat or equivalent approved by the Bank.</p> <p>(c) Laminate:- Greenlam/Century/Archid or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p>	Sq.mt	9.00		
5	WALL/ COLUMN PANELING WITH LAMINATE FINISH.(for wealth hub)				
	Wall paneling made from 25 x 25 x 1.00 mm thick hollow aluminum sections, over which BWR grade ply of 10 mm shall be fixed and additional 6-8mm ply in layers to create grooves as per the design in the drawing or as directed by Architect, with decorative molding patty on the edges.				
	<p>Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:-</p> <p>(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing & fixing 9 mm thick approved make BWR plywood and additional 6-8mm ply in layers to create grooves as per the design to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate, using approved adhesive, in approved pattern & design, including providing grooves, decorative moldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge.</p> <p>(iii) Providing approved quality, seasoned, full length, Teak Wood molding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as directed by the Engineer-in-charge at site.</p> <p>(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards,</p>				

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
	<p>AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>(v) Applying 2 or more coats of melamine polish to exposed edges of paneling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</p> <p>(c) Laminate:- Dorby Mica, Greenlam/Century/Archid / Aerolam or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear paneling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.</p>	Sq.mt	19.00		
6	MDF FLUTED WOODEN PANELLING (for wealth hub)				
	<p>Wall paneling made from framework of 25 x 25 x 1.20 mm thick hollow aluminum sections spaced 600mm c/c, over which MDF fluted wooden panel of 10mm +/- 2mm shall be fixed as per the design in the drawing or as directed by Architect.</p> <p>(i) Framework:- Made out of 25 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing & fixing 10mm +/- 2mm thick approved MDF Wooden Panelling fixed on the aluminum sections with tongue and groove joints in line and level.</p> <p>(iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p>	Sq.mt	6.00		
	<p>iv) The Duco paint shall be of approved make and shade. The surface to be painted shall be first prepared smooth by applying proper grade of sandpaper/water-paper and then if any pores are noticed the same shall be filled with approved quality synthetic filler agent. The complete surface shall be then applied an even coat of sealer putty and permitted to dry. The surface shall be again grinded smooth and even using appropriate grade of water-paper. When the surface is properly smooth and leveled without any pores or cracks the same shall be spray painted with approved quality Duco paint. The adjoining surfaces which are not to be painted with this application shall be suitably masked using appropriate masking tape. The paint shall be permitted to dry at room temperature and attain smooth lustrous finish.</p>				
7	BACK PAINTED GLASS + LOGO				

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
	<p>Back painted glass (Lacquer Glass) paneling: Providing and fixing in position wooden paneling to column / walls finished with Back painted (Lacquer Glass) comprising as under:- (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed upto 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. (ii) Panel Finishing:- Providing & fixing 9 mm thick approved make BWR plywood to Aluminum framework finished with 8 mm thick approved quality and make back painted Lacquer Glass panels of required size, rigidly fixed using 3M adhesive / double side self-adhesive tape complete as directed by the Engineer-in-charge. (iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards etc., including providing necessary wooden/aluminum section members support at cutouts, providing scaffolding for execution of work at all heights, complete as per drawings and as directed by the Engineer-in-charge at site.</p>	Sq.mt	5.00		
8	<p>Logo:- Providing and fixing in position with SS studs or as directed laser cut Logo as per design made from 18 mm MDF board (exterior grade) and and 10 inch -12 inch high and finished with PU metallic paint as directed complete.(<i>i.e. SBI LOGO and SBI EMERALD</i>)</p>	Nos.	1.00		
9	<p>FALSE CEILING FINISHED WITH LAMINATE</p>				
	<p>Same as Gypsum false ceiling but instead gypsum boards providing, making, and fixing 12 mm thick. BWR Grade ply, and additional 6-8mm ply in layers with molding of approved design shall be fixed as per drawing or as directed by Architect, with decorative molding patty. The plywood should be finished with 1 mm thick. Laminate of approved colour(wooden finish) and quality.</p>	Sq.mt	5.95		
10	<p>Fixed Glass / Glazing for B.O & E - Lobby - Toughened Glass 12.0 mm thk. including frosted film as and where specified. Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grainded, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate</p>	Sq.mt	27.50		
	<p>fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include nessery etching film / logo all inclusive, complete</p>				
11	<p>Wall Connecting Profile</p>				
	<p>Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass.,make: DORMA/OZONE</p>	Rmt	15.00		
12	<p>Toughned Glass Doors</p>				
	<p>Providing & Fixing Openable 12mm thk. Toughned Glass Door,holded with Patch fitting (i.e. bottom & top patch,L-Patch, floor machine & Door lock) of (Godrej/Dorma/Ozone/Stanley) make,fixed in position as per manufacturers guidelines.</p>				
	<p>The Job also includes providing & fixing of 24" long SS handle & provisions of holes/cuts in glass panel to facilitate fixing of Patch fitting & Handle. The job shall be complete in all respects,including necessary hardware, complete in all respects as per the instruction of the Architect / Engineer in charge.</p>	Sq.mt	4.25		
13	<p>Wooden Flooring (For Wealth Hub)</p>	Sq.mt	26.00		

S.N	ITEM	UNIT	QTY	RATE	AMOUNT
	Providing and placing in position wooden laminate flooring with planks of size not less than 1200 mm X 190 mm (with unlinlk panels / tongue-groove locking arrangement) having a 0.2 mm thick top abrasive layer followed by decorative layer upon HDF (high density fiberboard) substrate core over raisin saturated backing layer installed using tongue-groove system over 2 mm thick underlayer of polyurethane foam on 250-micron polythene sheet over a smooth, flat, hard and free from moisture floor surface complete in all respect with required accessories like end profile, transition profile, reducer 'T' profile etc. and preparation of base including all other incidental works as per direction & satisfaction of Architect in charge. Cost of Laminate Floor Accessories, Skirting, End edge, T- molding, Reducer shall have to be added in the cost, wherever required. Grade :- AC4				
SUB TOTAL PART B					
SUB TOTAL PART A+ PART B					
PART C					
B	CREDIT OF OLD MATERIALS				
a	Existing old Aluminium /Wooden partitions including dismantling and removing from premises.	Sq.mt	64.00		
b	Existing wooden / steel tables of various sizes, including removal from branch premises.	No	20		
c	Existing Wooden Storage including dismantling and removal from premises.	Rmt	24		
d	Existing Gypsum Ceiling/Mineral Ceiling including G.I Sections,Frames etc. and also removal from site.	Sq.ft	460		
SUB TOTAL PART C					
All old material to be lifted from branch to muncipal dump or contractors own dump.					
GRAND TOTAL (Part A + Part B)- Part C					
Signature of Contractor					