

SCHEDULE OF QUANTIITES FOR ATM WORK AT PONNAMPET BRANCH

Sl.No.	Description	Units	Qty	Rate	Amount
A	CIVIL WORK				
A1	DEMOLITION OF WALLS : Dismantling of existing structures like wall and other structures comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material debris and stacking the serviceable material with all lifts dismantling Brick / Tile work in cement mortar.	Sqm	14		
A2	CONSTRUCTING OF 8" THK SOLID BLOCK WALL: Providing and constructing 8"(200mm) thick Aerocon block masonry in cement mortar 1:4 using precast blocks with minimum crushing strength of 35 kg/sq. Cm including raking out joints, scaffolding, curing etc. complete as per directions of EIC / Architect.	Sqm	25		
A3	PROVIDING 12MM THICK PLASTERING : Providing and applying internal cement plaster - average 12mm thick in Cement Mortar 1:4 (1 cement : 4 fine sand) without neeru finish to concrete/brick/siporex or any other surfaces in all positions, levels and heights including finishing, scaffolding, curing, etc., complete as per directions of EIC / Architect.	Sqm	55		
A4	ANTISKIED FLOORING : Providing Ceramic Antiskid parking Tiles of approved makes,shade and size for flooring laid on a bed of 12mm thk,cement mortar 1:3 mix, flush pointing with white cement using colour pigment. Tile Size 300mmx300mm and 6mm thk. Rate including cost of materials,labour,curing, complete as per specifications. Basic cost shall not be less than Rs.65/- per sft excluding taxes, transport and labour. The vendor shall Submit the Tax invoice from manufacturer confirming make of tiles supplied.	Sqm	2		
A5	Rolling shutter with manually operated gear; Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with mechanical gear operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.20 mm M.S. laths with 1.20mm thick top cover including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Sqm	10		

A6	Vitrified Tile Flooring with Mortar; Providing and Laying Vitrified Tiles in Flooring laid in design pattern on bed of 20mm (average) thick cement mortar 1:3 laid to slope as required including cement slurry, finishing joints etc complete. Tiles shall be laid with 2-3 mm spacers for joints and finished with epoxy grout complete in matching shade.(Basic price 550 per smt excluding tax, transportation, wastage,loading/unloading etc)	Sqm	12		
		Total Civil (A)			
B	INTERIOR WORK				
B1	Providing and fixing aluminium composite panel partition with skin material each side 0.25mm thk aluminium sheet cover material with 2.5mm natural polyethelene core , cladding panel fixed on outside and innerside shall be 12mm thk. plain fibre cement bonded sheet. Supported on extruded aluminium frame (50x50x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete ACP Cladding - 3 mm thick ACP shall be of Eurobond/ Auldecor/ Alstone/ Viva or equivalent as approved by the Bank. Innersided of the partition shall be painted with 2 coats of plastic emulsion paint over primer coat.	Sqm	14		
	As per site requirement door made of extruded aluminium frame (50x25x1.5mm) having fixed with 4 ACP of same shade colour of the panelling on one side and otherside shall be of plain fibre cement bonded sheet with necessary powder coated (blu/ black colour) hinges, door locks etc complete shall be provided. width of the door shall be minimum 600mm wide.				
B2	Providing and fixing 150mm wide x 1200 mm length powder coated aluminium louvers. Color shade shall be as approved by the Bank.	nos.	2		
B3	Mineral Fibre Tile/ Grid ; 20mm thk Mineral fibre tile ceiling on metal grid as per standard, reputed manufacturers specifications broadly consisting of, metal 'T' sections of max.15mm wide and with groove(silhouette with black reveal) fixed at about 600mm bothways with GI wires, wall anglesec.Mineral fibre tile of approximate thickness 20mm and having NRC 0.70 placed in the above grid. All necessary cutouts to be made for spot lights, smoke detectors etc. All as per standard manufacturers specification.	Sqm	11.2		
B4	Designer film ; Providing and fixing in position Designer Film on all glasses as per drawings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.	Sqm	7		
B5	Plastic Emulsion ; Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.	Sqm	55		

B6	Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc., complete for finished item of work , if any. ACP Cladding - 3 mm thick.	Sqm	27		
B7	Supplying and fixing Rolling Shutter box of aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm), plywood boards angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc., complete for finished item of work , if any. ACP Cladding - 3 mm thick.	Sqm	6.9		
B8	FIXED GLASS WORKS FOR PARTITIONS Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Skirting level upto available Ceiling / beam / lintel level and inline with wooden parttions / doors etc as per layout plan. The glass is to be fixed onto the ply/Exterior Grade MDF base with patch fittings and all the edges of the glass to be machine polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions including silicon sealant between glass panels etc., complete.	Sqm	5		
B9	Providing, making and fixing in position Fixed 12mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1830mm x 2135mm - 2440mm in two leaves, and Partition Doors of approximate size 900 - 1065mm x 2135mm - 2440mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.	Sqm	2.05		
B10	Providing and supplying perforated stainless steel dustbin	Nos.	2		
B11	Providing and fixing sandwich acrylic display boards with SS studs of size 900mm x 1200 mm	Nos.	2		
B12	Providing Acrylic backlit SBI Logo, letter height shall be 1.5 feet	Nos.	1		
		Total Interior (B)			
		Total (A+B)			
	Amount in words				

*** GST will be extra