

TENDER FOR PROPOSED M.S STAIRCASE AT GM'S BUNGALOW, CHAR IMLI, BHOPAL					
S.No	Description	Unit	Qty	Rate	Amount
1	M.S Fabrication work for stalrs				
(a)	Providing and fixing at site M.S fabricated steel structure and railing made out of M.S sections, I-section, C-Channel as specified by the Bank in the drawings / details for roof truss, side cladding, purlin, grill door, retrofitting works etc. made out of ISA, Sq. M.S Bar, flat, Square and round M.S pipes, ISMC, ISMB section etc. supported on concrete bed blocks casted over Brick walls as specified in the details. The structure shall be welded by arc welding of superior quality using best quality electrodes, drilling etc. hammering excess deposits and then finishing with surface grinders. The rates shall includes the cost of anchor bolts, washer, nuts, cost of scaffolding, two or more coats of painting of superior quality of primer and then two or more coats of enamel paint of approve made or shade complete in all respects as directed by the Bank.	Kg	2200		
	For 3 Nos of Staicase				
	Total Cost of the Project				

GST EXTRA AS APPLICABLE

SEAL & SIGNATURE OF THE VENDOR