

Bill of Quantities (BOQ) for Interior Renovation Works of Staff Canteen, Ground floor at SBI L.H.O. Building, Sector-17 A, Chandigarh.

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
PART A CIVIL WORKS						
1.00 FLOORING / WALL CLADDING						
1.10	Full Body Vitrified Tiles	Providing & fixing Full body vitrified tiles of size 600x600 mm or PLANKS Tiles 280 x 1800 or 200 x 1200 of approved make (Emser / Restile/ Kajaria/Orient/Jhonson) in flooring laid in any pattern as specified over base of 20 mm thick cement coarse sand mortar 1:3,/ Tile chemical of approved make i.e. (Roff/Pidilite/Mapei) with 3-4mm spacers and grooves filled with epoxy of approved makes and color (make: Pidilite/Sika/Varmora) to match the shade to tiles. Works include dismantling of old floor and removal of malba to nearest MC dumpyard.	SQM	385.00		
		(Incl. Waiting Area/Pensioners Room/Childeren play area/PHYSIOTHERAPY Rm/ Canteen & Kitchen area)				
1.20	Vitrified tiles 600mm x 600mm or Moraccon Tiles 300mm x 300mm	Providing and laying 1st quality Vitrified / Moraccon tiles 600mm x600mm or 300mm x 300mm (as specified in Dado (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: on 20 mm thick cement mortar 1:4(1 cement: 4 coarse) sand), including grouting the joints with white cement and matching pigments etc., complete.Approved makes(Nitco, Johnson, RAK, Kajaria (Note: Work Incl.Dismantling of existing tiles and disposal of material to contractors own dump.)	SQM	125.00		
		(Incl. Canteen & Kitchen area)				
2.00 P.O.P. / FALSE CEILING WORK						
2.10	Gypsum False Ceiling	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed form M.S. sheet and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS ; 277 and consisting of angle cleats of size 25mm wide x 1.6 mm thick with flanges of 27 mm and 37 mm, at 1200 mm center to center, one flange fixed to the ceiling with dash fastner 12.5mmx50mm long with 6mm dia bolts other flange of cleat fixed to the angle hangers Of 25x10..50 mm of required length with nuts and bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the rate of 1200 mm centre to centre which the ceiling section 0.5 mm thick bottom wedge 80mm with tapered flanges of 26mm each having lips of 10.5 mm, at 450 mm centre to centre shall be fixed in the direction prepencicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channles 0.5 mm thick 27mm high having flanges of 20 mm and 30 mm long, the perimter of ceiling fixed to wall/partion with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screw @ 230 mm interval, including fixing of gypsum board to ceiling.Section and perimter channel with help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edes of the board with recmmended jointing compound, jointing tapes, finishing				

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
		with jointing compound in 3 layers covering up to 150 mm or both sides of joint and 2 coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channel suitably fixed, all complete as per drawings, specification and direction of the engineer in Charge but excluding the cost of painting with : Note: work to include, removing and staking of Existing Gypsumboard ceiling including G.I. channels and preparing the surface for new work neatly as per complete satisfaction of engineer-in-charge.				
		12mm thick tapered edge gypsum moisture resistant board.	Sqm	205.00		
2.20	Mineral Fibre Grid ceiling with Black Silhouett Grid	Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main runner spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.	Sqm	60.00		
2.30	Veneer Ceiling	Providing and fixing 4mm thk. veneer in ceiling over 12mm thk. marine ply screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes P.U. polished of approved shade. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.	Sqm	35.00		
2.40	Wooden Battens in ceiling	Providing and fixing 38-50mm thk. ply wood battens clad with 4mm thk. teak veneer all around and fixed in ceiling screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes P.U. polished of approved shade. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.	Rmt	60.00		
		Basic Veneer Price : Rs 85/-				
3.00	DOOR / WINDOW WORK.					
3.10	UPVC Door & Windows with DG Glass	Supplying and fixing in position UPVC Casement windows (one opening in each window size of different sizes (visit site for verification) made out of frame section size of 80 mm in white color with DG Glass 5-12-5 and openable section of 62mm complete in all respects with hardware of Kinlong as approved.	Sqm	85.00		
4.00	MASONRY					
4.10	230mm thick brick masonry	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in:				

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
.		Cement mortar 1:6(1 cement: 6 coarse sand)	CUM	0.30		
4.20	115mm thick brick masonry	Half brick masonry with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level				
		Cement mortar 1:4(1 cement :4 coarse sand)	SQM	18.00		
		Extra for providing and placing in position 2 Nos. 6mm dia. M.S. bars at every third course of brick masonry.	SQM	18.00		
4.30	Granite Cill	Providing and fixing 18mm thick gang saw cut mirror polished premoulded and prepolished machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
a		Granite of any colour and shade				
b		Area of slab over 0.50 sqm	sqm	8.00		
4.40		Providing edge moulding to 18mm thick stone counters, Vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge				
		Granite work	Rmt	31.00		
5.00	PLASTERING					
		The plaster shall be of sufficient thickness to fill up all undulations in the surfaces of masonry and to provide a true surface for wall/ceiling plaster. Special care shall be taken to soak the walls before applying the plaster and finishing the surface of plaster to ensure uniform texture and free from air cracks. Before starting the work sufficient No. of button marks shall be done to plumb and level to achieve uniform finish				
		The rate should include the cost of forming grooves of sizes as required, wherever grooves are to be provided horizontally/ vertically for in accordance with the drawings.				
		Plastering to be done either vertical face, horizontal face or angular face. Rate shall include circular /semicircular or any other shape of the faces of plastering area.				
		Rate shall include forming of drip mould/ bands etc.,				
		The rate to be inclusive of providing galvanised chicken mesh overlapping to a width of 150 mm at the junctions of masonry and concrete works including tying in position by using suitable nails / clamps / screws and as directed etc. complete at all levels				
		The contractor shall make good all the grooves, pockets etc. after the scaffolding is removed.				
5.10	Internal Rough Plaster	12 mm cement plaster of mix:				
		1:6 (1 cement: 6 fine sand)	Sqm	40.00		
6.00	PAINT & POLISH					

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
6.10	Plastic Emulsion Paint	Painting & finishing the walls, including surface preparation primer and putty ,finished with three or more coats of plstic emulsion paint, so as to achieve smooth and even finish complete in desired shades and colours (as approved by Architect/Engineer-In-Charge).				
		1:6 (1 cement: 6 fine sand)	Sqm	180.00		
7.00	Plumbing Works					
7.10	Composite Piping	Providing & fixing 1/2" and 3/4" composite pipes make : Kitec /Vectus pipes for distribution in toilets including chase cutting, chase filling, proper insulation for all pipes. The rate shall include all accessories like tees, unions, elbows, bends etc. Required to make the system operational and complete.	Rmt	80.00		
7.20	Drain Pipe	Providing & Laying PVC Drain Pipes of different sizes including all joints,tee, bends etc as per site requirement	Rmt	20.00		
7.30	Counter Basin	Providing & Fixing Counter Basin of JAQUAR MAKE 50mm x 40mm x 12mm	No	2.00		
7.40	Angle Cock	Providing & Fixing Angle Cock of JAQUAR MAKE	No	2.00		
7.50	Autoclosing Pillar Cock	Providing & Fixing Autoclosing Pillar Cock of JAQUAR MAKE	No	2.00		
7.60	Cp Jali	Providing & Fixing CP JALI of JAQUAR MAKE	No	8.00		
7.70	Paper Towel Dispenser	Providing & Fixing Paper Towel Dispenser of JAQUAR MAKE	No	1.00		
7.80	Wall Mounter Foam Soap	Providing & Fixing Wall Mounter Foan Soap Dispensor of JAQUAR MAKE	No	2.00		
7.90	Wall Mounter Sink Mixer	Providing & Fixing Sink Mixer with Regular Swinging Spout (Wall Mounted Model) With Connecting Legs & Wall Flanges., JAQUAR Model no: FLR-CHR-5309N	No	4.00		
7.11	Wall Mounter Sink Mixer	Providing & Fixing SS Double bowl sink with drainboard of minimum size of 1150 to 1200 mm and 460mm	No	2.00		
8.00	Dismantling Works					
8.10	Dismantling Works	Dismantalling of existing Wooden Flooring ., False Ceiling and removal of MS Doors & windows including dismantaling of granite cill.	Lumpsu m			
	Credit of Exiting MS Windows :	The work includes removal of existing MS windows and glass panels and uplifting of the same from site to contractors own dump.	Job	1.00		

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
TOTAL PART A (CIVIL WORKS)						
PART B INTERIOR WORKS						
1.00 PARTITIONS / PANELLING						
1.10	Wooden Partition in Laminate	Low/Full Height partly Glazed (with etching) & partly both side laminated Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be clad with 8mm thick commercial ply and 1.0mm thick laminate of APPROVED make in specified pattern as per interiors details on both sides .Also 2 1/2"X5/8" teak wood section shall be provided with 12mm thk. glass with etching work as per interior details where ever specified. The rate shall also include for providing grooves in laminate & wood. Note: (i) All ply to be sprayed with anty termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.	Sqm	160.00		
1.20	MDF Panelling with P.U. Paint	Providing and fixing ply base of wall panelling consisting of 50x50mm framework made out of kiln seasoned and chemically treated kail wood or equivalent approved wood. Members to be fixed at 600mmx600mm c/c bothways. 9 mm thick marine ply of approved make to be fixed to the framwork with the help of necessay screw, nails, adhesive etc. as per approved drawing complete in all respect and to the entire satisfaction of the Engineer-in-charge/consultent / architect. Finishing with additional 12mm thk. MDF (Greenlam/Action WaterProof) Panelling with chamfered edges as per design including P.U. Paint in desired shade and finish are to be pasted/nailed on an existing wooden subbase with additional 2" band of 12/8mm MDF around as per design.The base shall be prepared with PVC Sheet in backdrop over existing frame.	Sqm	60.00		
1.30	Exotic Laminate Panelling	Providing and fixing ply base of wall panelling consisting of 50x50mm framework made out of kiln seasoned and chemically treated kail wood or equivalent approved wood. Members to be fixed at 600mmx600mm c/c bothways. 9 mm thick marine ply of approved make to be fixed to the framwork with the help of necessay screw, nails, adhesive etc. as per approved drawing complete in all respect and to the entire satisfaction of the Engineer-in-charge/consultent / architect. Finishing with 1.25mm - 1.5mm thk. exotic Laminate of approved shade as per pattern with grooves to be pasted/nailed on an existing wooden subbase complete to the satisfaction of Engineer-in-charge/consultent / architect	Sqm	25.00		

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
1.40	Teak Veneer Panelling	Providing and fixing ply base of wall panelling consisting of 50x50mm framework made out of kiln seasoned and chemically treated kail wood or equivalent approved wood. Members to be fixed at 600mmx600mm c/c bothways. 9 mm thick marine ply of approved make to be fixed to the framwork with the help of necessay screw, nails, adhesive etc. as per approved drawing complete in all respect and to the entire satisfaction of the Engineer-in-charge/consultent / architect.Finishing with 4mm thk. Teak Veeneer of approved shade as per pattern with grooves to be pasted/nailed on an existing wooden subbase, including polish as per instructions complete to the satisfaction of Engineer-in-charge/consultent / architect	Sqm	15.00		
1.50	Teak Wood Beading	Providing and fixing 1.5" thk. And 2.5"- 3" high 1st Quality Teak wood Profile as per deail polished to approved shade as shown in the drawing and as per instructions given by the architect.	Rmt	25.00		
1.60	Deisgner Partition	Low/Full Height partly Glazed (with etching) & partly both side Teak/MDF Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 4.0mm thick TEAK PLY or 8mm thk. MDF as/approval finished with PU Paint/ polish made in specified pattern including CNC cut MDF Panels sandwiched in 4mm thk. glass/Fluuted Glass Panels/as per interiors details on both sides .All ply / wood to be treated with wood preservatives of approved ISI quality.Also 2 1/2"X5/8" teak wood section shall be provided with 12mm thk. glass as per interior details where ever specfied.	Sqm	12.00		
2.00 DOOR / WINDOW WORK.						
2.10	FLUSH DOOR with Laminate on Both Sides	Providing fully panelled 35mm thk. flush doors along with 2-1/2" x 5" door frames to be finished with 1.0mm laminate of approved shade with 1/8" x 1/8" groove asper design, complete in all respects including standard hardware of godrej/hettich/kich/edbo make i.e. hinges.,towerbolts,stopper,handles etc. to the satisfaction of Engg./ Architect	Sqm	9.35		
2.20	TOUGHENED GLASS DOOR	Providing & Fixing Openable 12mm thk. Toughned Glass Door,holded with Patch fitting (i.e. bottom & top patch,L-Patch, floor machine & Door lock) of (Godrej/Dorma/Ozone/Stanley) make,fixed in position as per manufacturers guidelines.The Job also includes providing & fixing of 24" long SS handle & provisions of holes/cuts in glass panel to facilitate fixing of Patch fitting & Handle. The job shall be complete in all respects,including necessary hardware, complete in all respects as per the instruction of the Architect / Engineer in charge.	Sqm	18.50		
2.30	Fixed Toughened Glass	Toughened Glass 12.0 mm thk. including frosted film as and where specified. Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grainded, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include necessary etching film / logo all inclusive, complete	Sqm	12.00		
3.00 BOUGHT OUT ITEMS						

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
3.10	Door closer	Doorset/Godrej make , cam action box type door closer with G-N slide channel arm for pull side fixing. Spring size EN 2-4 as per EN 1154 and CE marked. Silver/Antique finish. For maximum door size of 1100mm	Nos.	4.00		
3.20	Roller Blinds	Providing & Fixing S – CONTOUR BLINDS Vista Make Delux Collection (Elemental) Composition : 100% Polyester , Finished Width : 300 CM., Weight : 200 GSM., Thickness : 0.35 Mm,Colour Fastness to light: 4-5 Grade with supporting framework etc. of Bshade & colour complete in working order as per manufacturers specifications & drawings & directions of the Architect.	Sqm	95.00		
3.30	Art work	Providing and Fixing Paintings / Art work , selected by the Architects, Clients, for: size 12" x 12" or 15" x 15" or 12" x 24"	NOS.	12.00		
4.00	FURNITURE ITEMS					
4.10	Attendent Desk	Table made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); Table Top to be clad with additional 4mm thk MDF finished with Satin Enamel Spray Painted of approved shade, with 40 mm X 12 mm thick teak wood/MDF beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels, as per manufacturers instructions / specifications.				
		A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply finished with laminate 1mm thk. and ¾" x ¼" teakwood/MDF lipping on two visible sides. one lockable drawer running on side mounting drawer slides (channels) of EBCO make made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 1mm thk. laminate of white/off white shade and teak wood /MDF edges / lipping / beading shall be Spirit polished or Spray Painted as required.				
			Size 5'0" X 2'6" X 2'6"	No	1.00	

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
4.20	Officer's & Staff Tables	Table made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); Table Top to be clad with additional 4mm thk MDF finished with Satin Enamel Spray Painted of approved shade, with 40 mm X 12 mm thick teak wood/MDF beading all around, as per drawing. The front of the table top shall be projected as per drawing. The modesty guard shall be finished with 12.0 mm thk. toughed glass with 4" wide S.S. Spacer. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels, as per manufacturers instructions / specifications. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply finished with laminate 1mm thk. and 3/4" x 1/4" teakwood/MDF lipping on two visible sides. three lockable drawer running on side mounting drawer slides (channels) of EBCO make made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1 1/2" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 1mm thk. laminate of white/off white shade and teak wood /MDF edges / lipping / beading shall be Spirit polished or Spray Painted as required.				
		Size 5'0" X 2'6" X 2'6"	No	4.00		
4.30	8.0 MM thk glass on top of officers tables.	All the edges of the glass shall be grinded polished including Hole for cable manager.	Sq.mt	6.00		
4.40	Side Credenza	Providing & fixing Side credenza (15" to 18" deep) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment. Officer's & Staff side credenza as per Drawing & specification mention in item above. Size - 3'-0" / 4'-0" X 1'-6" X 2'-6" (W X D X H)	Rmt	5.00		
4.50	Back credenza / Storage	Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 36" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & 1mm thk laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawers 4" high, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf.				
		The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment	Sq.mt	3.00		

IT. NO	ITEM	DESCRIPTION OF ITEMS	UNIT	QTY.	RATE	AMOUNT
4.60	Storage Cabinet in Teak Finish with 12mm glass top	Providing and fixing 2'-0" deep Wooden Platform with Storage below (ht. 2'-9"). The Shutters shall be finished with approved shade teak ply from outside, including all hardware i.e. lock, handle, hinges etc. and the car case shall be finished with liner laminate from inside. The Top shall be finished with Teak ply and 12mm thk. glass on top with chamfered edges of approved shade with adhesives., complete with half round moulding from front side.	Sq.mt	5.00		
4.70	Buffet Counter	Providing and fixing Buffet Counters 21'-0" x 2'-6" x 3'-0" as per Design & details ., the car case to be made in 304 Grade (Food Grade) SS sheets and and frame of 1.5" x 1.5" section all around the outer profile to be made in 19mm thk. Comm.ply/ HDHMR Board as base for cladding Composite Stone 15mm thk. with 4 no. SS Electric Sunk-In DISH WARMERS of size 915mm in length.to keep food warmer over a longer period of time shall be provided on the table top fabricated of SS pipe & Sheets. All external visible surface finished with Corian Stone 12mm thk/ Teak Veneer including Polish as/detail. All external visible surface finished with Composite Stone 15mm thk. included 5-6 no. spolt lights COB 5 w in shelevs or LED Strip light as/design. <i>(The work has to be executed on 5th floor or either unit has to be shifted to 5th floor)</i>	No	1.00		
4.80	Re-Installation of Buffet Counter	Shifting and Re-installation of existing Buffet Counter already installed on 5th Floor. The work includes dismantaling of the same and shifting it on Ground floor with the use of chain-pully or mannuanly from staircase. The work also includes repair of any damage if made including, electric SS bain marie, corina stone, Teak Veneer and installation of the same by makinf necessary changes as per design at new location.	Lump sum	1.00		
TOTAL PART B (INTERIOR WORKS)						
GRAND TOTAL PART A + PART B						
		In Words				

Signature of Contractor