

# PRICE BID

BOQ FOR INTERIOR WORK WITH ALLIED WORKS FOR OFFICERS' MESS ON 10TH FLOOR IN SBI, ADMIN. OFFICE, AHMEDABAD AT LAL DARWAJA, (OLD LHO BUILDING) AHMEDABAD.

Sr. No.	Description	Quantity	Unit	Rate	Amount
Note :	Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris , cleaning cutting wastage etc. all taxes, transportation, VAT ,Excise, Octroi etc. Excluding GST complete. [ GST Will be paid as per Applicable at the time of payment of bills]				
	Basic Rate of Items are Excluding GST				
1	P/A POLYMER MORTAR PLASTER	10	SMT		
	Removing the loose plaster & concrete damages surfaces, cleaning the concrete surface with wire brush and reinforcement with rust remover, welding new reinforcement with Existing reinforcement if required applying epoxy resin to concrete & reinforcement surface of approved Brand and covering the surface with average 35 mm th. Polymer mortar using 1 bag cement 3 bag sand 5 lit Nitobond SBR Plus required water including scaffolding for repairing RCC slab, beam complete as directed (Rate including cleaning the site and carting away debris at all levels).				
2	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)	210	SMT		
	Providing and applying (with rollers only) Acrylic emulsion paint of required shed and approved make on new/old work in two or more coats to give an even shed including the preparation of surface for painting, applying FULL primer and putty, at all heights complete as per manufacturer's specification and as directed.				
3	P/F VITRIFIED TILES FLOORING [600mmx1200mm]	200	SMT		
	Providing & fixing 600 x 1200 mm Vitrified tiles flooring of approved make and dark shade for flooring as per design. in CM 1:4 over a cement mortar bedding, Levelling the existing underneath CM bedding & providing cement slurry including light compaction as directed. The rate includes filling the joints of tiles using adhesive & pigments. The rate includes curing acid cleaning, cutting etc. complete. Rate shall be same for all levels. Basic price of Tiles shall be Rs. 600=00 per Sq. Mt (Excluding GST). etc. complete as directed. The rates include removal of existing Flooring up to bedding mortar and Its disposal.No additional sand bedding charges shall be paid for Electric trenches filling				
	Providing and laying 3 mm thick bubble guard of Cello make or equiv. for flooring protection and after completion of other furniture removing the same and carrying away as buy back etc				

Sr. No.	Description	Quantity	Unit	Rate	Amount
4	P/F POLISHED GREEN KOTAH STONE FLOORING	14	SMT		
	Providing and laying polished green kotah stone flooring using one side pre-polished chiesel dressed green kotah stone in uniform shade of size 16"x22" / 22"x22" (thickness of the stone 20 mm to 25 mm) over required thickness of cement mortar 1:6 with flush pointing of joints with cement paste mixed with green pigment colour, machine polishing, with final coat of wax polishing as directed etc. complete.				
5	WOODEN FLOORING	51	SMT		
	Providing and fixing of 8 mm thick Laminated wooden flooring with a surface abrasion resistance of class AC4, with 0.2mm thick wear layer on top of a High Density Fibre substrate core of plank having uniline locking arrangement with an made of Armstrong natural colour foam, with accessories like Skirting, end profile, door profile, transition profile, reducer etc. complete. Make-ARMSTRONG/ AMBIENCE PLUS/ PERGO/VISTA. Length and breadth of superficial areas of the finished work shall be measured for payment. (Basic price Rs/- 330.00/sq.ft.)				
6.0	P/F CERAMIC TILES DADO ON WALL	135	SMT		
	Providing & laying wall dado of 5 to 6 mm thick coloured Glazed tiles(Mat Finish) of 300 x 450 of approved make first quality fixed cover 13mm thick plaster in CM 1:3, including providing groove upto 3mm wide if directed to do so and using grey cement in pointing of joints and applying neat cement paste about 3 Kg/Sq.m. The rate shall be inclusive of centre point fittings i.e. extra labour, material etc. to be considered so as to get outlet of plumbing/sanitary fittings at the junction. Rate shall be same for all levels.Sample of the tiles must be got approved from Architect/Bank.Rate all so includes backing coat of rough cement plaster. Rate includes dismantling of existing tiles and disposal complete as directed. (Basic price of tiles shall be Rs.430=00 Per Sqmt)				
7	P/F FLUSH DOOR SHUTTER WITH BOTH SIDE LAMINATE FINISH WITHOUT FRAME	3.5	SMT		
	Providing & fixing flush door shutter 30 mm thk BWP of Archid/Green Lam/Kit ply/Century or Approved ISI make , Water proof, thermosetting synthetic resin bond solid batten core of blockboard construction with 30 mm thick lipping of first quality teak wood battens on all edges of shutters with both side laminate as per architect's detail, supplying & fixing approved fixtures & fittings such as S.S hinges 4" long,tower bolts 8" long, handles 6" long ,Aldrops 12" Long, as per the details flush shutters are without frame (measurement will be out to out of shutter only). at all levels.[Approx Size 650/750 mmx2050mm				

Sr. No.	Description	Quantity	Unit	Rate	Amount
8	Dismantling Brick wall/ Brick partition wall with or without plaster etc.	1.5	CMT		
9	FALSE CEILING				
	FALSE CEILINGS WITH WPC PANNELS OF SIZE 2950MM (LENGTH)X 195MM (WIDTH) X 27MM(HEIGHT)- Providing and fixing false ceilings with WPC (Wood Polymer Composite) Fluted Panels of size 2950MM (LENGTH)X 195MM (WIDTH) X 27MM(HEIGHT) of LEBEN/ Alutuff / Murrato or other approved make of approved shade in approved pattern as directed by the architect. Rates shall be inclusive of all hardware fittings and fixtures as required to fix the same on ceilings including corner beading and fasteners.	250	SMT		
10	GLASS DOORS AND PARTITIONS				
	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS	6.10	SMT		
	Providing & Fixing fully glazed door includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, ptl pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides,, fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.				
	The patch fittings of approved make shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.				
11	Same as above item but P & F FULLY GLAZED PARTITION With Patch Fitting for fixed partition.	30.00	SMT		
12	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.	18.00	SMT		
	TOTAL AMOUNT				