

<b>PRICE BID</b>					
<b>CIVIL WORKS AT STATE BANK OF INDIA, MAIN BRANCH DASUYA (PB)</b>					
<b>S.No.</b>	<b>Specifications</b>	<b>Qty.</b>	<b>Units</b>	<b>Rate</b>	<b>Amount</b>
<b>1</b>	<b>DISMANTLING &amp; REPAIRWORKS</b>				
1.1	Gypsum False ceiling including frame & disposal of malba, away from site	476	sqm.		
1.2	AC Duct & Indoor machine removal	1	job		
1.3	Dismantling of brick wall 9" thick & disposal of malba, away from site.	12	sqm.		
1.4	Excavation for new 4.5" walls including disposal of debris away from site	6.00	cu.m.		
<b>2</b>	<b>RCC SLAB</b>				
	Providing and laying RCC slab 2.5" thk for kitchen in RCC 1:2:4 including shuttering and steel reinforcement as req.all complete as per direction of Engineer-in-Charge.	2.00	sqm.		
	steel reinforcement 12mm dia @ 6"c/c both way				
2.2	RCC lintel for doors / windows / opening including steel reinforcement and bending & binding of steel, inclusive of shuttering / scaffolding as required, complete in all respects.				
	steel reinforcement Main - 4nos.of 10mm dia, ring of 8mm dia @ 6"c/c				
	4.5"x9" ( for 2'-6" door)	4.00	each		
	9"x9" ( for 2'-6" door)	1.00	each		
2.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, INCLUDING the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).				
	steel reinforcement Main - 4nos.of 12mm dia, ring of 8mm dia @ 6"c/c				
	9"x12"( for 8'-9" opening in FO area & plinth beams)	28.00	mtr.		
<b>3</b>	<b>BRICKWORK</b>				
	Providing & laying brick wall with brick class designated 75 in cement mortar 1:4 (1 cement: 4 coarse sand), including all types of leads/ lift, scaffolding, pads, racking joints,	154.00	sqm.		

	curing, cutting concrete floor before starting work, complete in all respect. In case of half brick wall, MS reinforcement as per CPWD specifications to be provided, i.e. 2 nos. 6mm dia TOR steel bars will be provided at every third course, for which no extra payment will be made.				
<b>4</b>	<b>PCC WORK 1:4:8</b>				
	Providing & laying PCC 1:4:8 (40mm nominal aggregate) in foundation, complete in all respects	1.50	cu.m.		
<b>5</b>	<b>PLASTER WORK (12 TO 15MM THICK CEMENT PLASTER 1:4 )</b>				
	Providing & laying 12mm Cement plaster 1:4 (1cement: 4 fine sand) on brick walls, shelves, ceiling etc, including all types of leads/ lift, scaffolding, pads, racking joints, curing, etc. complete	207.00	sqm.		
<b>6</b>	<b>VITRIFIED TILES</b>				
	Providing and laying 1st quality vitrified tiles (Marble series Double charged- JOHNSON/ KAJARIA/ RAK / SOMANY- as approved by Bank's Engineer/Architect) of following sizes, as per design pattern on floor & skirting with chemical or adhesive/ cement as directed and joints to be filled with grout of approved colour, including dismantling existing floor tiles and disposal of malba from site, cutting wooden/ aluminum doors to match new floor level, preparing of surface & disposal of malba from site.				
	32"X32" Vitrified tiles Double Charged- marble series.	495	sq.m.		
<b>7</b>	<b>ANTI-SKID FLOORING TILES (TOILETS &amp; UPS ROOM)</b>				
	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete. Make: Kajaria, Nitco, Somany, Johnson	49	sq.m.		
<b>8</b>	<b>WALL TILES IN TOILETS / PANTRY</b>				
	Providing and laying 1st quality ceramic glazed tiles of size 12"x24" fixed usin cem. Sand mortar, with groves filled with white cement & matching pigment, complete in all respects Make: Kajaria, Nitco, Somany	132	sq.m.		

<b>9</b>	<b>GRANITE IN TOILETS / PANTRY</b>				
	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.				
	Polished Granite stone slab of all colour and texture except Black, Cherry/Ruby Red	7.00	sq.m.		
<b>10</b>	<b>G.I. PIPES</b>				
	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.				
10.10	15 mm dia nominal bore	100.00	mtr		
10.20	20 mm dia nominal bore	20.00	mtr		
<b>11</b>	<b>SOIL WASTE DRAINAGE PIPE WORK</b>				
	Providing & fixing <b>PVC(SWR) Pipes</b> Type B, heavy class conforming to S13592-1992. (PRINCE / SUPREME / DIPLAST/ ASTRAL), including necessary fittings like bend, offset, collars etc., complete. Rates to include cutting/ chasing walls, floor, fixing pipe & making good the damages with cement mortar AND CONNECTING UPTO TO EXISTING EXTERNAL MANHOLES, complete in all respect.				
11.1	75 mm dia	40.00	mtr		
11.2	100 mm dia	40.00	mtr		
<b>12</b>	<b>CP FITTINGS &amp; ACCESSORIES</b>				
	<i>NOTE: The scope of work shall include removal of old fittings &amp; fixtures wherever applicable. Making chase / holes &amp; repairing them, complet in all respects. No extra payment shall be allowed for any incidental as above.</i>				
12.1	Providing & fixing 15mm dia <u>CP Bib Cock</u> with CP wall flange, complete.	6	nos.		
	MODEL = FLR.5047N of Jaquar or equivalent of Cera /SOMANY				
12.2	<b>Bibcock Long Body:</b> Providing & fixing 15mm dia CP Long Body Bib Cock with CP wall flange, complete.	2	nos.		
	MODEL=CON.107KV of Jaquar or equivalent of Cera				

12.3	Providing & fixing 15mm dia <b>CP Angle valve A</b> with CP wall flange, complete.	20	nos.		
	MODEL = FLR-5053N of JAQUAR or equivalent of Cera / Hidware				
12.4	Providing & fixing 15mm dia <b>CP Pillar cock</b> (JAQUAR FLR-5015), complete.	2	nos.		
	MODEL FLR-5015 of JAQUAR, complete.				
12.5	Providing & fixing 15mm dia <b>CP Pillar cock</b> , auto closing type, complete.	4	nos.		
	MODEL=PRS-031 JAQUAR ,complete.				
12.6	Providing & fixing 15mm dia <b>CONCEALED Valve</b> with CP top cover, complete.	2	nos.		
	MODEL=JAQUAR ALD-083 CQT, UPER (FLR.5083 NK				
12.7	Providing & fixing <b>CP jali</b> (heavy duty) with CP outer ring, complete.	16	nos.		
12.8	Providing & fixing 600x450 mm or as directed, beveled edge mirror 5.5 mm superior glass (ATUL/ SAINT GOBBIN) complete with 6 mm thick hard board ground fixed to wooden cleats & CP brass screws, washers & clips etc. complete.	6	nos.		
12.9	Providing & fixing table top <b>Wash Basin</b> of size 515x415x145mm, including CP waste and CP BOTTLE TRAP, etc complete in all respects	6	nos.		
	MODEL: WHB: CRESPO (Cat No. S2020171) of CERA / equivalent of JAQUAR/SOMANY				
12.10	Providing & fixing <b>urinal</b> 385x325x635 including CP bottle trap, complete in all respects.	4	nos.		
	MODEL=URSWHT-13253N of JAQUAR /equivalent of CERA/SOMANY				
12.11	Providing & fixing <b>wall hung water closet</b> 380x515x360 including soft closing seat cover, anchor fasteners, etc complete as required.	2	nos.		
	MODEL=CNS.WHT.963UFSM of JAQUAR /equivalent of CERA/SOMANY				
12.12	Providing & fixing floor mounted <b>2-piece water closet</b> , with dual flushing system, size 655 x 370 x 770 mm including soft closing seat cover, anchor fasteners, etc complete as required.	4	nos.		
	MODEL=Campbell of CERA (Cat no. Cat. No: S1021109SL) or equivalent of JAQUAR/SOMANY				
12.13	Providing & fixing <b>HEALTH FAUCET/WASHER</b> having Flexible Metal Hose, 8mm dia. & 1.5M long, complete in all respects	6	nos.		

	MODEL=SHA-CHR-549D8 of JAQUAR /equivalent of CERA/SOMANY				
12.14	Providing & fixing Pneumatic Single Piece Slim <b>Concealed Cistern Body</b> on wall, with Installation Kit & "S-Type" drain pipe connection set for Wall Hung WC with Flush Control Plate, Complete in all respects.	2	nos.		
	Model: CISTERN : APCWHT-5012500 of JAQUAR /equivalent of CERA/SOMANY & FLUSH PLATE: JCP-CHR-2415 of JAQUAR /equivalent of CERA/SOMANY				
12.15	Providing & fixing single bowl Stainless Steel <b>Kitchen Sink</b> size 22"x18"x8" including cutting & shaping granite slab & filling the gaps with cement grout with matching color pigment around the edges of Sink, including CP waste & PVC drain pipe.	1	nos.		
	MODEL Flamingo of HINDWARE or equivalent of JAINA/NEELKANTH				
<b>13</b>	<b>PAINT WORK:</b>				
13.1	Interior paint				
	Applying three or more coats of <u>ACRYLIC EMULSION</u> (ASIAN/ NEROLAC) of approved shade including making of ground, rubbing, filling of putty base preparation with BIRLA/ JK Putty, applying a coat of cement primer, complete. In case where the surface has been earlier white/colour washed, the old white/colour wash shall be entirely removed and surface broomed/scrapped down before preparing the surface for applying paint as described above. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	780.00	sq.m.		
<b>14</b>	<b>ENAMEL PAINT</b>				
	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade, Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	41.00	sq.m.		
<b>15</b>	<b>TEXTURE PAINT</b>				
	Providing & applying a coat of RUSTIC textured finish in white color (ASIAN) on walls and columns. The rate shall include scrapping, leveling & preparing the surface with JK/ ASIAN/ BIRLA WHITE putty. Applying 1 coat of texture over a coat of primer & applying 2 or more coats of plastic	52.00	sq.m.		

	emulsion paint of approved shade to give even & uniform surface, including cleaning of floor, surface etc. complete.				
<b>16</b>	<b>FIRE RESISTANT DOOR (UPS ROOM) 3'-0"x7'-0"</b>				
	Providing & fixing Fire resistant door (GMC, Baddi/ Kutty, Paonta), including door frame 100x50x1.2mm GPST steel/ 16SWG GI sheet, duly powder coated, with hold fasts to be embedded in brick wall in cement concrete 1:2:4. Door shutter will be 46mm thick, made of powder coated 0.8mm thick GPST sheet, fire rating of 120 minutes, as per IS 3614 (Part 2). Fire rated wired glass of 300x200 mm size to be provided. Rates include all necessary hardware like pull handle, steel hinges, dead lock, hilt fasteners, complete in all respect.	1.00	no.		
<b>17</b>	<b>ACP CLADDING</b>				
	Providing cutting, bending and fixing of aluminium Composite Panel cladding of approved make / manufacture on external façade of size as shown in drawings at all heights and elevation including necessary frame work, either curved or straight or circular in plan. The aluminium composite panel should consist of 3 mm thick thermoplastic core of anti - oxident LDPE + HDPE ( Virgin Core) sandwiched between two layers 0.5 mm thick aluminium alloy sheet ( alloy grade 3003 of ASTM B-209) making a total panel thickness of 4 mm. The surface finish shall be PVDF coat of 30 micron over a base polyester coat on top and service coat on the reverse with chrome /alkyd of 6 - 7 microns coating shall confirm to ASTM D 2244-93 and ASTM D 523 - 89 for color retention and chalk resistance. ACP shall be fixed on especially designed aluminium frame work with horizontal and vertical members of extruded aluminium made out of AA 6063 T, 6 - 20 microns anodizing shall be done on the aluminium section. The aluminium frame work shall be of 50 x 25 x 1.6 Sheet to be supplied in width of 1220 mm. The color shade and texture of the ACP to be as per the approved Bank color design and pattern.	52.00	sq.m.		
	<i>MAKE: Alstrong, Alex, Aludecor</i>				
	TOTAL (ITEMS 1-17)				
	Amount in Words:				
	GST @ 18% Extra				