

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
<b>Note :</b>	<b>Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills</b>				
<b>[A]</b>	<b>FURNISHING WORK</b>				
<b>1</b>	<b>SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with White corian &amp; blue lacquered glass finishing</b>				
	Supplying, fixing and keeping in position single window counter complete as per Bank's instruction made out of 18 mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.				
	The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit with 18 mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.				
<b>[a]</b>	size :				
	Description:            L            B            Ht.				
	Writing Top            5'-0"            2'-9"            2'-6"				
	4 Drawers with				
	pigeon hole            2'-0"            1'-3"            2'-0"				
	Computer key Board with mouse				
	Supplying and fixing metal key Board of approved make in counter as per design and instructions.				
<b>[b]</b>	Working table top and edges shall be finished with 6 mm thick white corian of DUPONT or equivalent approved make as per Bank's direction with all labour and material.				
<b>[c]</b>	Front Apron : 2 nos 6 mm thick flexy ply wood in round shape with 6 mm thick white corian shall be provided at front as per design. All edges should be finished with corian of DUPONT make.				
<b>[d]</b>	Front pannel shall be finished with 6 mm thick 18" high blue back painted glass of approved make and fixed on 18 mm thick commercial ply wood with Natural Silicon gum as per manufacturer's specification complete.				
<b>[e]</b>	Foot rest of 3" x 1.5" in C.P. Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 16" x 24"				
<b>[f]</b>	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
<b>[g]</b>	All fittings like S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.				
<b>[h]</b>	Heavy duty telescopic full extension sliding channel of approved make shall be used.				
<b>[i]</b>	<b>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete</b>				
<b>[j]</b>	Counter shall be made independent in Length of 5'-0" and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid.				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Table Top : 6 mm thick white corian				
	2) <b>Front Apron:</b> Round corian and 6 mm thick backpainted blue glass fixed with Natural Silicon				
	3) <b>Facing of Drawers:</b> 1.00 mm thick laminate finish				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
1[a]	<b>SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with Matt finish laminate</b>	3.40	RMT		-
	Same as above item No-1 but providing 0.80 mm thick Matt finish superwhite laminate AICA Make-UGM G 324/1324 or equivalent instead of white corian and 1.00 mm thick matt finish sapphire Blue lamiante AICA Make- G 452/1452 instead of blue lacquered glass etc complete as directed				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) <b>Table Top</b> : 0.80 mm thick matt finish laminate				
	2) Front Apron & panel : Round matt finish white laminate and 1.00 mm thick sapphire Blue laminate				
	3) <b>Facing of Drawers:</b> 1.00 mm thick laminate finish				
	4) <b>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate</b>				
1[b]	<b>Providing and fixing 12 mm thick Toughened Glass partition on counter top, front side as follows.</b>	3.40	SQMT		-
	Providing and fixing 12 mm thick Toughened float glass with polished edges to be fixed with necessary S.S Brush finish brackets & support on wooden partition as directed with necessary cut out in glass. All edges of glass shall have Diamond cut polished edges as directed.				
	<b>TABLES</b>				
2	<b>MANAGER TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT. with 3.5 mm thick Teak veneer with PU coating finish on Table Top , sides &amp; Edges and all other visible surfaces etc complete as follows</b>				
	Supplying and installation of Table as per the following description : Size 6'-0" x 2'-9". Table top shall be made from 18 mm thick commercial ply wood with 3.50 mm thick Teak veneer with PU Coating with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the CABINET shall have Teak veneer with PU polish . Foot rest of 1 1/2" x 3" T.W members shall be provided. All internal surface will have 0.60 mm thick balacing laminate				
	<b>Apron (Modesty Panel) made from 18 mm thick ply wood finished with teak veneer PU Finish &amp; groove pattern as directed.</b>				
	<b>Table side made from 18 mm thick ply wood with 3.50 mm thick teak veneer with PU coating finish shall be provided in a pattern as directed. Veneer to be provided on all visible surfaces.</b>				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
	Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing veneer on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed.				
	Table shall have stand for keeping CPU and metallic cable Manager shall be provided in table top. All exposed edges of plywood shall have veneer with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	<b>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.</b>				
	All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade				
	<b>As per instruction of Architect/Bank work to be Completed.</b>				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Table Top : 3.5 mm thick Teak Veneer with PU Coating & Burma Teak beading on Edges with PU Coating				
	2) Front Apron & Sides: 3.5 mm thick Teak Veneer with PU Coating				
	3) Facing of Drawers: 3.5 mm thick Teak Veneer with PU Coating				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
2[d]	Same as above Item no-2, but size 5'-9"x 2'-9" all external surfaces including top to be finished with 1 mm thick Laminate (approved shades)	1.00	NO		-
2[f]	Same as above Item no-2 but Size: 4'-6"x2'-6" with 4 nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	1.00	NO		-
4	<b>GRAHAK MITRA TABLE OF 2'-3" WIDE with PU coating finish</b>				
	Same as above item no 2 but Size 2'-3" wide with storage unit in Table with 4mm thick MDF board + Blue and white PU Coating finishing on all exposed visible surface as per instruction of Architect/Bank For Grahak Mitra/Tech Mitra (Help Desk Table)				
	Table top made from 18 mm thick ply wood + 4mm thick MDF board with PU coating finish				
	Apron (Front side) made from 18 mm thick ply wood + 4mm MDF board with PU Coating finish				
	Both sides made from 18 mm thick ply wood + 4mm MDF board with PU Coating finish				
	3" thick Partition above working table top made from 18 mm thick+6 mm thick ply wood with necessary framing with 4mm thick MDF board + PU Coating finish as directed.				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) <b>Table Top :</b> 18 mm Thick Plywood with 4 mm thick MDF with High gloss white PU Coating				
	2) <b>Front Apron &amp; Sides:</b> 4mm thick MDF with High gloss white/blue PU Coating				
	3) <b>Facing of Drawers:</b> 1.0 mm thick Laminate finish				
4[a]	<b>GRAHAK MITRA TABLE OF 2'-3" WIDE : Same as above but with Laminate finish</b>	1.50	RMT		-
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Table Top : 18 mm Thick Plywood with 1.0 mm thick matt finish super white laminate AICA Make-UGM- G 324/1324 & sapphire Bule laminate G 452/1452				
	2) Front Apron & Sides: 1.0 mm thick high gloss super white laminate AICA Make- UGM- G 324/1324 & sapphire Bule laminate G 452/1452				
	3) <b>Facing of Drawers:</b> 1.0 mm thick Laminate finish				
5	<b>DINING TABLE Approx Size 3'-0"x 3'-0"</b>	1.00	SQ MT		-
	Supplying and installation of Dining Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
6	<b>CUSTOMER WRITING DESK</b>	1.00	NO		-
	Writing Desk Size 4'-0" L x 1'-3" x (0'-6"+3'-0") ht.				
	Verticle Sides and bottom shall be made out of 36 mm (2X18) thick Commercial plywood and back side 12 mm thick ply wood with Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12mm th Toughend glass with polished edges making different divisions by 18 mm thick glass / plywood with laminate on both side for slips or forms as per inststruction complete. Laminate to be provided on all visible surface.				
	<b>SIDE CREDENZA (SIDE TABLE)</b>				
7	<b>Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 3.50 mm thick Teak veneer with PU Coating finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges with PU Coating. Veneer to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. ( For BM) Rate for length Less then 3'-3" length</b>				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
	Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 3.50 mm thick veneer with PU Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with veneer finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate.				
7[b]	<b>SIDE CREDENZA (SIDE TABLE) Same as above Item No-7, but all external surfaces to be finished with 1.0 mm thick Laminate (approved shades). Size shall be 3'-0"/3'-3" x 1'-4" x 2'-6" ht. with openable shutters as directed.</b>	3.19	SQ.MT		-
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) Front Apron & Sides: Frosty White Laminate				
7[e]	<b>SIDE CREDENZA (SIDE TABLE) For S.W Countwer Same as above item No-7 but Side Table Top and edges shall be finished with 6 mmThick White Corian on Top and Edges. All other visible surface shall be finished with 1.00 mm th laminate. Size shall be 3'-0"x 1'-4"x2'-6" ht. With openable shutter as directed</b>	1.52	SQMT		-
7[f]	<b>STORAGE CABINET with Top &amp; Front laminate finished. Storage of any height</b>	6.20	SQMT		-
	Same as above Item No-7, but all external surfaces to be finished with Laminate (approved shades)				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) <b>Front Apron &amp; Sides:</b> Dark Laminate/Frosty white Laminate as per design & instructions				
7[g]	<b>P/F ELECTRIC CUB BOARD</b>	3.70	SQMT		-
	Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
7[h]	<b>P/F PANTRY PLATFORM CUB BOARD SHUTTER</b>	1.65	SQMT		-
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface				
	<b>LOW HEIGHT PARTITION WORK</b>				
8	<b>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR BACK SIDE AND IN BETWEEN S.W COUNTER AND CASH CABIN WITH TOUGHENED GLASS</b>	6.40	SQMT		-
	Providing and fixing low height partition using 50mm x 25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides, fixing 12 mm thick transparent toughened glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed. Laminate to be provided only on visible surface.				
	<b>For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.</b>				
8[a]	<b>PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE</b>	1.55	SQMT		-
	Same as item no 10 but P/F 30 / 32 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Aprroved make Night latch Lock, S.S Handles,Door stoppers, doorstop etc complete as directed.				
8[b]	<b>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS</b>	3.20	SQMT		-
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
	<b>FULL HEIGHT PARTITION WORK</b>				
9	<b>P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR</b>	10.00	SQMT		-
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.				
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.				
10	<b>Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows. (5 NOS)</b>	4.50	SQMT		-
	Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32 x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk S S screws, Approved make Dead Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. All exposed surface /edges not laminated be provided with lacquer polish. Work to be completed as per instructions.				
10[a]	<b>Providing and fixing UPS door shutter with Aluminium Frame and both side Hilux sheet</b>	2.15	SQMT		-
	Providing and fixing door shutter made out of 50x25x1.5mm thick aluminium framing at maximum 1'-6" C/C both way with 8 mm thick Hilux Board on both side with painting. Providing 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading. Steam beach beading of size 31x 12 mm should be placed around shutter edges, aluminium stoper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Dead Lock, S.S Handles, Door stoppers, doorstopper to be fixed as per instructions. All beadings should be polished.				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
10[b]	<b>CASH ROOM DOOR (P/F MS GATE / CASH ROOM DOOR)</b>	70	KG		-
	Providing, fabricating and fixing in position MS gate, of MS sections as per architect's details including cutting welding grinding to smooth surface of all works, anchor bolts, with rail track if required, hinges as per details, fixing and locking arrangements, including painting with two coat of first quality synthetic enamel paint of make J & N ? Shalimar / British / Asian, over a coat of primer etc. complete as directed.				
	2 Nos latches to be provided.				
	Banking hall side door to be finished with 12mm ply and 1 mm laminate with necessary fittings				
	<b>GLASS DOORS AND PARTITIONS</b>				
11	<b>P &amp; F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door For Branch and E-Lobby</b>	7.00	SQMT		-
	Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of <b>12 mm th. Toughened glass</b> with the help of <b>top patch &amp; bottom patch fittings</b> . The door will have patch lock, pti pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, <b>(Ozone Make OGH-55P11-25X400)</b> , fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.				
	The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.				
11[a]	Same as above item but P & F FULLY GLAZED PARTITION With Patch Fitting for front side of Main Entrance [ FIXED PORTION] For Branch and E-Lobby	11.14	SQMT		-
11[b]	<b>PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEPARATING TWO M/C FOR E-LOOBY</b>	1.80	SQMT		-
	P /F 12mm th Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid).				
	<b>PANELLING WORK</b>				
12	<b>P/F Wall panelling with laminate finishing for wall and Pillar etc</b>	30.00	SQMT		-
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .				



**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
12[a]	Providing and fixing 18 mm thick plywood of 4" height with 1.0 mm thick laminate finish runner patta on Storage Top / Table Top if required.etc complete as directed.	5.00	RMT		-
12[c]	Creating Box for fixing AC machine and concealing of copper and drain pipe and around front side main entrance door top, jambs using <b>18 mm thick MR Grade plywood</b> with 1.00 mm Thick Laminate to be fixed over aluminium framing of 25 X 25 X 1.2 mm as per requirement etc complete as directed.	3.00	SQMT		-
12[f]	<b>Panelling for Display wall with 3M Vinyl glossy Film with printed design</b>	5.50	SQMT		-
	Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose.				
	Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width.				
12[g]	<b>Panelling for Digital wall with Blue / white high gloss PU Coating finishing</b>				
	Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only finished visible surface area shall be measured for payment.				
12[h]	<b>Same as above item Panelling for Digital wall but with Blue matt finish 1 mm thick laminate finishing instead of PU paint</b>	2.35	SQMT		-
12[i]	<b>Same as above item, Panelling for Digital wall but using 12mm thick MDF board / 6 mm thick ply without laminate finishing if required for wall paper fixing.</b>	1.70	SQMT		-
12[j]	<b>P/A WALL PAPERS on Digital wall</b>	2.70	SQMT		-
	Providing and applying <b>Wall paper</b> approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
12[k]	ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION for BRANCH AND ATM ROOM IN SIDE WALL AND OUT SIDE	52.00	SQMT		-
	Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. <b>Design as per Bank and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or equivalent</b>				
	<b>FALSE CEILING WORK</b>				
13	<b>P/F GYPSUM BOARD FALSE CEILING</b>	46.00	SMT		-
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of <b>Gypsteel ULTRA (Gypsteel Ultra shall be used)</b> supporting system in line and level. Finishing the surface and <b>applying 3 coats of Plastic emulsion paint</b> as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	<b>After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.</b>				
	<b>Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment.</b>				
13[b]	Same as above but providing and fixing of 8 mm thick MDF board strip with Blue shade high gloss PU Coating instead of Gypsum Board for Item No-1 over Transaction Area etc complete as per design and instruction. Only finished surface area shall be measured for payment.				
13[c]	Same as above but providing and fixing 6 mm thick ply covered with 1 mm thick blue shade laminate	0.65	SMT		-
13[d]	Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid	62.00	SMT		-
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. <b>Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose</b>				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
14	<b>SOFT BOARD</b>	2.00	SQMT		-
	Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed.				
15	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Including GST)	5.00	SQMT		-
15[a]	Supplying and fixing Verticle Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 90=00 Per Sq.Ft Including GST)	7.50	SQMT		-
16	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.	5.00	SQMT		-
18	Providing and fixing "Dorma/Ozone/Godrej " or equivalent make door closure.	7.00	NO		-
18[a]	Providing and fixing "Dorma/Ozone/Godrej " or equivalent make 100 Kg Floor Spring.	3.00	NO		-
19	<b>Supplying and installation 3'-0" x 1'-9"x 1'-3" height Center Tepoy as follows.</b>	2.00	NO		-
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.				
34	<b>PAINTING WORK</b>				
34[a]	<b>P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)</b>	180.00	SMT		-
	Providing and applying (with rollers only) Acrylic emulsion paint of required shade and approved make on old/new surface in two or more coats to give an even shade including the preparation of surface for painting, applying FULL primer and putty at all heights complete as per manufacturer's specification and as directed.				
34[b]	<b>P/A DISTEMPER PAINT</b>	2.00	SMT		-
	Providing and applying distemper paint (water base) of approved make & shade on old/new surface including scrapping/cleaning and preparation of surface for painting, applying cement based primer & FULL putty of approved make. Applying distemper paint in two or more coats to give uniform covering at all heights as directed by Engineer / Architect.				

**PRICE BID OF INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA  
SUBIR BRANCH AT SUBIR SAO-NAVSARI**

Sr. No.	Description	Quantity	Unit	Rate	Amount
34[c]	P/A SYNTHETIC ENAMEL PAINT	40.00	SMT		-
	Providing and applying synthetic enamel paint at all heights of required shade and approved make on new / old work including scrapping / cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.				
34[d]	P/A APEX PAINT	2.00	SMT		-
	Providing and applying Apex paint (Asian Paint Advanced Anti Algal weather proof emulsion) on New/Old surface at all heights and levels. Work includes preparation of surface, cleaning and scraping by wire brush, filling cracks with "Rendroc cs"( fosroc) and applying coat of Hydroproof liquid mixed with white cement. Applying primer coat as per company specifications and applying 2 or more coats of paint to give uniform shade at all levels complete.				
35	<b>P/F VITRIFIED TILES FLOORING [600mmx600mm]</b>	5.00	SMT		-
	Providing & fixing 600 x 600 Vitrified tiles flooring of approved make first quality and shade for flooring as per design. <b>Tiles shall be laid on existing flooring and necessary adhesive of like NITOLITE -GP of FOSROC make shall be used as directed.</b> The rate includes filling the joints of tiles using adhesive & pigments, acid cleaning, cutting etc. complete. Rate shall be same for all levels. <b>Basic price of Tiles shall be Rs. 400=00 per Sq. Mt (Excluding GST).</b> etc. <b>No additional sand bedding charges shall be paid for Electric trenches filling.</b>				
	Providing and laying 3 mm thick bubble guard of Cello make or equiv. for flooring protection and after completion of other furniture work, removing the same and carrying away as advised.				
	<b>Only finished surface area shall be measured for payment</b>				
35[a]	<b>P/F 75MM HEIGHT SKIRTING</b>	2.00	RMT		-
	Providing & laying 75 mm height skirting cut out of vitrified tiles 600mmx600mm of approved make over cement paste after making necessary cutting / hacking in walls, surface preparation as directed complete with joint filling etc. <b>Rate also includes filling of Zaries in skirting complete as directed. The rates include removal of existing skirting &amp; its disposal. Basic price of Tiles shall be Rs. 400=00 per Sq. Mt excluding GST.</b>				
<b>TOTAL COST "A"</b>					-
<b>Note:</b>					
[a]	In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this				
[b]	All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balacing laminate of approved make & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.				