

**PRICE BID FOR AC WORK FOR SPPB BRANCH IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD**

Sr.No.	Description	QTY	UNIT	RATE	AMOUNT
<b>[I]</b>	<b>MACHINE PART</b>				
	<b>AC EQUIPMENT WITH - INVERTER COMPRESSOR</b>				
1	Supply & providing of 4 way Inverter Cassette Type AC ceiling mounted cassette unit with indoor and out door having eco friendly refrigerant. Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have copper condensor Unit, Make: Daikin/ Mitsubishi Heavy Industries / Toshiba				
1.a	Inverter 4-way Cassette of 3.00 TR (BEE 5 Star rating)	5	NOS		
2	Supplying & providing of Hi-wall Inverter Split Type AC with high wall mounted indoor and out door unit. having eco friendly refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall have copper condensor Unit, Make: Carrier/ Hitachi/ Daikin/ Mitsubishi Heavy Industries/ Toshiba/ Trane/ Voltas/ Blue star. [Mini 5 Star rating as per BEE Guide Line 2022]				
2.1	Inverter Hi-wall Split AC of 1.00 TR	1	NOS		
	<b>TOTAL FOR PART- I</b>				-
<b>[II]</b>	<b>LOW SIDE WORK</b>				
3	Installation of IDU & ODU of 4.00 TR / 3.00 TR / 2.00 TR ceiling mounted cassatte unit with first oil & gas charge & commissioning etc. Rate including ceiling mounted suspension Kit etc complete	5	NOS		
4	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including 5.0 Rmt copper tubing and electrical wiring connection etc. complete.	1	NOS		
5	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit of 4.00/3.00/2.00 TR ceiling mounted cassette unit with 4 Sqmm 4 Core copper flexible cable of Finolex / R R Kable/Havells/CEI make. The copper piping shall be insulated with 13mm thick Nitrite rubber insulated of 'O' Class of K Flax/ArmafleX/ Superlon Make	53	RMT		
6	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit beyong 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 2.5 Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/ArmafleX/ Superlon Make (copper pipe concealed in inside wall)	19	RMT		
7	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealed in inside wall)	52	RMT		

**PRICE BID FOR AC WORK FOR SPPB BRANCH IN OLD SBI ZONAL OFFICE AMBAVADI AT AHMEDABAD**

Sr.No.	Description	QTY	UNIT	RATE	AMOUNT
8	Providing of Fabricate and Fixing M.S stand Plateform for keeping outdoor unit of Cassette /Split A/C. with M.S cage for locking of outdoor unit of Cassette/Split A/C. including painting [Drawing should be prepared by the vendor and approved by the Architects]	150	KG		
9	Providing and Fixing M.S Powder coated stand for keeping outdoor unit of Split A/C. ( Redy made)	3	NOS		
10	Misc. civil wok for entire AC work of branch (including jari in wall and jari filling, hole filling with cement mortar and finishing with core cutting putty. This also include removing of flooring tiles and providing drain pipe during shifting of AC and refixing of same color tiles ptoperly) This work is for entire branch air conditioning system.	1	Job		
11	Removing and Re-installation charges for existing 2.00 TR / 1.5 TR / 1.00 TR High wall mounted split A/C at new location including connection servicing & gas filling complete as directed. Shifting Existing Premises including indoor and outdoor etc complete as directed, rates includes removing of AC from existing location, transportation to new location with proper care and fixing at new location with proper cleaning of machines. as per the item no - 6 entire new copper piping.	2	NOS		
	<b>TOTAL FOR PART- II</b>				
	<b>TOTAL ( I + II)</b>				