

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
---------	-------------	----------	-------	------	--------

**Note :** Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage & removing of all existing furniture items and relocating the same as per instruction by bank etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.

**1.0 OFFICER'S TABLES- Size 1500mm x 750mm x 750mm**

Supplying and installation of Table as per the following description and as designed by the Architect:

Table Top: Providing and fixing 19 mm thick IS 303 BWR grade plywood with 1 mm thick laminate with necessary intermediate support. Table top shall be supported by 18 mm thick BWR grade ply wood with plywood framing. The top of the table shall be provided with equal sized 12mm thick toughened glass with polished edges. The top level of the glass shall be 750mm. Apron (Modesty Panel) made from 18mm thick BWR grade plywood finished with 1mm laminate. Table sides, back & intermediate panels (at 500mm from each side) made from 18 mm thick MR ply wood finished with 1mm laminate for exposed surfaces (4 faces) and 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. Drawer / Storage cabinet: Box of 400 X 750 X 720 mm shall be provided using 18 mm thick BWR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick BWR grade plywood. The drawer unit box and individual drawers to be fixed with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles C-type for each drawer. The front ply of the drawers to be overlapping the frame. Computer Keyboard (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest of 38 x 76 MM T.W members shall be provided. All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm ply finish with 1 mm thk. Laminate of size 400 x 375 mm for keeping CPU and PVC cable Manager shall be provided in the cutouts on the tabletop.

All edges to be provided & fixed with teak wood lipping patti finished with melamine polish. All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade.As per drawing and instruction of Architect/Bank, work to be completed.

Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.

Officer table : 1500 x 750 x 750	3.00	Nos
Manager table 1800 x 850 x 750	1.00	No

**4.0 SIDE/ REAR CREDENZA- For officer and clerical staff table**

**A** Low Height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of 750 height and 450mm deep. Outer exposed structure with to be made with 19mm BWR ply as per IS 303 and back side using 8mm BWR grade ply. All shutters to be made from 25 mm thk BWR Ply and shelves to be made with 19 mm thk. BWR ply.

The top portion of the side and rear credenza to be finished with approved veneer and finished with melamine polish. All the other internal and external surfaces to be finished with 1mm laminate of approved shade and All edges to be provide with TW lipping patti finished with melamine polish. Shutters will have concealed handle with wooden groove finished with approved

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
	shade of melamine polish as per drawing, magnetic catchers, self-closing SS hinges, locks (Godrej/ Hettich/Haffele), SS towerbolts etc. All shutters to be made overlapping the frame Only front elevation will be considered for area calculation. As per drawing and instruction of Architect/Bank, work to be Completed Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.				
	Sizes :				
	Officer & S. W. : 3'-0" x 1'-4" x 2'-6" x 7 nos	7.00	Nos		
	Manager : 3'-9" L x 1'-6" w x 1no	1.00	smt		
<b>5.0</b>	<b>STORAGE CUPBOARDS</b>				
<b>A</b>	Providing and placing in position storage cupboard of 450 mm depth, made out of 18 mm thick BWR grade ply. Full Height Cupboard with Laminate Finish: Providing & fixing full Height Storage Cupboard of 2100mm height and 450mm deep. Outer exposed structure with to be made with 19mm BWR ply as per IS 303 and back side using 8mm BWR grade ply.All shutters and shelves to be made with 19 mm thk. BWR plywood. All internal and external surfaces to be finished with 1mm laminate of approved shade and make.All edges of the cupboard should be edge banded using PVC edge banding tape of approved shade.Shutters to be provided with S.S. 200mm handles, magnetic catchers, self-closing SS hinges, locks (Godrej/ Hettich/Haffele), SS tower bolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation. Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.				
	Sizes :				
	Back side S. W. : 15'-5" x 1'-6" x 2'-6" x 1no	8.54	smt		
	Manager cupboard 10'-9"x 1'-6" x 2'-6" x 1no				
	SBI wealth : 10'-7" x 1'-6" x 2'-6" x1 no				
*	<b>ELECTRICAL PANEL FRONT SHUTTER</b> Same specification but Front shutters, top, bottom & sides only Size : 3'-0" x 6'-0" x 1no	1.67	smt		
<b>6.0</b>	<b>WALL/ COLUMN PANELING WITH LAMINATE FINISH.</b>				
	Wall paneling made from 25 x 25 x 1.00 mm thick hollow aluminum sections, over which BWR grade ply of 10 mm shall be fixed and additional 6-8mm ply in layers to create grooves as per the design in the drawing or as directed by Architect, with decorative molding patty on the edges.	17.58	smt		
	Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:-				
	(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.				
	(ii) Panel Finishing:- Providing & fixing 9 mm thick approved make BWR plywood and additional 6-8mm ply in layers to create grooves as per the design to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate, using approved adhesive, in approved pattern & design, including providing grooves, decorative moldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge.				

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
	<p>(iii) Providing approved quality, seasoned, full length, Teak Wood molding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as directed by the Engineer-in-charge at site.</p> <p>(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>(v) Applying 2 or more coats of melamine polish to exposed edges of paneling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</p> <p>(c) Laminate:- Dorby Mica, Greenlam/Century/Archid / Aerolam or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear paneling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.</p> <p>Column size : 1'-4" + 2'-4" + 1'-4" = 5'-0" x 9'-0" x 2 nos  Entrance column : 0'-7" + 1'-1" + 1'-10" = 3'-6" x 9'-0" x 1no  1'-1" + 1'-1" + 1'-10" = 4'-0" x 9'-0" x 1no. 1'-4" + 1'-9" = 3'-1" x 9'-0" x 1no</p>				
<b>7.0</b>	<b>FULLY GLAZED DOOR</b>				
	<p>Providing and fixing position 12 mm fully glazed toughened glass door, single/ double shutter, of approx. size 900/ 1500 x 2100/2400 mm</p> <p>Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to the partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures &amp; hardware.</p> <p>Approved make: DORMA Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Handle - TG DIH600 - 600mm length) or equivalent brand fittings from Hettich / Hafele / as per sample approved by the Bank. Rate should also include providing film as per design/ instructions of Bank.</p> <p>Mode of Measurement: Door opening size shall be measured.</p> <p>Size : Manager chamber front door &amp; SBI wealth Front door  2'-6" x 7'-0" x 2nos</p>	3.25	smt		
<b>8.0</b>	<b>FULL HEIGHT FULLY GLAZED PARTITION WITH 12MM TOUGHENED GLASS UPTO 7' LEVEL WITH SOLID PARTITION ABOVE 7' LEVEL</b>				
	<p>Providing &amp; fixing full height glazed partition with 12mm Toughened glass of approved make up to 7' level height with solid partition above 7'-0" level up to false ceiling bottom.</p> <p>The glazed panels shall be fixed to the existing floor and false ceiling with all necessary SS brackets (D, C or U type)</p>	14.31	smt		

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
	<p>Vertical joints between the glass panels shall be sealed with suitable transparent sealant.</p> <p>The solid partition above 7'-0" level shall be made with aluminium framework of size 63mm X 38.10mm X 1.47 mm (0.780Kg /mtr) box section. The spacing of the Horizontal and Vertical members are approximately 600mm c/c (maximum) and the top of the frame shall be fixed to the RCC slab bottom. The exposed surfaces on both sides of framework are covered with 6mm BWR ply finished with 1.0mm thick laminate as per direction.</p> <p>Providing, placing in position &amp; erecting full height partition in desired shape, framework shall be of 50 x 50 x 1.5 mm thick aluminum square section placed at 500 mm c/c both ways or as directed.</p> <p>Manager front partition : 11'-0" x 9'-0" x 1no, less door : 2'-6" x 7'-0" x 1no SBI wealth front partition : 10'-0" x 9'-0" x 1no, less door : 2'-6" x 7'-0" x 1no.</p>				

**11.0 FULL HEIGHT SOLID / PARTLY GLAZED WOODEN PARTITION WITH BOTH SIDES LAMINATE**

	<p>Providing &amp; fixing in position 70mm thick +/- 2mm solid / opaque partly glazed full height wooden partitions with 1200 mm high glass middle panels finished with laminate on both sides comprising as under:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections not exceeding 600 mm c/c bothways (horizontal and vertical) except in glazed portion of partition, fixed rigidly on floor, wall / column &amp; ceiling. Spacing of frame members may vary to the nearest possible extent as per site conditions.</p> <p>(ii) Plywood skin:- Providing &amp; fixing 12mm thick MDF boards on both sides of the framework.</p> <p>(iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate, on both sides of partitions in approved design &amp; pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approved quality adhesive complete.</p> <p>(iv) Providing and fixing 12mm thick approved make 1200 mm high toughened Glass panels in the middle panels of partitions using second class seasoned teakwood moulding of finished sectional size 75mm x 12/15 mm all-round, complete as per drawing and as directed at site.</p> <p>(iv) Making suitable cutouts/openings/channels for Doors, electrical conduits, cables &amp; switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full-length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural</p> <p>(vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutout etc. complete.</p> <p>(vii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) MDF Board:- Greenply, Century, Samrat or equivalent approved by the Bank.</p> <p>(c) Laminate:- Greenlam/Century/Archid or equivalent approved by the Bank.</p>	22.35	smt		
--	--	-------	-----	--	--

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
	<p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.  Mode of measurement:- Though aluminium frame shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sqm.</p> <p>Partly glazed partition : SBI Wealth side partition : 13'-1" x 8'-0" x 1 no,  Manager chamber side partion : 12'-0" x 8'-0"x 1no  Manager chamber &amp; Cash room between partition with door  3'-10 1/2" x 9'-6" x 1no ( Double shutter Ht. 7'-0" )</p>				
<b>12.0</b>	<p>Providing &amp; Supplying Sofas, Sofa chairs of various types &amp; categories (Single seater, Two seater &amp; Three seater) etc complete as per the manufacturers specifications as mentioned below. The rights to select &amp; approve the sofas &amp; seating shall vest with the clients. The contractor shall submit brochures of manufacturer at the time of quoting for this item etc complete as per layout. The consultants reserve the right to select the sofas in line with the technical specifications envisaged &amp; meeting the specifications standards expected.  (Approved makes: Godrej / Durian / Featherlite)</p>				
<b>A</b>	<b>Single seater sofa</b>				
<b>B</b>	<b>Two seater sofa</b>	2.00	nos		
<b>C</b>	<b>Three seater sofa</b>				
<b>13.0</b>	<p><b>CHAIRS FOR OFFICERS / VISITORS AND MEETING ROOM</b>  Supplying &amp; Installation of Office Chairs</p> <p>a) The seat &amp; back are made of 1.20 cm thick hot-pressed plywood upholstered with fabric and polyurethane foam together with moulded ABS seat &amp; back covers. The back foam should be designed with contoured lumber support for extra comfort having seat size 51x47 cm and back size 48x68cm approx. Overall size of the chair Depth 70 cm x width 70 cm x height 106 - 123.5cm seat ht. -44 - 45 cm. The polyurethane foam should be moulded with density =45 ± 2 kg/m3 and hardness + 20 ± 2 kg on Hampden machine at 25% compression.</p> <p>b) Chair should be provided with a synchro tilt mechanism which should offer features like forward tilt, self-regulating tilt tension + Manual override, 4 position tilt locking and anti-shock back mechanism which prevents the back rest from hitting the user when the lock should be released. The backrest consists of a drop lift mechanism, which can be adjusted in the range of 6.5 cm and can be locked in 5 steps for the better lumbar support.</p> <p>c) Chair should be provided with a gas lift mechanism for height adjustments. The pedestal should be injection moulded in black 30% glass filled nylon. The pedestal should be 60 cm pitch centre dia (70 cm with castors). The twin wheel castors are injection moulded in black nylon. All metal components are epoxy polyester powder coated with dry film thickness of more than 45 microns, salt spray test to withstand more than 1000 hrs, pencil scratch hardness more than 2H, other tests conforming to Class D, IS:6005:1970. Polyurethane arm rest &amp; 5 twin wheel extra smooth castors.</p>				
<b>A</b>	<b>Chair for Officers (Godrej model- DIVA Revolving Mid Back with Fixed Loop Arms)</b>	8.00	nos		
<b>B</b>	<b>Chair for Visitors (Godrej model- DIVA Revolving Mid Back with Fixed Loop Arms)</b>	9.00	nos		
<b>C</b>	<b>Chairs for Meeting Room (Godrej model- DIVA Revolving Mid Back with Fixed Loop Arms) / equivalent approved make of Featherlite / Wipro</b>				

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
---------	-------------	----------	-------	------	--------

**14.0 GYPBOARD FALSE CEILING**

Providing and fixing false ceiling at all height including providing and fixing of frame work made galvanized M.S. sections as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clip made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval.

Fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of Engineer in charge including cost of painting the false ceiling with two coats of acrylic emulsion paint over a cost of putty

12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I)

70.00	smt
-------	-----

:2011 (Board with BIS certification marks) to be used.

**15.0 MINERAL FIBRE GRID TILE CEILING:**

Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc.

40.00	smt
-------	-----

Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
	GI Metal Ceiling Lay in perforated Tegular edge global white colour tiles of size 595x595 mm and 0.5 mm thick with 8 mm drop; made of GI sheet having galvanizing of 100 gms/sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC (Noise Reduction Coefficient ) of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation, and backed with a black Glass fibre acoustical fleece.				
<b>16.0</b>	<b>COVE IN FALSE CEILING</b>				
	Same as Gypsum false ceiling but provding, making and fixing Gypsum cove ( inside height 150 - 200mm and border 75mm ) to hide strip/ cover light in ceiling or to act as pelment for roller blinds on windows or for projectro screen, etc.	20.00	rmt		
<b>17.0</b>	<b>Center Table (3'-0" X 2'-0" Oval / Rectangular)</b>				
	Providing and supplying in position oval or rectangular centre table to be made out of 2" X 2" teak wood frame including 12mm thk clear glass top with bevelled edges including bottom glass shelf with etching etc complete. The rate shall also include SS lining design to the teakwood frames including all the necessary hardware, fittings, fixtures as per manufactursrs specifications complete.	2.00	nos		
<b>18.0</b>	<b>BACK PAINTED GLASS + LOGO Size : 10'-7" x 5'-6"</b>				
a.	<b>Back painted glass (Lacquer Glass) paneling:</b> Providing and fixing in position wooden paneling to column / walls finished with Back painted (Lacquer Glass) comprising as under:- (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed upto 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. (ii) Panel Finishing:- Providing & fixing 9 mm thick approved make BWR plywood to Aluminum framework finished with 8 mm thick approved quality and make back painted Lacquer Glass panels of required size, rigidly fixed using 3M adhesive / double side self-adhesive tape complete as directed by the Engineer-in-charge. (iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards etc., including providing necessary wooden/aluminum section members support at cutouts, providing scaffolding for execution of work at all heights, complete as per drawings and as directed by the Engineer-in-charge at site.	5.41	smt		
b	Logo : Providing and fixing in position with SS studs or as directed laser cut logo as per design made from 18 mm MDF board ( exterior grade ) and finished with enamel paint as directed complete. Logo size : 2'-6" x 2'-6"	1.00	no		
<b>21.0</b>	<b>WOODEN FLOORING + SKIRTING :</b>				
	Providing and placing in position wooden laminate flooring with planks of size not less than 1200 mm x 190mm ( with unlink panels/ tongue-groove locaking arrangement ) having a 0.2 mm thick top abrasive layer followed by decorative layer upon HDF ( high density fiberboard ) substrate over 2 mm thick underlayer of polyurethane foam on 250-micron poluthene sheet over a smooth, flat, hard and free from moisture floor surface complete in all respect with required accessories like end profile, transition profile, reducer 'T' profile etc. and preparation of base including all other incidental works as per direction & satisfaction of architect in charge. Cost of laminate floor	13.50	smt		

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
	accessories, skirting end edge, T- molding Reducer shall have to be added in the cost, wherever required. SBI Wealth size : 13'-0" X 11'-0"				
<b>22.0</b>	<b>Low Height wooden Partitions (LHP) with laminate finish with flap gate</b>				
	Nr. Officer table partition : 8'-0" x 4'-0" x 1no S. W. low ht. partition : 1650 L x 1350 (avg. ) H x 3 nos, 750 x 1200 x 1no, 450 x 1200 x 1no, Flap gate : 750x 1350 x 1no, 850 x 1200 x 1no Providing & fixing in position 70 mm +/- 2mm thick Low height wooden partitions with 450mm high glass panel finished with laminate on both sides comprising as under:-  (i) Total Height of the partitions shall be from 1200 mm to be 1350 mm including 300 to 450 mm high 12 mm clear glass panel as per approved drawing.  (ii) Framing : Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections placed bothways (horizontal and vertical) not exceeding 450 mm c/c rigidly fixed to floor, wall / columns etc including extending end/intermediate vertical members not exceeding 1500 mm c/c for total finished height of LHP. (ii) Skin : Providing & fixing 12 mm thick MDF plywood on both sides of the framework and all-round vertical posts extending up to total height of LHP. (iii) Finishing :- Providing and fixing 1.00mm thick approved quality and shade laminates using approved quality adhesive, over ply as per approved design & pattern including providing grooves as per Architectural drawing and as directed by the Engineer-in-charge. (iv) Glazing :- Providing and fixing 12mm thick approved make clear float glass panels (not exceeding 1.50 m in length) with polished edges on all sides, fixed using suitable CP Brass /SS 'D' brackets placed not exceeding 450mm c/c on horizontal surface of partition and at both ends on vertical posts to rigidly hold the glass panels.  (v) Providing finished section size 70/75 x 8mm thick seasoned second class Teak wood moulding to all exposed edges of partition including applying 2 or more coats of melamine polish / Duco paint including necessary preparatory work for surface preparation with putty, priming coat, sealer coat etc. complete as per sample approved by the Bank.  (vi) Making necessary cutouts for electrical conduits / cables & switchboard etc., including providing additional supports wherever required complete as per drawings and as directed by Engineer.  (vii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. Approved make:- (a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.  (b) MDF: - Greenply, Century, Samrat or equivalent approved by the Bank. (c) Laminate:- Greenlam/Century/Archid or equivalent approved by the Bank. (d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.  (e) Enamel Paint/polish: Asian/Nerolac/Berger or equivalent approved by the Bank. (d) Glass: Saint Gobain, Asahi Float, Modi Guard.	13.15	smt		



**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
---------	-------------	----------	-------	------	--------

**23.0 SINGLE WINDOW COUNTER / CASH COUNTER**

Size : 1500 x 900 x 750 mm x 4 nos

Supplying & fixing single window counter as per design and drawing made out of 18 mm thick IS 303 BWR grade ply wood boxing of approved make, complete with 18 X 6 mm Teak wood beading on all edges wherever required. Tabletop made from 12mm thick ISI 303 BWR-grade flexi ply. The countertop to be finished with 6mm thk. sparkle white Corian sheet with 1.5" Thk. Bull Nose Moulding from inside and Curved Machine polished edge from outside dropped down to form light pelmet on front Apron as per detail drawing. The vertical surface below the apron to be finished with blue

6.00 rmt

lacquered glass. Working table top and edges shall be finished with 6 mm thick sparkle white acrylic solid surface (corian of DUPONT/ Merino/ REHAU or equivalent approved make ) as per drawing and direction with all labour and material. The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit (in place of bottom 2 drawers) made of 18 mm thick MR grade plywood and with approved make multipurpose Auto Lock in drawer and group lock in shelf unit. Inner width of drawer box be 400mm, one side of box is leg panel, upper side of box is table top, back side modesty panel and Bottom of Box is of 18 mm thick ply. 4 Nos drawers shall be 525 mm deep (inner dimension), First (Top) drawer 100mm height (facia) & rest 3 of equal size. Top two drawers shall be Cash drawer having 6 equal compartments for currency notes. Foot rest of 75 mm X 38 mm (3" x 1.5") in Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 400 mm X 375 mm. Key board tray of approved make of size 450 mm X 375 mm to be fixed. All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade. All fittings like 75 mm long S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make. Heavy duty telescopic full extension sliding channel of approved make shall be used in all drawers.

All the internal surface (non-visible surface) shall be provided with 0.80 mm thick balancing laminate of approved shade etc. complete. Counter shall be made independent in Length of 1600 mm and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid.

**FINISHING DETAILS:**

- 1) Table Top: 6 mm thick white acrylic solid surface
- 2) Front Apron: Round 6 mm thick white acrylic solid surface and 6 mm thick blue lacquered glass fixed with Natural Silicon
- 3) Facing of Drawers: 1.00 mm thick laminate finish
- 4) All the internal surface (non-visible surface) shall be provided with 0.80 mm thick balancing laminate

Brief list of make are as under or any equivalent make will be permitted by the Engineer:

MR grade Ply wood ( IS :303) - Green / Century / Anchor / Archid / Mayur / Kit / Samrat / Croma Acrylic solid surface (Corain) - Dupont/ Merino/ REHAU or equivalent approved

Laminate- Green / Formica / Sunmica / Century /Marino / Aica Multipurpose group Lock - Ebco / EG / Godrej Telescopic channels - Ebco / Everite Keyboard tray - Ebco / Hettich / Innofit / Featherlite Auto lock- Ebco / Dorma / Ozone Cable Manager (60mm) - Metal - Ebco or equivalent Adhesive- Fevicol / Pedilite / Araldite / Royal Bond

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
24	<p><b>PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS PARTITION ON COUNTER TOP, FRONT SIDE AS FOLLOWS.</b></p> <p>Providing and fixing 12 mm thick Toughened float glass with polished edges to be fixed with necessary S.S Brush finish brackets &amp; support on wooden partition as directed with necessary cut out in glass. Two cutouts to be made one half round of 150mm dia and another for mouth piece rectangular size of 75mm wide 450mm long. All edges of glass shall have Diamond cut polished edges as directed.</p> <p>Brief list of make are as under or any equivalent make will be permitted by the Engineer. Glass- Asaahi/ Tata / Modi guard / Saint gobain Square bracket (50 mm x 12.5 mm ) S S finish - Oswal / Riddhi / Swift or equivalent Size : 1500 x 750 x 3 nos</p>	3.37	smt		
25	<p><b>PROVIDING AND FIXING 12 MM THICK TOUGHENED FLOAT GLASS PARTITION TOWARDS FRONT SIDE OF SINGLE WINDOW COUNTERS TOWARDS PUBLIC SPACE AS FOLLOWS.</b></p> <p>12 mm thick Toughened clear float glass of required shape with bevelled edges on top portion shall be fixed with SS brackets with flat back on wooden partition and counter top as directed. All edges of glass shall be Diamond cut polished edges as directed complete. Maximum length and height will be measured for payment purpose. Brief list of makes are as under or any equivalent make will be permitted by the Engineer. Glass- Asaahi/ Tata / Modi guard / Saint gobain Square / D bracket S S finish of required size - Oswal / Riddhi / Swift or equivalent approved make Size : 1131 x 300 x 4 nos</p>	1.36	smt		
28.0	<p><b>Acrylic Emulsion Paint on old wall surfaces</b></p> <p>Preparing earlier treated surface by scraping, rubbing with sand paper, applying two coats of Birla white putty wherever required, to level the surface, and its rubbing with sand paper, to ensure smooth surface, suitable to receive paint and then applying 2 or more coats of approved colour and shade of Acrylic Emulsion Paint with low VOC content over a coat of approved primer complete as per manufacturers' specifications to internal walls/ceiling including necessary scaffolding etc. complete. Make:- Asian / Berger/ICI or approved equivalent make.</p>	290.00	smt		
30.0	<p><b>Polyester Film over glazed partitions:</b></p> <p>Providing and fixing in position high impact resistant Polyester Films of approved design &amp; pattern, which once installed on glass, give additional strength to glass, reduce glare &amp; prevent glass from splintering on impact. thickness not less than 4 Mil (100 mic.) or 7 Mil (175 mic.) Size : 3.23 x 0.950 x 1no, 3.28 x 0.950 x 1no.</p>	6.18	smt		

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

Sr. No.	Description	Quantity	Unite	Rate	Amount
<b>ADDITIONAL ITEMS</b>					
<b>1.0</b>	<b>GLASS DOORS AND PARTITIONS FOR MAIN ENTERANCE</b>				
A	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance of Branch  Removing the existing glass door & partition, staking them aside and providing & Fixing fully glazed main door at the main entrance. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, pti pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, (Ozone Make OGH-55P11-25X400), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.  The patch fittings (Ozone make) shall be of aluminium with s. s. matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.  Branch door : 6'-0" x 7'-0" x 1no. Double shutters	3.90	smt		
<b>2.0</b>	<b>CUSTOMER WRITING DESK</b>				
	Writing Desk Size 3'-0" L x 1'-3" x (0'-6"+3'-0") ht. Verticle Sides and bottom shall be made out of 19mm thick IS 303 BWR plywood and back side 12 mm thick BWR ply wood with Laminate on Top and Edges on all sides including inside divisions. Top and vertical sides of the divisions shall be made from 12mm th Thoughend glass with polished edges for slips or forms as per detail drawing and instruction complete. (Drawing as enclosed herewith) Laminate to be provided on all visible ply wood surfaces. Including front side openable shutters with s. s. hinges, godreg lock ect. complete.	1.00	no		
<b>3.0</b>	<b>P/A SYNTHETIC ENAMEL PAINT</b>	25.00	smt		
	Providing and applying synthetic enamel paint at all heights of required shade and approved make on new / old work including scrapping / cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.  Rolling shutter : 6'-0 x 7'-0" x 2nos x 1.10 times Collapsible gate : 6'-0" x 7'-0" x 1 no x 1.50 time all over Strong room door : 4'-0" x 7'-0" x2 nos x 1.50 times				
<b>CIVIL WORK :</b>					
<b>1</b>	Dismantling Brick partition wall located behind manager table. Size : 10'-0" x 9'-6" x 1no, 0'-9" x 9'-6" x 1no	9.50	smt		

**BOQ FOR PROPOSED FURNISHING WORK AT OFF S. G. HIGHWAY SBI EMERALD BRANCH, AHMEDABAD.**

<b>Sr. No.</b>	<b>Description</b>	<b>Quantity</b>	<b>Unite</b>	<b>Rate</b>	<b>Amount</b>
----------------	--------------------	-----------------	--------------	-------------	---------------

<b>2</b>	<b>P/F VITRIFIED TILES FLOORING [600mmx600mm]</b>	5.00	smt		
----------	---	------	-----	--	--

Providing & fixing 600 x 600 Vitrified tiles flooring of approved make and shade for flooring as per design. in CM 1:4 over a cement mortar bedding, .Levelling the existing underneath CM bedding & providing cement slurry including light compaction as directed. The rate includes filling the joints of tiles using adhesive & pigments. The rate includes curing acid cleaning, cutting etc. complete. Rate shall be same for all levels. Basic price of Tiles shall be Rs. 500=00 per Sq. Mt (Excluding GST). etc. complete as directed. The rates include removal of existing Flooring up to bedding mortar. Its disposalal .No additional sand bedding charges shall be paid for Electric trenches filling.

Providing and laying 3 mm thick bubble guard of Cello make or equiv. for flooring protection and after completion of other furniture removing the same and carrying away as buy back etc.

10'-0" x 2'-0" x 1no, 6'-0" x 2'-0" x 1no ( Nr. Present server room )

Rs

**Note:**

- [a] In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabelling and No extra amount shall be paid for this.
- [b] All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balancing laminate of aproved make & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.