5.N	Schedule of Quantities for Air-conditioning work of SBI ACB Bina Branch (01427) Under RBO-6 Sagar					
(A)	Description of items AIR CONDITIONING	Qty	Unit	Unit Rate	Amount	
<u>(A)</u>	Supply, installation, testing and commissioning of following AIR CONDIRIONERS as under. The Rate shall be inclusive of all taxes excluding GST. GST will be paid additionally by the Bank as applicable subject to GST					
	Number. and system has complete one year warranty & If any additinal warranty provided by company/vendor in any specific part like compressor etc that is acceptable, please mentioned it.					
1	Supply, installation, testing and commissioning of Higher Efficient models of CASSETTE TYPE AIR CONDITIONERS (Two) 2.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 220 /415 Volts + 10 %, three Phase, 50 Hz AC supply with Rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. The copper piping, drains piping and electrical cabling should be fixed with clamps		Nos			
2	Supply, installation, testing and commissioning of Higher Efficient models of CASSETTE TYPE AIR CONDITIONERS (Three) 3.0 Ton Machines, confirming to latest Indian Standards and suitable for operation on 415 Volts + 10 %, three Phase, 50 Hz AC supply with Rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. The copper piping, drains piping and electrical cabling should be fixed with clamps .	7	Nos			
3	Supply and installation of hard & prime quality of min. 22 G Copper pipe for "Cassette AC Only" with class "o" Nitrile insulation of minimum 12 mm for 3 / 4 ton cassette type air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement.(If required additionally, payment will made as per actual installtion.) The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:- Superlon/Aflex/Armacell/Kflex . Make of cable:Finolex/RR	190	Mtr			
4	Drain Pipe (If Required additional) Applicale to both ACs (Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. (If required additionally, payment will made as per actual installtion.) Make:-Kasta/supreme	120	Mtr			
5	Supplying and drawing of control cum transmission cable of size 4 core X 2.5 sqmm PVC insulated copper conductor cable in the suitable PVC conduit for		R Mtr.			
6	connections from I/D Unit to O/D unit complete as reqd. Providing & fixing of Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work and minor civil work as per site requirement.	8	No			
7	Deinstallation of Existing split & Cassate AC , piping etc. complete and deposit store as directed by Bank's officials	13	Nos			
8	TOTAL(Excluding GST)					

Amount (in words)	Onlv