

**N.O.W. - FURNISHING OF STATE BANK OF INDIA**

**ARKI BRANCH**

**PRICE BID FOR THE CIVIL WORKS.**

<b>S.No.</b>	<b>DSR REF.</b>	<b>Item</b>	<b>Quantity</b>	<b>Units</b>	<b>Rate</b>	<b>Amount</b>
<b>1</b>		<b><u>VITRIFIED TILE FLOORING 600MM X 1200MM</u></b>				
	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm with 3mm thick groves all around including grouting the joints with epoxy of matching pigments etc., complete. (Italian Marble Shade Digital Tiles from Johnson and Johnson, Kajaria, Somany etc)	<b>229.51</b>	<b>SQM</b>		
	11.41.2	Size 600mm x 1200mm				
		<b>NOTE: THE COST SHALL INCLUDE ANY KIND OF REQUIRED ADDITIONAL CONCRETE/CEMENT MORTAR OR FILLING. NO EXTRA COST SHALL BE PAID FOR ANY ADDITIONAL WORKS FOR LEVELING THE SURAFCE FOR NEW TILING WORKS.</b>				
		<b>MAKES:</b>				
		<b>VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				

<b>2</b>		<b><u>VITRIFIED TILE FLOORING 400MM X 400MM</u></b>				
	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. (PAVER ANTISKID ROUGH TEXTURE 12MM THCIK Tiles from Johnson and Johnson, Kajaria, Somany etc)	<b>13.29</b>	<b>SQM</b>		
	11.41.2	Size 400mm x 400mm				
		<b>MAKES:</b>				
		<b>VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				
<b>3</b>		<b><u>EXCAVATION</u></b>				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge.				
	2.6.1	All kinds of soil	<b>2.85</b>	<b>CUM</b>		
<b>4</b>		<b><u>HALF BRICK MASONARY</u></b>				
	6.12	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure :				

	6.12.2	cement mortar 1:4 (1 cement : 4 coarse sand)	<b>10.64</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>BRICKS: FIRST CLASS BRICKS</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				

<b>5</b>		<b><u>FULL BRICK MASONARY</u></b>				
	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and superstructure above plinth level up to floor V level and in foundations (including the cost of back-filling as required) in all shapes and sizes in :				
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	<b>1.10</b>	<b>cu.m</b>		
		<b>MAKES:</b>				
		<b>BRICKS: FIRST CLASS BRICKS</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				
<b>6</b>		<b><u>PLASTERING</u></b>				
	13.1	12 mm cement plaster of mix :				
	13.1.1	1:4 (1 cement: 4 fine sand)	<b>29.72</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				
<b>7</b>	13.2	15 mm cement plaster on the rough side of single or half brick wall of mix :				
	13.2.1	1:4 (1 cement: 4 fine sand)	<b>29.72</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				

<b>8</b>		<b><u>WALL/FLOOR TILES</u></b>				
	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. SIZE 1'0" X 2'0"	<b>37.73</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				
<b>9</b>	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	<b>6.88</b>	<b>SQM</b>		
		<b>MAKES:</b>				
		<b>VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.</b>				
		<b>CEMENT: ULTRATECH/ACC/AMBUJA</b>				
<b>10</b>		<b><u>PUBLIC HEALTH</u></b>				

	17.78	Providing and fixing white vitreous china single body (cistern and seat attached) with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete.	2.00	NO.		
		<b>MAKES:</b>				
		<b>WC : KEROVIT/HINDWARE/CERA</b>				
		<b>KEROVIT KUPA- KS709</b>				

<b>11</b>	NS	Providing and fixing UPVC pipes 6kg pressure for soil and waste water pipes with required specials like bends/tees/union etc. Including making the base and covering the same with cement concrete 1:3:6 as per the direction of the engineer-in-charge.				
		75mm dia pipes	<b>10.67</b>	<b>M</b>		
		<b>NOTE: THE COST SHALL INCLUDE THE COST OF THE EXCAVATION</b>				
		<b>MAKES:</b>				
		<b>UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT</b>				
<b>12</b>	NS	100mm dia pipes	<b>15.24</b>	<b>M</b>		
		<b>NOTE: THE COST SHALL INCLUDE THE COST OF THE EXCAVATION</b>				
		<b>MAKES:</b>				
		<b>UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT</b>				
<b>13</b>	NS	Providing and fixing vitreous china wash basin with pedestal including the CP waste complete with required brackets/rawl plugs etc.	<b>2.00</b>	<b>EACH</b>		
		<b>MAKES:</b>				
		<b>WC : KEROVIT/HINDWARE/CERA</b>				
		<b>KEROVIT CASINO- KS283</b>				
<b>14</b>	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including PVC. waste fittings complete.				
	17.28.1	Semi rigid pipe				
	17.28.1.1	32 mm dia	<b>3.00</b>	<b>EACH</b>		

<b>15</b>	18.11	Providing & Fixing CPVC pipes complete with fittings and clamps including making good the walls etc. concealed pipe including jointing with the chemical/adhesive, cutting chases and making good the wall:				
	18.11.1	25 mm dia nominal bore	<b>36.59</b>	<b>RM</b>		
		<b>MAKES:</b>				
		<b>UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT</b>				



<b>16</b>	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
	18.53.1	15 mm nominal bore	<b>13.00</b>	<b>EACH</b>		
		<b>MAKES:</b>				
		<b>WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT</b>				
		<b>KEROVIT HYDRUS PLUS</b>				
<b>17</b>	NS	Providing and fixing C. P. Brass Center Hole Mixture/ SINK MIXTURE of approved quality conforming to IS:8931	<b>2.00</b>	<b>EACH</b>		
		<b>MAKES:</b>				
		<b>WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT</b>				
		<b>KEROVIT HYDRUS PLUS</b>				
<b>18</b>	NS	Providing and fixing the CP Brass connections for the connections from angle valve to the wash basin mixture. The pipe shall have brass ends complete with rubber gaskets etc.	<b>13.00</b>	<b>EACH</b>		
<b>19</b>	NS	Providing and fixing 100mm dia. Floor traps complete with the CP. Brass grating both normal grating and grating below the wash basins with and hole for the waste pipe.	<b>7.00</b>	<b>EACH</b>		
		<b>MAKES:</b>				
		<b>FLOOR TRAP : SUPREME/ASTRAL/PRINCE OR EQUIVALENT</b>				
		<b>JALI: 304A STAINLESS STEEL</b>				

20	NS	providing and fixing of complete CP brass accessories set for toilets (towel rail, hand towel rail, paper holder, tooth paste stand, soap dishes for wb's and bathing area etc) as per the direction of the Architect.	2.00	EACH		
21	NS	Providing and fixing the CP brass hand Jet for ablution complete with the PVC connection etc.	2.00	EACH		
		<b>MAKES:</b>				
		<b>WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT</b>				
22	18.5	Providing and fixing C.P. brass bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.				
	18.50.1	15 mm nominal bore	2.00	EACH		
		<b>MAKES:</b>				
		<b>WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT</b>				
		<b>KEROVIT HYDRUS PLUS</b>				
23		Providing and fixing urinal in the Gent's toilet with complete fittings and hardware. The cost shall include providing and fixing of one ceramic partition also. (of approved make)	1.00	EACH		
		<b>MAKES:</b>				
		<b>WC : KEROVIT/HINDWARE/CERA</b>				
		<b>KEROVIT ARUSA- KO512W</b>				
24	NS	Providing and fixing handmade stainless steel sink with sink mixture and all accessories including the cost of cutting of the granite/slab/tiles. Single Bowl 230 mm deep.	1.00	EACH		
		<b>MAKES:</b>				

		<b>SINK: NIRALI, KOHLER, AMERICAN STANDARD</b>				
		<b>NIRALI ELOR SMALL</b>				
25	NS	Providing and fixing Black Granite for the counters/outer verandahs /flooring/skirting etc including the cost of providing single moulding and polishing the same. The cost shall also include the cost of making the sub-base and fixing the granite with neat cement slurry and filling the joints with grout of desired shade as per the direction of the Engineer-in-charge.	8.46	SQ.M		
26	4.1.5	1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	2.19	CU.M		
27	NS	Providing and laying RCC slab with mix 1:1.5:3 (one cement: 1.5 sand: 3 aggregate) for the Kitchen Platform 3" thick including the cost of shuttering <b>AND</b> reinforcement and any other sundries required. The work shall also include keeping the provisions for the sink as per the required size	2.04	SQ.M		
		The steel reinforcement shall be 10mm dia bars @ 5"c/c bothways.				
28	NS	Providing and laying RCC lintel for the doors of 150/230mm x 150mm in RCC with mix 1:1.5:3 (one cement: 1.5 sand: 3 aggregate) including cost of 5-12mm dia bars and rings of 8mm dia placed @ 5"c/c. The work shall include the cost of required shuttering or any other sundries.	1.37	RM		

29	NS	Dismantling the existing walls/rcc/floor/ and other civil items etc. complete, providing the required supports in terms of steel girders/rcc beams and making good the surfaces damaged or as per the direction of the engineer-in-charge. The work shall also include removal of the same to an appropriate location as permissible to the local authorities or as per the direction of the Engineer in-charge. (Note: The amount is expected after deduction of amount to be deducted for the buyback of the existing furniture)	1.00	LS		
30	NS	<b><u>Plastic Emulsion paint</u></b>				
		Providing and applying Plastic Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including applying 2 coat of P.O.P to give a smooth surface, complete in all respects (Colour to approval) applicable to old or new.	250.00	SQ.M		
		<b>MAKES:</b>				
		<b>PAINTS : ASIAN/NEROLAC/DULUX/BERGER</b>				

<b>31</b>	NS	<b><u>External Emulsion paint</u></b>				
		Providing and applying External Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including one primer coat, complete in all respects (Colour to approval) applicable to old or new.	<b>200.00</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>PAINTS : ASIAN/NEROLAC/DULUX/BERGER</b>				
<b>32</b>		<b><u>FLUSH DOORS</u></b>				
		providing and fixing of partly glazed wooden door shutters using 32 mm readymade ISI flush door shutter with 1.0mm thick laminate of desired shade/textures and gloss as per drawing with teak wood frame of 150mm x 62.5mm. The door shall have 6mm thick teak wood lipping all around the edges. The door shall have vision panels with 8mm thick clear float glass with etching fixed with double 14mmx25mm thick teak wood moulding as per design. The exposed surface of wood shall be deco painted in desired shade. The door shall be complete in all respect with hardware handles, godrej 6-lever lock/night latch lock, door stoppers, 8" tower bolts, hinges etc all in brass.	<b>12.69</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>FLUSH DOOR: CENTURY/GREEN/DURO OR EQUIVALENT</b>				
		<b>MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT</b>				
		<b>ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT</b>				
		<b>GLASS: SAIN GOBAIN/MODI GLASS/ASAHI FLOAT GLASS</b>				

		<b>LIPPING/MOULDING: CP TEAK FIRST CLASS</b>				
		<b>HARDWARE: OZONE/DORMA/GODREJ</b>				

<b>33</b>		<b><u>ACP BASE/FRAME LED ACRYLIC SIGNAGE</u></b>				
		providing and fixing acrylic signage made with router cutting or moulding of a- cast acrylic in desired colour as per logo design with the thickness of letter or logo atleast 3" thick. The base made with MS sheet powder coated or with ACP sheet and as per requirement special vinyl pasting on the logo. The complete signage with backlit water proof and heavy duty LED lighting including provision for easy repairs after installation complete.	<b>4.65</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>ACP: ALSTONE/ALUDECOR/EUROBOND OR EQUIVALENT</b>				
<b>34</b>		<b><u>TEXTURE PAINT:- ( Spectrum Finish )</u></b>				
		Providing & applying spectrum surface texture finish of approved shade & colour on walls as per requirement & manufacturers recommendations.	<b>40.00</b>	<b>SQ.M</b>		
		<b>MAKES:</b>				
		<b>TEXTURE PAINT: SPECTRUM/ASIAN/ALTEC OR EQUIVALENT</b>				
<b>35</b>		<b><u>DAMP PROOF COURSE</u></b>				
		Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 12.5mm nominal size derived from natural sources)	<b>2.09</b>	<b>SQM</b>		
		<b>Total Value of Works</b>				
		<b>NOTE: GST SHALL BE PAID EXTRA</b>				